

Appendix B

Engineering Design, Cost Estimates, and Cost Risk Analysis

Brazos Island Harbor, Texas Channel Improvement Project Cameron County, Texas

**U.S. Army Corps of Engineers, Galveston District
2000 Fort Point Road
Galveston, Texas 77550**

December 2013

P2-370840 - BRAZOS ISLAND HARBOR, TEXAS CHANNEL IMPROVEMENT PROJECT FEASIBILITY STUDY

LOCATION AND DESCRIPTION:

Port of Brownsville is located on the south Texas coast near the border of U.S. and Mexico. The study area encompasses the entire Brownsville Ship Channel and surrounding region. The entrance channel is located offshore of Cameron County, Texas, in the Gulf of Mexico, and ends at Port of Brownsville Main Harbor. Brownsville Ship Channel provides deep draft access from the Gulf of Mexico through a jetty entrance channel to Brownsville, and a side channel, authorized to 36-feet, and a shallow draft Fishing Boat Harbor near Port Isabel. The primary purpose of the study is navigation, which consists of enlarging the existing Brownsville Ship Channel by deepening the entrance channel, jetty channel, the lower section of the main channel, the upper section of the main channel, and turning basin.

The MII is developed using October 2013 price levels and the latest labor rates for Galveston District. The estimate is divided into seven (7) contracts. Each contract is organized in accordance with a work breakdown structure. Midpoint dates for the construction contracts are developed in conjunction with the project manager for developing the fully-funded costs. The estimate is prepared in accordance with ER 1110-2-1302 Civil Works Cost Engineering, dated 15 Sep 08. The costs are escalated in accordance with the above Engineering Regulation and EM 1110-2-1304 Civil Works Construction Cost Index System (CWCCIS), dated 31 Mar 2013. All data is input into the Total Project Cost Sheet (TPCS).

Marine fuel price is averaged, locked in at \$3.30/gallon (October 2013). Diesel fuel price is locked in at \$4.00/gallon (October 2013). There are no impacts to utilities anticipated. There are no Hazardous, Toxic, and Radioactive Wastes anticipated. The Operation and Maintenance estimate is dated October 2013, with an effective pricing date of October 2013. A formal Cost Risk Analyses is performed with the cooperation of the PDT and Cost Engineering Directory of Expertise (DX) of the Walla Walla District (October 2013). The risks are quantified and a cost risk model developed to determine a contingency at 80% Confidence Level (CL). The new contingencies along with the updated estimates are used to revise the TPCS. An ATR Certification of Cost Estimate is provided by Walla Walla District.

CONTRACT 01:

This contract is for hopper dredging -17+000 to 00+000 and delivery to New Work Ocean Dredged Material Placement Area (offshore). The stationing listed is located on the Gulf of Mexico side of the jetties (entrance channel) and is unsuitable for a pipeline dredge due to wave action. The approximate duration is seven (7) months.

CONTRACT 02:

This contract is for dike raising and rehabilitation of Placement Area 4B and Placement Area 5A. The approximate duration is 15 months.

CONTRACT 03:

This contract is for dike raising and rehabilitation of Placement Area 7 and Placement Area 8. The approximate duration is seven (7) months. In addition, this contract is for pipeline dredging 70+000 to 82+000 and 82+000 to 89+500 and delivery to Placement Area 7 and Placement Area 8, respectively. The stationing listed is located in the upper section of the main channel and turning basin. The approximate duration is 10 months. The approximate duration of the total contract is 13 months as dike raising and rehabilitation can occur, in some instances, concurrently with pipeline dredging.

CONTRACT 04:

This contract is for pipeline dredging 25+000 to 50+000 and delivery to Placement Area 5A. The stationing listed is located in the middle section of the main channel. The approximate duration is 16 months.

CONTRACT 05:

This contract is for dike raising and rehabilitation of Placement Area 2. The approximate duration is three (3) months. In addition, this contract is for pipeline dredging 00+000 to 07+000 and delivery to Placement Area 2. The stationing listed is located in the lower section of the main channel near the jetties (entrance channel). The approximate duration is three (3) months.

CONTRACT 06:

This contract is for pipeline dredging 07+000 to 25+000 and delivery to Placement Area 4B. The stationing listed is located in the middle section of the main channel. The approximate duration is 11 months.

CONTRACT 07:

This contract is for dike raising and rehabilitation of Placement Area 5B. The approximate duration is three (3) months. In addition, this contract is for pipeline dredging 50+000 to 70+000 and delivery to Placement Area 5B. The stationing listed is located in the upper section of the main channel near the turning basin. The approximate duration is nine (9) months.

ACCOUNT CODE 12 - NAVIGATION PORTS AND HARBORS:

Dredge quantities are developed by SWG, Engineering Division, General Engineering (EC-EG). One (1) large hopper dredge is to be used for Contract 01 with offshore placement (with an option for the Contractor to bid Contract 05 as pump-out to PA 2 based on durations and schedules). The remainder of the channel is to be dredged with 30" pipeline dredges, with the material discharged into various, existing placement areas located along the waterway (PA 2, 4B, 5A, 5B, 7, and 8). Dredging costs are developed using Cost Engineering Dredge Estimating Program (CEDEP). Dredge production rates and losses are reduced to account for Resident Management System (RMS) historical effective working times and stiffer "new work" materials. Cost for mobilization and demobilization are developed using CEDEP, assuming the dredges are based in New Orleans, Louisiana. Dredge estimates are based on standard operation practices for the Galveston District, which assume conventional contracting practices of large business IFBs. For estimation purposes and contractor capabilities (derived from current Sabine-Neches Waterway dredging project, which includes four pipeline dredges working simultaneously), no more than three (3) dredges will be underway at any given time. In addition, dredges will be located no less than one (1) mile apart due to Coast Guard regulations; for estimate purposes, the dredges have been strategically spaced at stations so as not to impede dredging workflow.

The cost for Sea Turtle Protection is associated with hopper dredging and includes: 1) cost for two (2) trawlers per hopper; 2) a sea turtle protection device fitted to the hopper; and 3) 24-hour monitoring survey.

The cost for raising placement areas is included under this code of account. Part of the cost for raising a placement area includes clearing, grubbing, and stripping the area; seeding the outside of the dikes is not considered. Labor rates and overhead costs are adjusted to reflect Galveston District, Region 6. The placement area dikes are built using 3-CY dragline buckets, with an optimal production rate of 125-CY/HR, respectively. A total of three (3) draglines are working at the same time. For estimate purposes, dike works are lumped by perimeter and training dikes, locations, and bucket sizes. Articulated concrete block is to be placed approximately 22+000 to 34+000. Production assumed at 50-CY/HR in addition to transport of material from Central Texas via railcars, then trucks, then barges, and finally to the site. Material characteristics are provided by SWG, Engineering Division, Geotechnical and Structural Section (EC-ES).

ACCOUNT CODE 30 - ENGINEERING AND DESIGN:

The cost for this account are developed using the guidelines provided in the TPCS, with the agreement of the cost engineer and the project manager.

ACCOUNT CODE 31 - CONSTRUCTION MANAGEMENT:

The cost for this account are developed using the guidelines provided in the TPCS, with the agreement of the cost engineer and the project manager.

--- NEW WORK ---
P2-370840 - BRAZOS ISLAND HARBOR, TEXAS, CHANNEL IMPROVEMENT PROJECT
FEASIBILITY STUDY
OCTOBER 2013 PRICE LEVELS
CONTRACT CALENDAR

| CONTRACT | DESCRIPTION | DURATION (month) | DESIGN MIDPOINT | START DATE | MIDPOINT | END DATE |
|----------|----------------------------------|------------------|-----------------|------------|----------|----------|
| 1 | Dredge: ODMDS | 7 | Oct-16 | Oct-17 | Jan-18 | Apr-18 |
| 2 | Dike: PA 5A, PA 4B | 15 | Oct-16 | Oct-17 | May-18 | Dec-18 |
| 3 | Dike: PA 8, PA 7 Dredge: 8, 7 | 13 | Oct-16 | Oct-17 | Apr-18 | Oct-18 |
| 4 | Dredge: 5A | 16 | Feb-17 | Feb-18 | Sep-18 | May-19 |
| 5 | Dike: PA 2 Dredge: 2 | 6 | Feb-17 | Feb-18 | May-18 | Jul-18 |
| 6 | Dredge: 4B | 11 | Jan-18 | Jan-19 | Jun-19 | Nov-19 |
| 7 | Dike: 5B Dredge: 5B | 12 | Mar-18 | Mar-19 | Aug-19 | Feb-20 |

Print Date Wed 30 October 2013
Eff. Date 10/10/2013

U.S. Army Corps of Engineers
Project : P2-370840 - BRAZOS ISLAND HARBOR, TEXAS CHANNEL IMPROVEMENT PROJECT
Standard Corps Reports
FEASIBILITY STUDY
OCTOBER 2013 PRICE LEVELS

Time 07:38:12

Title Page

Estimated by USACE SWG EC PS

Designed by USACE SWG EC

Prepared by USACE SWG EC PS

Preparation Date 10/10/2013

Effective Date of Pricing 10/10/2013

Estimated Construction Time 812 Days

This report is not copyrighted, but the information contained herein is For Official Use Only.

Project Direct Summary.....1

1 CONTRACT 011

 1.1 NON-FED/FED COSTS1

 1.1.1 NAVIGATION PORTS AND HARBORS1

2 CONTRACT 021

 2.1 NON-FED/FED COSTS1

 2.1.1 NAVIGATION PORTS AND HARBORS1

3 CONTRACT 031

 3.1 NON-FED/FED COSTS1

 3.1.1 NAVIGATION PORTS AND HARBORS1

4 CONTRACT 041

 4.1 NON-FED/FED COSTS1

 4.1.1 NAVIGATION PORTS AND HARBORS1

5 CONTRACT 051

 5.1 NON-FED/FED COSTS1

 5.1.1 NAVIGATION PORTS AND HARBORS1

6 CONTRACT 061

 6.1 NON-FED/FED COSTS1

 6.1.1 NAVIGATION PORTS AND HARBORS1

7 CONTRACT 071

 7.1 NON-FED/FED COSTS1

 7.1.1 NAVIGATION PORTS AND HARBORS1

Print Date Wed 30 October 2013
Eff. Date 10/10/2013

U.S. Army Corps of Engineers
Project : P2-370840 - BRAZOS ISLAND HARBOR, TEXAS CHANNEL IMPROVEMENT PROJECT
Standard Corps Reports

Time 07:38:12

Table of Contents

Standard Corps Reports

| Description | Quantity | UOM | ContractorOwnCost | Contingency | Escalation | ProjectCost |
|------------------------------------|----------|-----|-------------------|-------------|------------|-------------|
| Project Direct Summary | | | 175,228,790 | 0 | 0 | 180,386,373 |
| 1 CONTRACT 01 | 1.0 | LS | 13,925,247 | 0 | 0 | 13,994,091 |
| 1.1 NON-FED/FED COSTS | 1.0 | LS | 13,925,247 | 0 | 0 | 13,994,091 |
| 1.1.1 NAVIGATION PORTS AND HARBORS | 1.0 | LS | 13,925,247 | 0 | 0 | 13,994,091 |
| 2 CONTRACT 02 | 1.0 | LS | 45,772,091 | 0 | 0 | 48,391,056 |
| 2.1 NON-FED/FED COSTS | 1.0 | LS | 45,772,091 | 0 | 0 | 48,391,056 |
| 2.1.1 NAVIGATION PORTS AND HARBORS | 1.0 | LS | 45,772,091 | 0 | 0 | 48,391,056 |
| 3 CONTRACT 03 | 1.0 | LS | 20,485,895 | 0 | 0 | 21,779,880 |
| 3.1 NON-FED/FED COSTS | 1.0 | LS | 20,485,895 | 0 | 0 | 21,779,880 |
| 3.1.1 NAVIGATION PORTS AND HARBORS | 1.0 | LS | 20,485,895 | 0 | 0 | 21,779,880 |
| 4 CONTRACT 04 | 1.0 | LS | 37,210,494 | 0 | 0 | 37,210,494 |
| 4.1 NON-FED/FED COSTS | 1.0 | LS | 37,210,494 | 0 | 0 | 37,210,494 |
| 4.1.1 NAVIGATION PORTS AND HARBORS | 1.0 | LS | 37,210,494 | 0 | 0 | 37,210,494 |
| 5 CONTRACT 05 | 1.0 | LS | 7,077,543 | 0 | 0 | 7,619,017 |
| 5.1 NON-FED/FED COSTS | 1.0 | LS | 7,077,543 | 0 | 0 | 7,619,017 |
| 5.1.1 NAVIGATION PORTS AND HARBORS | 1.0 | LS | 7,077,543 | 0 | 0 | 7,619,017 |
| 6 CONTRACT 06 | 1.0 | LS | 29,307,250 | 0 | 0 | 29,307,250 |
| 6.1 NON-FED/FED COSTS | 1.0 | LS | 29,307,250 | 0 | 0 | 29,307,250 |
| 6.1.1 NAVIGATION PORTS AND HARBORS | 1.0 | LS | 29,307,250 | 0 | 0 | 29,307,250 |
| 7 CONTRACT 07 | 1.0 | LS | 21,450,271 | 0 | 0 | 22,084,585 |
| 7.1 NON-FED/FED COSTS | 1.0 | LS | 21,450,271 | 0 | 0 | 22,084,585 |
| 7.1.1 NAVIGATION PORTS AND HARBORS | 1.0 | LS | 21,450,271 | 0 | 0 | 22,084,585 |

**** TOTAL PROJECT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
LOCATION: Cameron County, Texas

DISTRICT: SWG Galveston District
POC: CHIEF, COST ENGINEERING, Willie Honza
PREPARED: 10/9/2013

This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | |
|--------------------------------------|---|--------------------|--------------------|------------------|---------------------|---|--------------------|---------------------|---------------------------------------|-----------------------------------|--------------------|--------------------|--------------------|
| WBS NUMBER A | Civil Works Feature & Sub-Feature Description B | COST (\$K) C | CNTG (\$K) D | CNTG (%) E | TOTAL (\$K) F | Program Year (Budget EC): 2016 | | TOTAL (\$K) J | Spent Thru: 1-Oct-13 (\$K) K | L | COST (\$K) M | CNTG (\$K) N | FULL (\$K) O |
| | | | | | | ESC (%) G | COST (\$K) H | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | |
| 12 | non-Federal | \$95,019 | \$19,004 | 20% | \$114,023 | 1.9% | \$96,871 | \$19,374 | \$116,245 | \$0 | \$103,900 | \$20,780 | \$124,679 |
| 12 | Federal | \$85,367 | \$17,073 | 20% | \$102,441 | 2.0% | \$87,098 | \$17,420 | \$104,517 | \$0 | \$93,627 | \$18,725 | \$112,352 |
| CONSTRUCTION ESTIMATE TOTALS: | | \$180,386 | \$36,077 | | \$216,464 | 2.0% | \$183,968 | \$36,794 | \$220,762 | \$0 | \$197,526 | \$39,505 | \$237,032 |
| 01 | LANDS AND DAMAGES | | | | | | | | | | | | |
| 01 | non-Federal | \$4 | \$1 | 25% | \$5 | 3.8% | \$4 | \$1 | \$5 | \$0 | \$4 | \$1 | \$5 |
| 01 | Federal | \$9 | \$2 | 25% | \$11 | 3.8% | \$9 | \$2 | \$12 | \$0 | \$10 | \$2 | \$12 |
| 22 | FEASIBILITY STUDY (non-CAP) | | | | | | | | | \$0 | \$0 | \$0 | \$0 |
| | non-Federal | | | | | | | | | \$0 | \$0 | \$0 | \$0 |
| | Federal | | | | | | | | | \$0 | \$0 | \$0 | \$0 |
| 30 | PLANNING, ENGINEERING & DESIGN | \$18,039 | \$3,608 | 20% | \$21,647 | 4.0% | \$18,760 | \$3,752 | \$22,512 | \$0 | \$20,874 | \$4,175 | \$25,049 |
| 31 | CONSTRUCTION MANAGEMENT | \$10,824 | \$2,165 | 20% | \$12,989 | 2.1% | \$11,046 | \$2,209 | \$13,255 | \$0 | \$11,859 | \$2,372 | \$14,231 |
| PROJECT COST TOTALS: | | \$209,262 | \$41,853 | 20% | \$251,115 | | \$213,788 | \$42,758 | \$256,546 | \$0 | \$230,274 | \$46,055 | \$276,329 |

- Mandatory by Regulation** CHIEF, COST ENGINEERING, Willie Honza
- Mandatory by Regulation** PROJECT MANAGER, Byron Williams
- Mandatory by Regulation** CHIEF, REAL ESTATE, Orlando Rosas
- CHIEF, PLANNING, Dolan Dunn
- CHIEF, ENGINEERING, Joe King
- CHIEF, OPERATIONS, Joe Hrametz
- CHIEF, CONSTRUCTION, Don Carelock
- CHIEF, CONTRACTING, Curtis Cole
- CHIEF, PM-PB, Valerie Miller

ESTIMATED FEDERAL COST: **\$151,632**
ESTIMATED NON-FEDERAL COST: **\$124,679**
ESTIMATED TOTAL PROJECT COST: \$276,312

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
 LOCATION: Cameron County, Texas
 This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

DISTRICT: SWG Galveston District
 POC: CHIEF, COST ENGINEERING, Willie Honza
 PREPARED: 10/9/2013

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|------------------------------|---------|-----------------------------------|----------|---|----------|--------------------------------------|----------|-----------------------------------|----------|----------|---------|----------|
| | | Estimate Prepared: 10/9/2013 | | Effective Price Level: 1-Oct-2013 | | Program Year (Budget EC): 2016 | | Effective Price Level Date: 1 OCT 15 | | FULLY FUNDED PROJECT ESTIMATE | | | | |
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | COST | CNTG | CNTG | TOTAL | ESC | COST | CNTG | TOTAL | Mid-Point | INFLATED | COST | CNTG | FULL |
| | | (\$K) | (\$K) | (%) | (\$K) | (%) | (\$K) | (\$K) | (\$K) | (\$K) | Date | (%) | (\$K) | (\$K) |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| PHASE 1 or CONTRACT 1 | | | | | | | | | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | | |
| 12 | non-Federal | \$5,570 | \$1,114 | 20% | \$6,684 | 3.8% | \$5,780 | \$1,156 | \$6,936 | 2018Q2 | 4.3% | \$6,030 | \$1,206 | \$7,236 |
| 12 | Federal | \$8,334 | \$1,667 | 20% | \$10,001 | 3.8% | \$8,649 | \$1,730 | \$10,378 | 2018Q2 | 4.3% | \$9,023 | \$1,805 | \$10,828 |
| 12 | Navigation Aids (Federal) | \$90 | \$18 | 20% | \$108 | 3.8% | \$93 | \$19 | \$112 | 2018Q3 | 4.8% | \$98 | \$20 | \$117 |
| | | | | | | | \$0 | | | | | | | |
| CONSTRUCTION ESTIMATE TOTALS: | | \$13,994 | \$2,799 | 20% | \$16,793 | | \$14,522 | \$2,904 | \$17,426 | | | \$15,151 | \$3,030 | \$18,182 |
| 01 | LANDS AND DAMAGES | | | | | | | | | | | | | |
| 01 | non-Federal | \$4 | \$1 | 25% | \$5 | 3.8% | \$4 | \$1 | \$5 | 2017Q1 | 1.9% | \$4 | \$1 | \$5 |
| 01 | Federal | \$9 | \$2 | 25% | \$11 | 3.8% | \$9 | \$2 | \$12 | 2017Q1 | 1.9% | \$10 | \$2 | \$12 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 0.5% | Project Management | \$70 | \$14 | 20% | \$84 | 8.0% | \$76 | \$15 | \$91 | 2017Q1 | 4.3% | \$79 | \$16 | \$95 |
| 1.0% | Planning & Environmental Compliance | \$140 | \$28 | 20% | \$168 | 8.0% | \$151 | \$30 | \$181 | 2017Q1 | 4.3% | \$158 | \$32 | \$189 |
| 5.0% | Engineering & Design | \$700 | \$140 | 20% | \$840 | 8.0% | \$756 | \$151 | \$907 | 2017Q1 | 4.3% | \$788 | \$158 | \$946 |
| 0.7% | Reviews, ATRs, IEPRs, VE | \$98 | \$20 | 20% | \$118 | 8.0% | \$106 | \$21 | \$127 | 2017Q1 | 4.3% | \$110 | \$22 | \$132 |
| 0.5% | Life Cycle Updates (cost, schedule, risks) | \$70 | \$14 | 20% | \$84 | 8.0% | \$76 | \$15 | \$91 | 2017Q1 | 4.3% | \$79 | \$16 | \$95 |
| 0.8% | Contracting & Reprographics | \$112 | \$22 | 20% | \$134 | 8.0% | \$121 | \$24 | \$145 | 2017Q1 | 4.3% | \$126 | \$25 | \$151 |
| 1.5% | Engineering During Construction | \$210 | \$42 | 20% | \$252 | 8.0% | \$227 | \$45 | \$272 | 2018Q2 | 9.9% | \$249 | \$50 | \$299 |
| 0.0% | Planning During Construction | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 0.0% | Project Operations | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 5.0% | Construction Management | \$700 | \$140 | 20% | \$840 | 3.8% | \$727 | \$145 | \$872 | 2018Q2 | 4.3% | \$758 | \$152 | \$910 |
| 0.5% | Project Operation: | \$70 | \$14 | 20% | \$84 | 3.8% | \$73 | \$15 | \$87 | 2018Q2 | 4.3% | \$76 | \$15 | \$91 |
| 0.5% | Project Management | \$70 | \$14 | 20% | \$84 | 3.8% | \$73 | \$15 | \$87 | 2018Q2 | 4.3% | \$76 | \$15 | \$91 |
| CONTRACT COST TOTALS: | | \$16,247 | \$3,250 | | \$19,497 | | \$16,920 | \$3,385 | \$20,304 | | | \$17,665 | \$3,534 | \$21,198 |

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
 LOCATION: Cameron County, Texas
 This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

DISTRICT: SWG Galveston District PREPARED: 10/9/2013
 POC: CHIEF, COST ENGINEERING, Willie Honza

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|------------------------------|---------------|-----------------------------------|----------------|---|---------------|--------------------------------------|----------------|-----------------------------------|-----------------|---------------|---------------|---------------|
| | | Estimate Prepared: 10/9/2013 | | Effective Price Level: 1-Oct-2013 | | Program Year (Budget EC): 2016 | | Effective Price Level Date: 1 OCT 15 | | FULLY FUNDED PROJECT ESTIMATE | | | | |
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | Mid-Point Date | INFLATED (%) | COST (\$K) | CNTG (\$K) | FULL (\$K) |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| PHASE 2 or CONTRACT 2 | | | | | | | | | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | | |
| 12 | non-Federal | \$2,285 | \$457 | 20% | \$2,742 | 1.8% | \$2,327 | \$465 | \$2,793 | 2018Q3 | 6.8% | \$2,486 | \$497 | \$2,983 |
| 12 | Federal | \$6,856 | \$1,371 | 20% | \$8,227 | 1.8% | \$6,982 | \$1,396 | \$8,378 | 2018Q3 | 6.8% | \$7,458 | \$1,492 | \$8,949 |
| 12 | Associated Costs (non-Federal) | \$39,250 | \$7,850 | 20% | \$47,100 | 1.8% | \$39,971 | \$7,994 | \$47,965 | 2018Q3 | 6.8% | \$42,697 | \$8,539 | \$51,236 |
| | | | | | | | \$0 | | | | | | | |
| CONSTRUCTION ESTIMATE TOTALS: | | \$48,391 | \$9,678 | 20% | \$58,069 | | \$49,279 | \$9,856 | \$59,135 | | | \$52,641 | \$10,528 | \$63,169 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 0.5% | Project Management | \$242 | \$48 | 20% | \$290 | 3.7% | \$251 | \$50 | \$301 | 2017Q1 | 8.7% | \$273 | \$55 | \$327 |
| 1.0% | Planning & Environmental Compliance | \$484 | \$97 | 20% | \$581 | 3.7% | \$502 | \$100 | \$602 | 2017Q1 | 8.7% | \$545 | \$109 | \$654 |
| 5.0% | Engineering & Design | \$2,420 | \$484 | 20% | \$2,904 | 3.7% | \$2,509 | \$502 | \$3,010 | 2017Q1 | 8.7% | \$2,726 | \$545 | \$3,271 |
| 0.7% | Reviews, ATRs, IEPs, VE | \$339 | \$68 | 20% | \$407 | 3.7% | \$351 | \$70 | \$422 | 2017Q1 | 8.7% | \$382 | \$76 | \$458 |
| 0.5% | Life Cycle Updates (cost, schedule, risks) | \$242 | \$48 | 20% | \$290 | 3.7% | \$251 | \$50 | \$301 | 2017Q1 | 8.7% | \$273 | \$55 | \$327 |
| 0.8% | Contracting & Reprographics | \$387 | \$77 | 20% | \$464 | 3.7% | \$401 | \$80 | \$481 | 2017Q1 | 8.7% | \$436 | \$87 | \$523 |
| 1.5% | Engineering During Construction | \$726 | \$145 | 20% | \$871 | 3.7% | \$753 | \$151 | \$903 | 2018Q3 | 15.7% | \$871 | \$174 | \$1,045 |
| 0.0% | Planning During Construction | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 0.0% | Project Operations | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 5.0% | Construction Management | \$2,420 | \$484 | 20% | \$2,904 | 1.9% | \$2,466 | \$493 | \$2,959 | 2018Q3 | 6.8% | \$2,634 | \$527 | \$3,161 |
| 0.5% | Project Operation: | \$242 | \$48 | 20% | \$290 | 1.9% | \$247 | \$49 | \$296 | 2018Q3 | 6.8% | \$263 | \$53 | \$316 |
| 0.5% | Project Management | \$242 | \$48 | 20% | \$290 | 1.9% | \$247 | \$49 | \$296 | 2018Q3 | 6.8% | \$263 | \$53 | \$316 |
| CONTRACT COST TOTALS: | | \$56,135 | \$11,227 | | \$67,362 | | \$57,256 | \$11,451 | \$68,707 | | | \$61,306 | \$12,261 | \$73,568 |

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
 LOCATION: Cameron County, Texas
 This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

DISTRICT: SWG Galveston District PREPARED: 10/9/2013
 POC: CHIEF, COST ENGINEERING, Willie Honza

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|------------------------------|---------------|-----------------------------------|----------------|---|---------------|--------------------------------------|----------------|-----------------------------------|-----------------|---------------|---------------|---------------|
| | | Estimate Prepared: 10/9/2013 | | Effective Price Level: 1-Oct-2013 | | Program Year (Budget EC): 2016 | | Effective Price Level Date: 1 OCT 15 | | FULLY FUNDED PROJECT ESTIMATE | | | | |
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | Mid-Point Date | INFLATED (%) | COST (\$K) | CNTG (\$K) | FULL (\$K) |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| PHASE 3 or CONTRACT 3 | | | | | | | | | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | | |
| 12 | non-Federal | \$8,317 | \$1,663 | 20% | \$9,981 | 1.8% | \$8,470 | \$1,694 | \$10,164 | 2018Q3 | 6.8% | \$9,048 | \$1,810 | \$10,857 |
| 12 | Federal | \$13,463 | \$2,693 | 20% | \$16,155 | 1.8% | \$13,710 | \$2,742 | \$16,452 | 2018Q3 | 6.8% | \$14,645 | \$2,929 | \$17,574 |
| | | | | | | | \$0 | | | | | | | |
| CONSTRUCTION ESTIMATE TOTALS: | | \$21,780 | \$4,356 | 20% | \$26,136 | | \$22,180 | \$4,436 | \$26,616 | | | \$23,693 | \$4,739 | \$28,431 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 0.5% | Project Management | \$109 | \$22 | 20% | \$131 | 3.7% | \$113 | \$23 | \$136 | 2017Q1 | 8.7% | \$123 | \$25 | \$147 |
| 1.0% | Planning & Environmental Compliance | \$218 | \$44 | 20% | \$262 | 3.7% | \$226 | \$45 | \$271 | 2017Q1 | 8.7% | \$246 | \$49 | \$295 |
| 5.0% | Engineering & Design | \$1,089 | \$218 | 20% | \$1,307 | 3.7% | \$1,129 | \$226 | \$1,355 | 2017Q1 | 8.7% | \$1,227 | \$245 | \$1,472 |
| 0.7% | Reviews, ATRs, IEPRs, VE | \$152 | \$30 | 20% | \$182 | 3.7% | \$158 | \$32 | \$189 | 2017Q1 | 8.7% | \$171 | \$34 | \$205 |
| 0.5% | Life Cycle Updates (cost, schedule, risks) | \$109 | \$22 | 20% | \$131 | 3.7% | \$113 | \$23 | \$136 | 2017Q1 | 8.7% | \$123 | \$25 | \$147 |
| 0.8% | Contracting & Reprographics | \$174 | \$35 | 20% | \$209 | 3.7% | \$180 | \$36 | \$216 | 2017Q1 | 8.7% | \$196 | \$39 | \$235 |
| 1.5% | Engineering During Construction | \$327 | \$65 | 20% | \$392 | 3.7% | \$339 | \$68 | \$407 | 2018Q3 | 15.7% | \$392 | \$78 | \$471 |
| 0.0% | Planning During Construction | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 0.0% | Project Operations | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 5.0% | Construction Management | \$1,089 | \$218 | 20% | \$1,307 | 1.9% | \$1,110 | \$222 | \$1,332 | 2018Q3 | 6.8% | \$1,185 | \$237 | \$1,422 |
| 0.5% | Project Operation: | \$109 | \$22 | 20% | \$131 | 1.9% | \$111 | \$22 | \$133 | 2018Q3 | 6.8% | \$119 | \$24 | \$142 |
| 0.5% | Project Management | \$109 | \$22 | 20% | \$131 | 1.9% | \$111 | \$22 | \$133 | 2018Q3 | 6.8% | \$119 | \$24 | \$142 |
| CONTRACT COST TOTALS: | | \$25,265 | \$5,053 | | \$30,318 | | \$25,769 | \$5,154 | \$30,923 | | | \$27,592 | \$5,518 | \$33,111 |

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
 LOCATION: Cameron County, Texas
 This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

DISTRICT: SWG Galveston District PREPARED: 10/9/2013
 POC: CHIEF, COST ENGINEERING, Willie Honza

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|------------------------------|---------------|-----------------------------------|----------------|---|---------------|--------------------------------------|----------------|-----------------------------------|-----------------|---------------|---------------|---------------|
| | | Estimate Prepared: 10/9/2013 | | Effective Price Level: 1-Oct-2013 | | Program Year (Budget EC): 2016 | | Effective Price Level Date: 1 OCT 15 | | FULLY FUNDED PROJECT ESTIMATE | | | | |
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | Mid-Point Date | INFLATED (%) | COST (\$K) | CNTG (\$K) | FULL (\$K) |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| PHASE 4 or CONTRACT 4 | | | | | | | | | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | | |
| 12 | non-Federal | \$15,667 | \$3,133 | 20% | \$18,801 | 1.8% | \$15,955 | \$3,191 | \$19,146 | 2018Q4 | 7.3% | \$17,124 | \$3,425 | \$20,549 |
| 12 | Federal | \$21,543 | \$4,309 | 20% | \$25,852 | 1.8% | \$21,939 | \$4,388 | \$26,326 | 2018Q4 | 7.3% | \$23,546 | \$4,709 | \$28,255 |
| | | | | | | | \$0 | | | | | | | |
| CONSTRUCTION ESTIMATE TOTALS: | | \$37,210 | \$7,442 | 20% | \$44,653 | | \$37,894 | \$7,579 | \$45,472 | | | \$40,670 | \$8,134 | \$48,804 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 0.5% | Project Management | \$186 | \$37 | 20% | \$223 | 3.7% | \$193 | \$39 | \$231 | 2017Q2 | 9.8% | \$212 | \$42 | \$254 |
| 1.0% | Planning & Environmental Compliance | \$372 | \$74 | 20% | \$446 | 3.7% | \$386 | \$77 | \$463 | 2017Q2 | 9.8% | \$423 | \$85 | \$508 |
| 5.0% | Engineering & Design | \$1,861 | \$372 | 20% | \$2,233 | 3.7% | \$1,929 | \$386 | \$2,315 | 2017Q2 | 9.8% | \$2,118 | \$424 | \$2,541 |
| 0.7% | Reviews, ATRs, IEPRs, VE | \$260 | \$52 | 20% | \$312 | 3.7% | \$270 | \$54 | \$323 | 2017Q2 | 9.8% | \$296 | \$59 | \$355 |
| 0.5% | Life Cycle Updates (cost, schedule, risks) | \$186 | \$37 | 20% | \$223 | 3.7% | \$193 | \$39 | \$231 | 2017Q2 | 9.8% | \$212 | \$42 | \$254 |
| 0.8% | Contracting & Reprographics | \$298 | \$60 | 20% | \$358 | 3.7% | \$309 | \$62 | \$371 | 2017Q2 | 9.8% | \$339 | \$68 | \$407 |
| 1.5% | Engineering During Construction | \$558 | \$112 | 20% | \$670 | 3.7% | \$578 | \$116 | \$694 | 2018Q4 | 17.0% | \$677 | \$135 | \$812 |
| 0.0% | Planning During Construction | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 0.0% | Project Operations | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 5.0% | Construction Management | \$1,861 | \$372 | 20% | \$2,233 | 1.9% | \$1,896 | \$379 | \$2,276 | 2018Q4 | 7.3% | \$2,035 | \$407 | \$2,442 |
| 0.5% | Project Operation: | \$186 | \$37 | 20% | \$223 | 1.9% | \$190 | \$38 | \$227 | 2018Q4 | 7.3% | \$203 | \$41 | \$244 |
| 0.5% | Project Management | \$186 | \$37 | 20% | \$223 | 1.9% | \$190 | \$38 | \$227 | 2018Q4 | 7.3% | \$203 | \$41 | \$244 |
| CONTRACT COST TOTALS: | | \$43,164 | \$8,633 | | \$51,797 | | \$44,026 | \$8,805 | \$52,831 | | | \$47,388 | \$9,478 | \$56,866 |

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
 LOCATION: Cameron County, Texas
 This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

DISTRICT: SWG Galveston District PREPARED: 10/9/2013
 POC: CHIEF, COST ENGINEERING, Willie Honza

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|------------------------------|---------------|-----------------------------------|----------------|---|---------------|--------------------------------------|----------------|-----------------------------------|-----------------|---------------|---------------|---------------|
| | | Estimate Prepared: 10/9/2013 | | Effective Price Level: 1-Oct-2013 | | Program Year (Budget EC): 2016 | | Effective Price Level Date: 1 OCT 15 | | FULLY FUNDED PROJECT ESTIMATE | | | | |
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | Mid-Point Date | INFLATED (%) | COST (\$K) | CNTG (\$K) | FULL (\$K) |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| PHASE 5 or CONTRACT 5 | | | | | | | | | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | | |
| 12 | non-Federal | \$2,769 | \$554 | 20% | \$3,323 | 1.8% | \$2,820 | \$564 | \$3,384 | 2018Q3 | 6.8% | \$3,012 | \$602 | \$3,615 |
| 12 | Federal | \$4,850 | \$970 | 20% | \$5,820 | 1.8% | \$4,939 | \$988 | \$5,927 | 2018Q3 | 6.8% | \$5,276 | \$1,055 | \$6,331 |
| | | | | | | | \$0 | | | | | | | |
| CONSTRUCTION ESTIMATE TOTALS: | | \$7,619 | \$1,524 | 20% | \$9,143 | | \$7,759 | \$1,552 | \$9,311 | | | \$8,288 | \$1,658 | \$9,946 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 0.5% | Project Management | \$38 | \$8 | 20% | \$46 | 3.7% | \$39 | \$8 | \$47 | 2017Q2 | 9.8% | \$43 | \$9 | \$52 |
| 1.0% | Planning & Environmental Compliance | \$76 | \$15 | 20% | \$91 | 3.7% | \$79 | \$16 | \$95 | 2017Q2 | 9.8% | \$86 | \$17 | \$104 |
| 5.0% | Engineering & Design | \$381 | \$76 | 20% | \$457 | 3.7% | \$395 | \$79 | \$474 | 2017Q2 | 9.8% | \$434 | \$87 | \$520 |
| 0.7% | Reviews, ATRs, IEPRs, VE | \$53 | \$11 | 20% | \$64 | 3.7% | \$55 | \$11 | \$66 | 2017Q2 | 9.8% | \$60 | \$12 | \$72 |
| 0.5% | Life Cycle Updates (cost, schedule, risks) | \$38 | \$8 | 20% | \$46 | 3.7% | \$39 | \$8 | \$47 | 2017Q2 | 9.8% | \$43 | \$9 | \$52 |
| 0.8% | Contracting & Reprographics | \$61 | \$12 | 20% | \$73 | 3.7% | \$63 | \$13 | \$76 | 2017Q2 | 9.8% | \$69 | \$14 | \$83 |
| 1.5% | Engineering During Construction | \$114 | \$23 | 20% | \$137 | 3.7% | \$118 | \$24 | \$142 | 2018Q3 | 15.7% | \$137 | \$27 | \$164 |
| 0.0% | Planning During Construction | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 0.0% | Project Operations | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 5.0% | Construction Management | \$381 | \$76 | 20% | \$457 | 1.9% | \$388 | \$78 | \$466 | 2018Q3 | 6.8% | \$415 | \$83 | \$498 |
| 0.5% | Project Operation: | \$38 | \$8 | 20% | \$46 | 1.9% | \$39 | \$8 | \$46 | 2018Q3 | 6.8% | \$41 | \$8 | \$50 |
| 0.5% | Project Management | \$38 | \$8 | 20% | \$46 | 1.9% | \$39 | \$8 | \$46 | 2018Q3 | 6.8% | \$41 | \$8 | \$50 |
| CONTRACT COST TOTALS: | | \$8,837 | \$1,767 | | \$10,604 | | \$9,013 | \$1,803 | \$10,816 | | | \$9,659 | \$1,932 | \$11,590 |

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
 LOCATION: Cameron County, Texas
 This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

DISTRICT: SWG Galveston District
 POC: CHIEF, COST ENGINEERING, Willie Honza
 PREPARED: 10/9/2013

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|------------------------------|---------------|-----------------------------------|----------------|---|---------------|--------------------------------------|----------------|-----------------------------------|-----------------|---------------|---------------|---------------|
| | | Estimate Prepared: 10/9/2013 | | Effective Price Level: 1-Oct-2013 | | Program Year (Budget EC): 2016 | | Effective Price Level Date: 1 OCT 15 | | FULLY FUNDED PROJECT ESTIMATE | | | | |
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | Mid-Point Date | INFLATED (%) | COST (\$K) | CNTG (\$K) | FULL (\$K) |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| PHASE 6 or CONTRACT 6 | | | | | | | | | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | | |
| 12 | non-Federal | \$12,305 | \$2,461 | 20% | \$14,766 | 1.8% | \$12,531 | \$2,506 | \$15,037 | 2019Q3 | 8.9% | \$13,640 | \$2,728 | \$16,368 |
| 12 | Federal | \$17,002 | \$3,400 | 20% | \$20,403 | 1.8% | \$17,314 | \$3,463 | \$20,777 | 2019Q3 | 8.9% | \$18,847 | \$3,769 | \$22,616 |
| | | | | | | | \$0 | | | | | | | |
| CONSTRUCTION ESTIMATE TOTALS: | | \$29,307 | \$5,861 | 20% | \$35,169 | | \$29,845 | \$5,969 | \$35,814 | | | \$32,487 | \$6,497 | \$38,984 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 0.5% | Project Management | \$147 | \$29 | 20% | \$176 | 3.7% | \$152 | \$30 | \$183 | 2018Q2 | 14.5% | \$174 | \$35 | \$209 |
| 1.0% | Planning & Environmental Compliance | \$293 | \$59 | 20% | \$352 | 3.7% | \$304 | \$61 | \$364 | 2018Q2 | 14.5% | \$348 | \$70 | \$417 |
| 5.0% | Engineering & Design | \$1,465 | \$293 | 20% | \$1,758 | 3.7% | \$1,519 | \$304 | \$1,822 | 2018Q2 | 14.5% | \$1,739 | \$348 | \$2,087 |
| 0.7% | Reviews, ATRs, IEPRs, VE | \$205 | \$41 | 20% | \$246 | 3.7% | \$212 | \$42 | \$255 | 2018Q2 | 14.5% | \$243 | \$49 | \$292 |
| 0.5% | Life Cycle Updates (cost, schedule, risks) | \$147 | \$29 | 20% | \$176 | 3.7% | \$152 | \$30 | \$183 | 2018Q2 | 14.5% | \$174 | \$35 | \$209 |
| 0.8% | Contracting & Reprographics | \$234 | \$47 | 20% | \$281 | 3.7% | \$243 | \$49 | \$291 | 2018Q2 | 14.5% | \$278 | \$56 | \$333 |
| 1.5% | Engineering During Construction | \$440 | \$88 | 20% | \$528 | 3.7% | \$456 | \$91 | \$547 | 2019Q3 | 20.7% | \$551 | \$110 | \$661 |
| 0.0% | Planning During Construction | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 0.0% | Project Operations | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 5.0% | Construction Management | \$1,465 | \$293 | 20% | \$1,758 | 1.9% | \$1,493 | \$299 | \$1,791 | 2019Q3 | 8.8% | \$1,625 | \$325 | \$1,950 |
| 0.5% | Project Operation: | \$147 | \$29 | 20% | \$176 | 1.9% | \$150 | \$30 | \$180 | 2019Q3 | 8.8% | \$163 | \$33 | \$196 |
| 0.5% | Project Management | \$147 | \$29 | 20% | \$176 | 1.9% | \$150 | \$30 | \$180 | 2019Q3 | 8.8% | \$163 | \$33 | \$196 |
| CONTRACT COST TOTALS: | | \$33,997 | \$6,799 | | \$40,797 | | \$34,676 | \$6,935 | \$41,611 | | | \$37,945 | \$7,589 | \$45,534 |

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: P2-370840 Brazos Island Harbor, Texas, Channel Improvement Project
 LOCATION: Cameron County, Texas
 This Estimate reflects the scope and schedule in report: BIH Engineering Appendix 2013

DISTRICT: SWG Galveston District PREPARED: 10/9/2013
 POC: CHIEF, COST ENGINEERING, Willie Honza

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|------------------------------|---------------|-----------------------------------|----------------|---|---------------|--------------------------------------|----------------|-----------------------------------|-----------------|---------------|---------------|---------------|
| | | Estimate Prepared: 10/9/2013 | | Effective Price Level: 1-Oct-2013 | | Program Year (Budget EC): 2016 | | Effective Price Level Date: 1 OCT 15 | | FULLY FUNDED PROJECT ESTIMATE | | | | |
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | Mid-Point Date | INFLATED (%) | COST (\$K) | CNTG (\$K) | FULL (\$K) |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| PHASE 7 or CONTRACT 7 | | | | | | | | | | | | | | |
| 12 | NAVIGATION PORTS & HARBORS | | | | | | | | | | | | | |
| 12 | non-Federal | \$8,855 | \$1,771 | 20% | \$10,626 | 1.8% | \$9,018 | \$1,804 | \$10,821 | 2019Q4 | 9.4% | \$9,862 | \$1,972 | \$11,835 |
| 12 | Federal | \$13,230 | \$2,646 | 20% | \$15,875 | 1.8% | \$13,472 | \$2,694 | \$16,167 | 2019Q4 | 9.4% | \$14,734 | \$2,947 | \$17,681 |
| | | | | | | | \$0 | | | | | | | |
| CONSTRUCTION ESTIMATE TOTALS: | | \$22,085 | \$4,417 | 20% | \$26,502 | | \$22,490 | \$4,498 | \$26,988 | | | \$24,597 | \$4,919 | \$29,516 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 0.5% | Project Management | \$110 | \$22 | 20% | \$132 | 3.7% | \$114 | \$23 | \$137 | 2018Q2 | 14.5% | \$131 | \$26 | \$157 |
| 1.0% | Planning & Environmental Compliance | \$221 | \$44 | 20% | \$265 | 3.7% | \$229 | \$46 | \$275 | 2018Q2 | 14.5% | \$262 | \$52 | \$315 |
| 5.0% | Engineering & Design | \$1,104 | \$221 | 20% | \$1,325 | 3.7% | \$1,144 | \$229 | \$1,373 | 2018Q2 | 14.5% | \$1,310 | \$262 | \$1,572 |
| 0.7% | Reviews, ATRs, IEPRs, VE | \$155 | \$31 | 20% | \$186 | 3.7% | \$161 | \$32 | \$193 | 2018Q2 | 14.5% | \$184 | \$37 | \$221 |
| 0.5% | Life Cycle Updates (cost, schedule, risks) | \$110 | \$22 | 20% | \$132 | 3.7% | \$114 | \$23 | \$137 | 2018Q2 | 14.5% | \$131 | \$26 | \$157 |
| 0.8% | Contracting & Reprographics | \$177 | \$35 | 20% | \$212 | 3.7% | \$183 | \$37 | \$220 | 2018Q2 | 14.5% | \$210 | \$42 | \$252 |
| 1.5% | Engineering During Construction | \$331 | \$66 | 20% | \$397 | 3.7% | \$343 | \$69 | \$412 | 2019Q4 | 22.0% | \$419 | \$84 | \$502 |
| 0.0% | Planning During Construction | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 0.0% | Project Operations | \$0 | \$0 | 20% | \$0 | 0.0% | \$0 | \$0 | \$0 | 0 | 0.0% | \$0 | \$0 | \$0 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 5.0% | Construction Management | \$1,104 | \$221 | 20% | \$1,325 | 1.9% | \$1,125 | \$225 | \$1,350 | 2019Q4 | 9.4% | \$1,230 | \$246 | \$1,476 |
| 0.5% | Project Operation: | \$110 | \$22 | 20% | \$132 | 1.9% | \$112 | \$22 | \$135 | 2019Q4 | 9.4% | \$123 | \$25 | \$147 |
| 0.5% | Project Management | \$110 | \$22 | 20% | \$132 | 1.9% | \$112 | \$22 | \$135 | 2019Q4 | 9.4% | \$123 | \$25 | \$147 |
| CONTRACT COST TOTALS: | | \$25,617 | \$5,123 | | \$30,740 | | \$26,128 | \$5,226 | \$31,354 | | | \$28,718 | \$5,744 | \$34,462 |

CHANNEL IMPROVEMENT PROJECT
BRAZOS ISLAND HARBOR, TEXAS

ENGINEERING APPENDIX FOR
FEASIBILITY STUDY BROWNSVILLE SHIP
CHANNEL 52 FT DEEPENING PROJECT




Coastal Navigation and Environmental Restoration

Office of the District Engineer
U. S. Army Engineer District, Galveston
Corps of Engineers
Galveston, Texas
October 2013



| INDEX OF DRAWINGS | | |
|---------------------|----------|---|
| SHEET # of 51 | DWG. NO. | TITLE |
| GENERAL | | |
| 1 | | COVER SHEET |
| 2 | G-01 | GENERAL NOTES AND INDEX OF DRAWINGS |
| CIVIL-SITE | | |
| 3 | C-01 | LOCATION PLAN |
| 4 | C-02 | PLAN - STA.89+500 TO STA.77+000 |
| 5 | C-03 | PLAN - STA.77+000 TO STA.62+500 |
| 6 | C-04 | PLAN - STA.62+500 TO STA.49+000 |
| 7 | C-05 | PLAN - STA.49+000 TO STA.35+000 |
| 8 | C-06 | PLAN - STA.35+000 TO STA.21+000 |
| 9 | C-07 | PLAN - STA.21+000 TO STA.7+000 |
| 10 | C-08 | PLAN - STA.7+000 TO STA.-7+000 |
| 11 | C-09 | PLAN - STA.-7+000 TO STA.-13+000 |
| 12 | C-10 | PLAN - OCEAN DREDGED MATERIAL DISPOSAL SITE (ODMDS) |
| 13 | C-11 | PLAN - NEARSHORE BERM BU SITE |
| 14 | C-12 | CROSS SECTIONS - ENTRANCE AND JETTY CHANNEL STA.-15+000 TO STA.-1+000 |
| 15 | C-13 | CROSS SECTIONS - MAIN CHANNEL STA.3+000 TO STA.79+415 |
| 16 | C-14 | CROSS SECTIONS - TURNING BASINS STA.82+000 TO STA.89+500 |
| GEOTECHNICAL | | |
| 17 | F-01 | CHANNEL BORING GEOREFERENCE AND GENERAL SOIL PLOT INFORMATION |
| 18 | F-02 | BORING LOCATION PLAN CONTAINMENT DIKE TYPICAL PLACEMENT AREA NO.2 |
| 19 | F-03 | BORING LOCATION PLAN CONTAINMENT DIKE TYPICAL PLACEMENT AREA NO.4A |
| 20 | F-04 | CONTAINMENT DIKE TYPICAL FOR PA 4B |
| 21 | F-05 | BORING LOCATION PLAN CONTAINMENT DIKE TYPICAL PLACEMENT AREA NO.5-A |
| 22 | F-06 | BORING LOCATION PLAN CONTAINMENT DIKE TYPICAL PLACEMENT AREA NO.5-B |
| 23 | F-07 | BORING LOCATION PLAN CONTAINMENT DIKE TYPICAL PLACEMENT AREA NO.7 |
| 24 | F-08 | BORING LOCATION PLAN CONTAINMENT DIKE TYPICAL PLACEMENT AREA NO.8 |
| 25 | F-09 | LOGS OF BORINGS |
| 26 | F-10 | LOGS OF BORINGS |
| 27 | F-11 | LOGS OF BORINGS |
| 28 | F-12 | LOGS OF BORINGS |
| 29 | F-13 | LOGS OF BORINGS |
| 30 | F-14 | LOGS OF BORINGS |
| 31 | F-15 | LOGS OF BORINGS |
| 32 | F-16 | LOGS OF BORINGS |
| 33 | F-17 | LOGS OF BORINGS |
| 34 | F-18 | LOGS OF BORINGS |
| 35 | F-19 | LOGS OF BORINGS |
| 36 | F-20 | CHANNEL BORINGS |
| 37 | F-21 | CHANNEL BORINGS |
| 38 | F-22 | CHANNEL BORINGS |
| 39 | F-23 | CHANNEL BORINGS |
| 40 | F-24 | CHANNEL BORINGS |
| 41 | F-25 | PA NO.2 CONTAINMENT DIKE SLOPE STABILITY ANALYSIS RESULTS |
| 42 | F-26 | PA NO.4A CONTAINMENT DIKE SLOPE STABILITY ANALYSIS RESULTS |
| 43 | F-27 | PA NO.4B CONTAINMENT DIKE SLOPE STABILITY ANALYSIS RESULTS |
| 44 | F-28 | PA NO.5A CONTAINMENT DIKE SLOPE STABILITY ANALYSIS RESULTS |
| 45 | F-29 | PA NO.5B CONTAINMENT DIKE SLOPE STABILITY ANALYSIS RESULTS |
| 46 | F-30 | PA NO.7 CONTAINMENT DIKE SLOPE STABILITY ANALYSIS RESULTS |
| 47 | F-31 | PA NO.8 CONTAINMENT DIKE SLOPE STABILITY ANALYSIS RESULTS |
| 48 | F-32 | UNDRAINED CHANNEL STABILITY ANALYSIS NEAR PA NO.4 REGION |
| 49 | F-33 | CHANNEL DRAINED STABILITY ANALYSIS NEAR PA NO.4 REGION |
| 50 | F-34 | CHANNEL DRAINED STABILITY ANALYSIS NEAR PA NO.5 REGION |
| 51 | F-35 | CHANNEL DRAINED STABILITY ANALYSIS NEAR PA NO.5 REGION |
| 51 | | -- Total Number of Drawings |



GENERAL NOTES

- ELEVATIONS ARE REFERENCED TO MEAN LOWER-LOW WATER (MLLW). ALL FUTURE CONSTRUCTION CONTRACTS WILL BE DREDGED TO 52 FEET MLLW ACTUAL
- HORIZONTAL DATUM IS REFERENCED TO NAD(83), TEXAS SOUTH ZONE, U.S. SURVEY FEET.
- THE BOTTOM WIDTHS OF THE PROPOSED CHANNEL WERE NOT INCREASED FROM THE EXISTING CHANNEL BOTTOM WIDTH.
- THE CENTERLINE OF THE EXISTING CHANNEL WAS USED FOR THE PROPOSED CHANNEL.
- ALL PLACEMENT AREAS FOR THIS PROJECT ARE EXISTING, NO NEW AREAS TO BE CONSTRUCTED.
- THE EXISTING OPEN WATER MAINTENANCE ODMDS PA IS NOT PLANNED TO BE USED FOR MAINTENANCE OPERATIONS, BUT WILL BE AVAILABLE IF NEEDED.




| Rev. | Date | Description |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| | | | | |
|--|-----------------|---|-----------------------------------|--------------------------------------|
| Drawn by: MAN | Checked by: BRH | Submitted by: BRH | Approved by: DAVID S. BROWN, P.E. | Chief, Civil Engineering |
| Date: OCT 2013 | Scale: AS SHOWN | Approval Recommendation: JOSEPH L. KWIC, P.A. | Chief, Engineering Branch | Approved by: TERRY F. BAUTISTA, P.E. |
| U.S. ARMY ENGINEER DISTRICT, GALVESTON CORPS OF ENGINEERS GALVESTON, TEXAS | | | | |
| PREPARED UNDER THE DIRECTION OF RICHARD P. PANNELL, Col., C.E., DISTRICT COMMANDER | | | | |

CHANNEL IMPROVEMENT PROJECT BRAZOS RIVER NEAR BROWNSVILLE, TEXAS FOR FEASIBILITY STUDY BRUNNEN AND SHIP CHANNEL 52 FT DEEPENING PROJECT

GENERAL NOTES AND INDEX OF DRAWINGS

File: W:\CADD\Projects\Rio\Brownsville Ship Channel_Study\Existing-Conditions\BH-Plan-01b.dgn
 Model Name: Default
 By: MSODXMAN Date: 11/19/2013 Time: 8:13:55 AM



**WESTERLY LIMITS
OF DREDGING
STA. 84+200**

**EASTERLY LIMITS
OF DREDGING
STA. -17+000**




| Rev. | Date | Description |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| | | |
|----------------------------|--|------|
| MAN | DATE | REV. |
| BRH | OCT 2013 | 1 |
| BRH | SCALE AS SHOWN | |
| BRH | APPROVAL RECOMMENDED: | |
| DAVID S. BROWN, P.E. | JOSEPH L. KWIC, P.A. | |
| Chief, Coastal Engineering | Chief, Engineering Branch | |
| APPROVED BY: | TERRY F. BAUTISTA, P.E. | |
| | Chief, Engineering and Construction Division | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS
 PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER FEASIBILITY STUDY BROWNSVILLE SHIP
 CHANNEL 52 FT DEEPENING PROJECT
 LOCATION PLAN

Drawing No.:
C-01
 Sheet 3 of 51



| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |

| | | | | | |
|---------------|--------------------------|-----------|--|------|--|
| Drawn by: | MAN | Date: | OCT 2013 | Rev. | |
| Designed by: | BRH | Scale: | AS SHOWN | | |
| Checked by: | BRH | Approval: | Recommended | | |
| Submitted by: | DAVID S. BROWN, P.E. | Approval: | Recommended | | |
| | Chief, Civil Engineering | Approval: | Chief, Engineering Branch | | |
| | | Approval: | Chief, Engineering and Construction Division | | |
| | | Approval: | Chief, Engineering and Construction Division | | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS

PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER FEASIBILITY STUDY BROWNSVILLE SHIP
 CHANNEL 52 FT DEEPENING PROJECT

PLAN
 STA. 89+500 TO STA. 77+000

Drawing No.:
C-02
 Sheet 4 of 51




| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |

| Drawn by: | MAN | Date: | OCT 2013 | Rev. |
|--|--|---|-------------------------------------|------|
| Designed by: <td>BRH <td>Scale: <td>AS SHOWN <td> </td> </td></td></td> | BRH <td>Scale: <td>AS SHOWN <td> </td> </td></td> | Scale: <td>AS SHOWN <td> </td> </td> | AS SHOWN <td> </td> | |
| Checked by: <td>BRH <td>Approval: <td>Recommended:</td> <td> </td> </td></td> | BRH <td>Approval: <td>Recommended:</td> <td> </td> </td> | Approval: <td>Recommended:</td> <td> </td> | Recommended: | |
| Submitted by: <td>DAVID S. BROVIN, P.E. <td>Checked by: <td>JOSEPH L. KWIC, P.A. <td> </td> </td></td></td> | DAVID S. BROVIN, P.E. <td>Checked by: <td>JOSEPH L. KWIC, P.A. <td> </td> </td></td> | Checked by: <td>JOSEPH L. KWIC, P.A. <td> </td> </td> | JOSEPH L. KWIC, P.A. <td> </td> | |
| Approved by: <td>TERRY F. BAUTISTA, P.E. <td>Chief Engineer: <td>Chief Engineering Branch <td> </td> </td></td></td> | TERRY F. BAUTISTA, P.E. <td>Chief Engineer: <td>Chief Engineering Branch <td> </td> </td></td> | Chief Engineer: <td>Chief Engineering Branch <td> </td> </td> | Chief Engineering Branch <td> </td> | |
| | | Chief of Construction: <td> </td> <td> </td> | | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS
 PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER FEASIBILITY STUDY BRUNSWICK AND
 FOR FEASIBILITY STUDY BRUNSWICK LE SHIP
 CHANNEL 52 FT DEEPENING PROJECT
 PLAN
 STA. 77+000 TO STA. 62+500

Drawing No.:
C-03
 Sheet 5 of 51



| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| | | |
|--------------------------------------|--|------|
| Drawn by: MAN | Date: OCT 2013 | Rev. |
| Designed by: BRH | Scale: AS SHOWN | |
| Checked by: BRH | Approval Recommended by: | |
| Submitted by: DAVID S. BROVIN, P.E. | JOSEPH L. KWIC, P.A. | |
| Chief, Civil Engineering | Chief, Engineering Branch | |
| Approved by: TERRY F. BAUTISTA, P.E. | Chief, Engineering and Construction Division | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS

PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER SYSTEMS AND CHANNELS AND
 FOR FEASIBILITY STUDY BROWNSVILLE SHIP
 CHANNEL 52 FT DEEPENING PROJECT

PLAN
 STA. 62+500 TO STA. 49+000

Drawing No.:
C-04
 Sheet 6 of 51



| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |

| Drawn by: | Date: | Rev. |
|--------------------------------------|--|------|
| MAN | OCT 2013 | |
| Designed by: BRH | Scale: AS SHOWN | |
| Checked by: BRH | Approval Recommended: | |
| Submitted by: DAVID S. BROWN, P.E. | JOSEPH L. KWIC, P.A. | |
| Chief, Civil Engineering | Chief, Engineering Branch | |
| Approved by: TERRY F. BAUTISTA, P.E. | Chief, Engineering and Construction Division | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS

PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER SYSTEM STUDY BRUNSWICK AND
 FOR FEASIBILITY STUDY BRUNSWICK LE SHIP
 CHANNEL 52 FT DEEPENING PROJECT

PLAN
 STA. 49+000 TO STA. 35+000

Drawing No.:
C-05
 Sheet 7 of 51



| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |

| Drawn by: | MAN | Date: | OCT 2013 | Rev. |
|--|---|---|--|------|
| Designed by: <td>BRH <td>Scale: <td>AS SHOWN <td> </td> </td></td></td> | BRH <td>Scale: <td>AS SHOWN <td> </td> </td></td> | Scale: <td>AS SHOWN <td> </td> </td> | AS SHOWN <td> </td> | |
| Checked by: <td>BRH <td>Approval: <td>Recommended:</td> <td> </td> </td></td> | BRH <td>Approval: <td>Recommended:</td> <td> </td> </td> | Approval: <td>Recommended:</td> <td> </td> | Recommended: | |
| Submitted by: <td>DAVID S. BROUIN, P.E. <td>Chief: <td>JOSEPH L. KWIC, P.A. <td> </td> </td></td></td> | DAVID S. BROUIN, P.E. <td>Chief: <td>JOSEPH L. KWIC, P.A. <td> </td> </td></td> | Chief: <td>JOSEPH L. KWIC, P.A. <td> </td> </td> | JOSEPH L. KWIC, P.A. <td> </td> | |
| Approved by: <td>TERRY F. BAUTISTA, P.E. <td>Chief: <td>Engineering Branch <td> </td> </td></td></td> | TERRY F. BAUTISTA, P.E. <td>Chief: <td>Engineering Branch <td> </td> </td></td> | Chief: <td>Engineering Branch <td> </td> </td> | Engineering Branch <td> </td> | |
| | | Chief: <td>Engineering and Construction Division <td> </td> </td> | Engineering and Construction Division <td> </td> | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS

PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER FEASIBILITY STUDY BRUNSVILLE SHIP
 CHANNEL 52 FT DEEPENING PROJECT

PLAN
 STA. 35+000 TO STA. 21+000

Drawing No.:
C-06
 Sheet 8 of 51



| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |

| Drawn by: | MAN | Date: | OCT 2013 | Rev. |
|---------------|--------------------------|-----------|--|------|
| Designed by: | BRH | Scale: | AS SHOWN | |
| Checked by: | BRH | Approval: | Recommended: | |
| Submitted by: | DAVID S. BROVIN, P.E. | Chief: | JOSEPH L. KWIC, P.A. | |
| Chief: | Chief, Civil Engineering | Chief: | Chief, Engineering Branch | |
| Approved by: | TERRY F. BAUTISTA, P.E. | Chief: | Chief, Engineering and Construction Division | |


U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS

PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER AND NEARBY TRIBUTARIES AND
 FOR FEASIBILITY STUDY BROWNSVILLE SHIP
 CHANNEL 52 FT DEEPENING PROJECT

PLAN
 STA. 21+000 TO STA. 7+000

Drawing No.:
C-07
 Sheet 9 of 51



MATCH LINE SHEET C-11

MATCH LINE STA. -7+000




| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| | | | | |
|-----------------|-------------------------|---------------------------|----------------------|------|
| Drawn by: | MAN | Date: | OCT 2013 | Rev. |
| Designed by: | BRH | Scale: | AS SHOWN | |
| Checked by: | BRH | Approval: | Recommended | |
| Submitted by: | DAVID S. BROUIN, P.E. | Chief Engineer: | JOSEPH L. KWIC, P.A. | |
| Chief Engineer: | TERRY F. BAUTISTA, P.E. | Chief Engineering Branch: | | |
| Approved by: | | Chief of Construction: | | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS
 PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER AND RYAN CREEK AND
 FOR FEASIBILITY STUDY BROWNSVILLE SHIP
 CHANNEL 52 FT DEEPENING PROJECT
 PLAN
 STA. 7+000 TO STA. -7+000

Drawing No.:
C-08
 Sheet 10 of 51



MATCH LINE SHEET C-10



| Rev. | Date | Description |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| Drawn by: | MAN | Date: | OCT 2013 | Rev. |
|---------------|-------------------------|-----------|---------------------------------------|------|
| Checked by: | BRH | Scale: | AS SHOWN | |
| Submitted by: | BRH | Approval: | Recommended: | |
| Checked by: | DAVID S. BROWN, P.E. | Checked: | JOSEPH L. KWIC, P.A. | |
| Approved by: | TERRY F. BAUTISTA, P.E. | Chief: | Engineering Branch | |
| | | Chief: | Engineering and Construction Division | |

CHANNEL IMPROVEMENT PROJECT BRAZOS RIVER DELTA AND BROWNVILLE SHIP CHANNEL 52 FT DEEPENING PROJECT
 ISLE FOR FEASIBILITY STUDY BROWNVILLE SHIP CHANNEL 52 FT DEEPENING PROJECT
 PLAN
 STA. -7+000 TO STA. -13+000

Drawing No.:
C-09
 Sheet 11 of 51

- NOTE:
 1. THE PROPOSED EXTENSION TO THE ENTRANCE CHANNEL IS FROM STA. -13+000 TO STA. -17+000
 2.

MATCH LINE SHEET C-09

GULF OF MEXICO

GULF OF MEXICO

**NEW WORK ODMDS
 (OCEAN DREDGED MATERIAL
 DISPOSAL SITE)**

1,445,000
 16,557,500

Y= 16,557,045
 X= 1,448,548

1,450,000
 16,557,500

1,455,000
 16,557,500

Y= 16,556,600
 X= 1,453,842

Y= 16,559,430
 X= 1,454,083

1,447,500
 16,555,000

1,455,000
 16,555,000

1,445,000
 16,552,500

1,450,000
 16,552,500

1,455,000
 16,552,500

NOTE: NEW WORK DREDGE MATERIAL FROM STA. 0+000 TO -17+000 WILL BE PLACED IN THE NEW WORK ODMDS.




| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| | | |
|--|--|------|
| Drawn by: MAN | Date: OCT 2013 | Rev. |
| Designed by: BRH | Scale: AS SHOWN | |
| Checked by: BRH | Approval Recommended: | |
| Submitted by: DAVID S. BROWN, P.E. | JOSEPH L. KIRK, P.A. | |
| Chief, Civil Engineering | Chief, Engineering Branch | |
| Approved by: TERRY F. BAUTISTA, P.E. | Chief, Engineering and Construction Division | |
| U.S. ARMY ENGINEER DISTRICT, GALVESTON CORPS OF ENGINEERS GALVESTON, TEXAS | | |
| PREPARED UNDER THE DIRECTION OF RICHARD P. PANNELL, Col., C.E., DISTRICT COMMANDER | | |

CHANNEL IMPROVEMENT PROJECT BRAZOS RIVER AND GULF OF MEXICO SHIP CHANNEL FOR FEASIBILITY STUDY BRUNNENSHULE SHIP CHANNEL 52 FT DEEPENING PROJECT
PLAN
 OCEAN DREDGED MATERIAL DISPOSAL SITE (ODMDS)

Drawing No.:
C-10
 Sheet 12 of 51

MATCH LINE SHEET C-08



| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| Drawn by: | MAN | Date: | OCT 2013 | Rev. |
|---|--|--|---------------------------------|------|
| Designed by: <td>BRH <td>Scale: <td>AS SHOWN <td> </td> </td></td></td> | BRH <td>Scale: <td>AS SHOWN <td> </td> </td></td> | Scale: <td>AS SHOWN <td> </td> </td> | AS SHOWN <td> </td> | |
| Checked by: <td>BRH <td>Approval: <td> </td> <td> </td> </td></td> | BRH <td>Approval: <td> </td> <td> </td> </td> | Approval: <td> </td> <td> </td> | | |
| Submitted by: <td>DAVID S. BROVIN, P.E. <td>Approval Recommendation: <td> </td> <td> </td> </td></td> | DAVID S. BROVIN, P.E. <td>Approval Recommendation: <td> </td> <td> </td> </td> | Approval Recommendation: <td> </td> <td> </td> | | |
| Chief: <td>Chief, Coastal Engineering <td>Chief, Engineering Branch: <td>JOSEPH L. KWIK, P.A. <td> </td> </td></td></td> | Chief, Coastal Engineering <td>Chief, Engineering Branch: <td>JOSEPH L. KWIK, P.A. <td> </td> </td></td> | Chief, Engineering Branch: <td>JOSEPH L. KWIK, P.A. <td> </td> </td> | JOSEPH L. KWIK, P.A. <td> </td> | |
| Approved by: <td>TERRY F. BAUTISTA, P.E. <td>Chief, Engineering and Construction Division: <td> </td> <td> </td> </td></td> | TERRY F. BAUTISTA, P.E. <td>Chief, Engineering and Construction Division: <td> </td> <td> </td> </td> | Chief, Engineering and Construction Division: <td> </td> <td> </td> | | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
 CORPS OF ENGINEERS
 GALVESTON, TEXAS

PREPARED UNDER THE DIRECTION OF
 RICHARD P. PANNELL, Col., C.E.,
 DISTRICT COMMANDER

CHANNEL IMPROVEMENT PROJECT BRAZOS
 RIVER AND GULF OF MEXICO COAST
 FOR FEASIBILITY STUDY BRONSONVILLE SHIP
 CHANNEL 52 FT DEEPENING PROJECT

PLAN
 NEARSHORE BERM BU SITE

Drawing No.:
C-11
 Sheet 13 of 51



ENTRANCE AND JETTY CHANNEL - STA. -15+000 TO STA. -1+000



U.S. Army Corps of Engineers
Galveston District

| Rev. | Description | Date | By |
|------|-------------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |





| | | | |
|---------------|-------------------------|--|----------|
| Drawn by: | MAN | Date: | |
| Designed by: | BRH | Scale: | AS SHOWN |
| Checked by: | BRH | Approval Recommended by: | |
| Submitted by: | DAVID R. BROWN, P.E. | Chief, General Engineering | |
| Approved by: | TERRY F. BAUTISTA, P.E. | Chief, Engineering and Construction Division | |

U.S. ARMY ENGINEER DISTRICT, GALVESTON
CORPS OF ENGINEERS
GALVESTON, TEXAS

PREPARED UNDER THE DIRECTION OF
RICHARD P. PANNELL, Col., C.E.,
DISTRICT COMMANDER

BRAZOS ISLAND HARBOR, TEXAS
FEASIBILITY STUDY
BROWNSVILLE SHIP CHANNEL
52 FT DEEPENING PROJECT
CROSS SECTIONS
ENTRANCE AND JETTY CHANNEL
STA. -15+000 TO STA. -1+000

Drawing No.:
C-12
Sheet 14 of 51



CHANNEL SURFACE
 - - - - - EXISTING CHANNEL
 ———— PROPOSED CHANNEL
 - - - - - EXISTING GROUND
 Vertical Scaled 10 Times

NOTES:
 1. CROSS SECTIONS PLOTTED LOOKING TOWARDS INCREASING STATIONS
 2. VERTICAL DATUM IS IN MLLW (MEAN LOWER LOW WATER)
 3. ADVANCED MAINTENANCE IS INCLUDED IN THE PROPOSED CHANNEL TEMPLATE SHOWN

MAIN CHANNEL - STA. 3+000 TO STA. 79+415



U.S. Army Corps of Engineers
Galveston District








| Rev. | Date | Description |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |

| | | | |
|--------------|-----|---------------|--|
| Drawn by: | MAN | Date: | AS SHOWN |
| Designed by: | BRH | Scale: | AS SHOWN |
| Checked by: | BRH | Submitted by: | DAVID R. BROWN, P.E. |
| | | | Chief, General Engineering |
| | | | Approved by: |
| | | | TERRY F. BAUTISTA, P.E. |
| | | | Chief, Engineering and Construction Division |

U.S. ARMY ENGINEER DISTRICT GALVESTON
CORPS OF ENGINEERS
GALVESTON, TEXAS
PREPARED UNDER THE DIRECTION OF
RICHARD P. FANNELL, Col., C.E.,
DISTRICT COMMANDER

BRAZOS ISLAND HARBOR, TEXAS
FEASIBILITY STUDY
BROWNSVILLE SHIP CHANNEL
52 FT DEEPENING PROJECT
CROSS SECTIONS
MAIN CHANNEL
STA. 3+000 TO STA. 79+415

Drawing No.:
C-13
Sheet 15 of 51



CHANNEL SURFACE
 --- EXISTING CHANNEL
 ——— PROPOSED CHANNEL
 -·-·- EXISTING GROUND
 Vertical Scaled 10 Times

NOTES:
 1. CROSS SECTIONS PLOTTED LOOKING TOWARDS INCREASING STATIONS
 2. VERTICAL DATUM IS IN MLLW (MEAN LOWER LOW WATER)
 3. ADVANCED MAINTENANCE IS INCLUDED IN THE PROPOSED CHANNEL TEMPLATE SHOWN






File: W:\CADD\Projects\Rio\Brownsville Ship Channel_Study\Existing-Conditions\BH-Plan-Xsecs-12-14.dgn
 Model Name: 0-TYP Sections - 2
 By: M3ODYMAN Date: 11/19/2013 Time: 8:18:39 AM

TURNING BASINS - STA. 82+000 TO STA. 89+500



U.S. Army Corps
of Engineers
Galveston District

CHANNEL SURFACE
 --- EXISTING CHANNEL
 - - - PROPOSED CHANNEL
 - - - EXISTING GROUND
 Vertical Scaled 10 Times



NOTES:
 1. CROSS SECTIONS PLOTTED LOOKING TOWARDS INCREASING STATIONS
 2. VERTICAL DATUM IS IN MLLW (MEAN LOWER LOW WATER)
 3. ADVANCED MAINTENANCE IS INCLUDED IN THE PROPOSED CHANNEL TEMPLATE SHOWN

| Rev. | Date | Description |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |

| | | | |
|---------------------------------------|--|---------------|----------------------|
| U.S. ARMY ENGINEER DISTRICT GALVESTON | MAN | DATE: | |
| CORPS OF ENGINEERS | BRH | DESIGNED BY: | AS SHOWN |
| GALVESTON, TEXAS | BRH | CHECKED BY: | |
| PREPARED UNDER THE DIRECTION OF | DAVID R. BROWN, P.E. | SUBMITTED BY: | JOSEPH L. KING, R.A. |
| RICHARD P. FANNELL, Col., C.E., | | APPROVED BY: | |
| DISTRICT COMMANDER | | | |
| | TERRY F. BAUTISTA, P.E. | | |
| | Chief, Engineering and Construction Division | | |

BRAZOS ISLAND HARBOR, TEXAS
 FEASIBILITY STUDY
 BROWNSVILLE SHIP CHANNEL
 52 FT DEEPENING PROJECT
 CROSS SECTIONS
 TURNING BASINS
 STA. 82+000 TO STA. 89+500

Drawing No.:
C-14
 Sheet 16 of 51

File: W:\CADD\Projects\Rio\Brownsville Ship Channel_Study\Existing-Conditions\BIH-Plan-Xsecs-12-14.dgn
 Model Name: 0-TYP Sections - 3
 By: M3ODXMAN Date: 11/19/2013 Time: 8:18:40 AM