

Beacon Hill

INTERIOR FINISH SCHEDULE

**100% Construction
Document
April 6, 2015**

PREPARED BY:

BRIDGET BOHACZ + associates, inc.

810 Landmark Drive, Suite 120

Glen Burnie, MD 21061

(410) 768-2244

(410) 768-2254 fax

INDEX:**PAGE #:**

Notes	A-F
Independent Living Commons Basement	1 - 15
Independent Living Residential Apartments	16-17
Independent Living Residential Commons Level 0	18-21
Independent Living Residential Commons Level 1	22-30
Independent Living Residential Commons Level 2	31-34
Independent Living Residential Commons Level 3	35-38
Independent Living Office Renovation	39-45

NOTES:

General Note: All spaces are finished. Do not assume any space receives no finish materials.

FLOOR COVERING -

CARPET

Carpet 1

IL Apartments

Mohawk, Portico, Portofino II, Choice of 5 colors, with 64 oz. SCI underlayment pad. For all Mohawk carpets, contact Marc McDonald at 410-456-8884 to assist with pricing and/or finding a local dealer.

Carpet pad to be used under carpet:

Leggett & Platt , SCI ,Contract Comfort 64, contact Vincent Dimino at 717-503-9474 to assist.

Carpet 2

IL Residential Corridors, Lounges, Auditorium

Durkan Patterned Carpet. Base grade is 36 oz Texture Craft. Direct glue installation. Use \$35 for material cost only. Material cost does not include mark-up, freight, installation, glue or overages. Refer to the Interior Design drawings for patterns consisting of rugs, insets and medallions. Installation costs need to factor in these rug designs, insets and medallions. Each level of Independent Living Resident Corridors will utilize a unique/separate colorway; the pattern will be identical on all levels but the colorway will change. Contact Beth Reymer, Durkan Manufacturer's Representative for assistance – (443) 438-3920.

Carpet 3

Walk-Off Roll Goods at Vestibules

Sbemco, Ultra Dry Series. Interior Designer to select from manufacturer's full line of colors. Up to 2 colors will be used.

OR

Mats Inc., Super Nop 52, with custom logo. Up to 3 colors will be used, from the manufacturer's full range of colors. Contact Lori Hilty, for pricing info. Ph# (703) 798-1400.

Carpet 4

Stairwells

PatcraftCarpet, Style: Home Room. Color TBD. Contact Rodney Dennis for pricing info. Ph# (202) 744-7736.

CERAMIC TILE

CT 1

IL Apartment Bathrooms. Daltile, Sandalo or Brixton 18”x 18”. Residents are to choose from 3 colors. Colors to be selected by Interior designer. Contact Catherine Massey-Saenz for Daltile pricing info. Ph #301.257.7665

CT 2

IL Apartment Bathrooms – Shower Floors. Daltile, Sandalo or Brixton mosaic tiles. Residents are to choose from 3 colors. Colors to be selected by Interior designer. Contact Catherine Massey-Saenz for Daltile pricing info. Ph #301.257.7665

CT 3

IL Apartment Kitchens. Daltile, Franciscan Slate 18” X 18”. Residents are to choose from 3 colors. Colors to be selected by Interior designer. Contact Catherine Massey-Saenz for Daltile pricing info. Ph #301.257.7665

CT 4

Commons Restrooms

Daltile, Continental Slate, 12x12, with matching 6”x12” cove base.

NOTE: Wherever there is an adjacent shower that is tiled, the tile on the shower floor changes to Continental Slate in 2x2 mosaic. Contact Catherine Massey-Saenz for Daltile pricing info.

Ph #301.257.7665

CT 5

Commercial Kitchen/Pantry

Daltile, Quarry Textures, 6x6, seal, use black grout. Contact Catherine Massey-Saenz for Daltile pricing info.

Ph #301.257.7665

ALTERNATE CT5

Altro Floor, Stronghold 30. Designer to select from manufacturer’s full range of colors. Contact Suzy McGarity for pricing info. Ph# 410- 920-8757.

VINYL COMPOSITE TILE

VCT -

BOH Assorted BOH, Service Elevator.

Altro Floor Inc., Altro Quartz Tile, 12x12. Designer to select from the manufacturer's full range of colors and patterns from the chipped and marbled range. Contact Suzy McGarity for pricing info. Ph# 410- 920-8757.

ALTERNATE VCT

Mannington, Essentials, 12x12. A 3 color pattern will be used. Designer to select from the manufacturer's full range of colors. Contact Brian Knutson for Mannington pricing info. Ph# 202-421-1610

SV 1 - Altro Flooring, Altro Maxis Unity. Contact Suzy McGarity for pricing info. Ph# 410- 920-8757.

POURED FLOORING

Poured Concrete

Cafe

Elite Crete Systems, Corporation, concrete floor with pattern, sealed.

WOOD FLOORING

Wood Floor 1

Stage at Auditorium

Armstrong, Commercial Grade Flooring, Performance Plus, Natural Oak, ESP5200.

WALL COVERING

VINYL WALL COVERING (VWC)

VWC

Use an allowance of \$1.25 per square foot, for material cost only. Allowance does not include mark-up, freight, installation or tax.

Allow for 27" repeat in Auditorium. Allow for 9" repeat in all other areas.

ACROVYN WALL PROTECTION

This product will be used at all BOH corridors. Corner guards (2" stainless steel) will be used in conjunction with this product, on all exposed corners. This product covers the wall from floor to 48" a.f.f. Coordinating bumper guard and chair rail trim will be used in conjunction with wall covering. Interior designer to select from the manufacturer's standard range of colors.

CERAMIC TILE

WCT 1

IL Apartment Bathrooms – Shower Walls.

WCT 3 – Not Used

WCT 4

Commons Restrooms

Tile wainscot with decorative tile/glass border

Daltile, Continental Slate, 12x12 with Architectural Ceramics, Skyline Linear Border. Border is 12" in height. Overall tile wainscot is floor to 48" a.f.f.

WCT 5

Café Backsplash Walls

Architectural Ceramics, Jeffery Court - Atlas, Spanish Moss, 3"x 6" subway tile with Jeffery Court, Island Pier Mosaic, Spanish Moss border, 2¼" x 11 ¾" Atlas Crown. Contact Kersi Press for pricing info. Ph# (240) 676-0097

CASEWORK & WOOD TRIM -

STAINED WOOD

Auditorium, Café and Adjacent Public Corridors

All stained wood items will be cherry species. Stain to match approved control sample. Color similar to Wilsonart, Versailles Antique, 7923K-07.

STAINED WOOD

Dining Room, Private Dining Room, Club Room

Match existing wood species and stain in IL Commons

RECLAIMD WOOD BEAM

Cafe

Reclaimed wood beam, white oak hand hewn, provided by Christopher Construction Company. Business Address: 207 N Saginaw Byron, MI 48418. Storage Facility Address: 8440 Bennett LK. Rd Fenton, MI 48430.

PAINTED WOOD

All wood trim and casework in the IL Wing will be painted. Poplar wood species. Color TBD. MDF may be substituted for wood trim, except for wood base.

CABINETRY

Merillat Prefabricated Cabinetry for Apartments

Merillat, Seneca Ridge, with crown moulding at top, and apron or lip at bottom of uppers to conceal task lighting. Residents to select from 5 standard finish options plus painted white wood – Chiffon, Hazlenut, Sedona, Toffee and Pecan. Include HP106 pull with all cabinetry. Include pull out shelving in all base cabinets.

Custom Millwork – Stained

Auditorium and Cafe

Cherry species. Stain to match approved control sample.

CABINETRY HARDWARE

General Note

Include Nickel hardware with all cabinetry.

DOOR HARDWARE

Resident Units to receive nickel hardware throughout.
All public areas will receive nickel hardware.

SPECIALTIES –

ACOUSTICAL CEILING TILE

ACT A

IL Commons Areas & Corridors

Armstrong, Calla, Tegular, 2x2, 9/16” Beveled Tegular w/ 9/16” Suprafine Grid.

ACT B

BOH Areas

Armstrong, Cortega 2x4, Square lay-in, with 15/16” Prelude Grid.

ACT C

Food Service Areas

Armstrong, Clean Room VL unperforated, with 15/16” Prelude XL Fire Guard Grid.

FLOOR TRANSITIONS

Contractor to provide mock-ups of each type of floor transition below.

Carpet to Vinyl Plank: Johnsonite SLT-XX-A. Interior designer to select from manufacturer's full range of colors.

Carpet to Vinyl Tile: Johnsonite SLT-XX-A. Interior designer to select from manufacturer's full range of colors.

Carpet to Sheet Vinyl: Johnsonite SLT-XX-C. Interior designer to select from manufacturer's full range of colors.

Carpet to Rubber Tile: Johnsonite SLT-XX-F. Interior designer to select from manufacturer's full range of colors.

Carpet to Carpet: Johnsonite SLT-XX-A. Interior designer to select from manufacturer's full range of colors.

Carpet to Ceramic Tile: Schluter, RENO-TK-ETK-80. Interior designer to select from manufacturer's full range of finishes.

Carpet to Quarry Tile: Schluter, RENO-TK0-ETK-125. Stainless steel finish.

Quarry Tile to VCT: Schluter, RENO-V EU 125. Stainless steel finish.

VCT to Sealed Concrete: Johnsonite RSS-XX-C. Interior designer to select from manufacturer's full range of colors.

Rubber to Sheet Vinyl: Schluter, RENO-TK-ETK-80. Stainless steel finish.

GROUT

Quarry Tile at Commercial Kitchen: Mapei Epoxy Grout.

All other floor and wall tile: Mapei. Interior designer to select from manufacturer's full range of Opti-Color grouts.

INDEPENDENT
LIVING

COMMONS
BASEMENT
LEVEL

INTERIOR FINISH SCHEDULE

ROOM NAME: Corridor
ROOM NUMBER: B001

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CPT - 2

BASE: Base C, Wood, stained -

WALLS:

Above Chair Rail: VWC -
Below Chair Rail: VWC -

DOORS: Stained -

CEILING: ACT-A
Paint -

TRIM: Casing B, Wood, Stained-
Chair Rail A, Wood, Stained -
Crown B, Wood, Stained-

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Cafe , Cook
ROOM NUMBER: B002, B003

Beacon Hill
DATE: 4/1/15
REVISED:

FLOOR: Stained Concrete -

BASE: Base C, Wood, Stained -

WALLS:

VWC -

DOORS: Stained -

CEILING: Soffits - Paint
6" T&G Plank Wood Ceiling, Stained – Pine Species

TRIM: Casing B, Wood, Stained -

SPECIALTY:

Custom Millwork: Cook Island
Countertop: Granite
Wood, Stained, Cherry species
Recessed bead board panels, wood, stained -

Custom Millwork: Counter Niches
Cabinetry: Stained, Cherry species -
Hardware: Nickel finish -
Countertop: Granite -

Cook B003:
Back wall – Decorative tile with tile border- WCT5
Reclaimed wood beam, white oak hand hewn.

Exposed trusses- Stained wood
Flat Panel trim – Stained wood

INTERIOR FINISH SCHEDULE

ROOM NAME: Cafe , Cook

ROOM NUMBER: B002, B003

Beacon Hill

DATE: 4/6/15

REVISED:



INTERIOR FINISH SCHEDULE

ROOM NAME: Prep Cook

ROOM NUMBER: B004

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CT5 - Altro Floor, Stronghold 30. (Color TBD by designer)

BASE: CT5 – Altro Floor, Stronghold 30. (Color TBD by designer)

WALLS:

Epoxy Paint -

DOORS: Paint-

CEILING: ACT-C

TRIM: Casing B, Wood, Paint-

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Green Room

ROOM NUMBER: B005

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: SV-1 - Altro Flooring, Maxis unity

BASE: Vinyl

WALLS:

Paint-

DOORS: Paint

CEILING: Paint -

TRIM:

Casing B, Wood, Paint-

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Men's and Women's Restroom

ROOM NUMBER: B010, B011

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CT-4 - Daltile, Continental Slate, 12x12

BASE: CT-4 - Daltile, Continental Slate 6x12 cove base

WALLS:

WCT4 - Wainscot with decorative tile/glass border

Daltile, Continental Slate, 12x12 w/ architectural ceramics, Skyline linear border. Border is 12" in height, overall wainscot is floor to 48" a.f.f

VWC above wainscot -

DOORS: Stained-

CEILING: Paint -

TRIM: Casing B, Wood, Stained -

SPECIALTY:

Vanity:

Granite Countertop and splashes-

Wood apron, paint -

Undermount sink -

Decorative wood framed mirror -

INTERIOR FINISH SCHEDULE
ROOM NAME: Prefunction, Vestibule
ROOM NUMBER: B009, B009A

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CPT 2
CPT 3- At vestibule B009A

BASE: Base C, Wood, Stained-

WALLS:

Above Chair Rail, VWC -
Below Chair Rail, VWC -

DOORS: Stained-

CEILING: Paint -

TRIM: Crown B, Wood, Stained –
Chair Rail A, Wood, Stained -
Casing B, Wood, Stained -
Decorative door header, stained-

SPECIALTY:

Decorative door header at auditorium entrances and Men's and Women's Restrooms.

INTERIOR FINISH SCHEDULE

ROOM NAME: Auditorium, Platform, Meditation Room
ROOM NUMBER: B012, B008, B015

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CPT-2 – Auditorium, Meditation Room
Wood Flooring 1- Armstrong, Performance Plus, Natural Oak, ESP5200.
At Stage and Stairs

BASE: Base C, Wood, Stained-

WALLS:

Paint -

Acoustical Wallcovering - National Wallcovering, 1" EcoCore acoustical board by vertical interior solutions. Contact Whitney Treadwell for pricing. (703) 216- 5618.

VWC – At Meditation Room

DOORS: Stain -

CEILING: T&G Wood Ceiling, Stain -
ACT B –
Paint -

TRIM: Casing B, Wood, stained -

SPECIALTY:

Exposed trusses:
Stained wood -

Flat Panel trim around acoustical panels.
Stained wood-

INTERIOR FINISH SCHEDULE

ROOM NAME: Dressing Room

ROOM NUMBER: B007

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: SV-1 - Altro Flooring, Maxis unity

BASE: Vinyl

WALLS:

Paint-

DOORS: Paint

CEILING: ACT B -

TRIM:

Casing B, Wood, Paint-

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Mech., Storage, Elec/AV, BOH Corridor

ROOM NUMBER: B001A, B012A, B012B, B012C, B013, B019.

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT -
SV-1 - Altro Flooring, Maxis unity – at BOH Corridor B013
CPT-3 Walk off Mat - at BOH Corridor B019

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: ACT-B
Paint -

TRIM:

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Equipment Storage, Bolier

ROOM NUMBER: B005, B016, B024

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: Sealed Concrete

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -

TRIM:

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Toilet

ROOM NUMBER: B006

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: SV-1 - Altro Flooring, Maxis unity

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -

TRIM:

SPECIALTY:

Vanity:
Solid Surface, Countertop -

INTERIOR FINISH SCHEDULE

ROOM NAME: Resident Storage

ROOM NUMBER: B023

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: ACT-B

TRIM:

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Elevators

ROOM NUMBER: 1, 2

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CT4 - Daltile, Continental Slate, 12x12

BASE: CT4 - Daltile, Continental Slate, 6x12 cove base.

WALLS:

Manufactures upgraded wall panel system. Stained wood paneling, no plastic laminate.

DOORS: Stainless steel- Brushed finish

CEILING: LED Lighting

TRIM: Handrail- Stainless Steel - Brushed finish

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Stairs 1,2

ROOM NUMBER: B017, B021, 0002, 0015, 1002, 1015, 2015, 3001, 3015

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT-4

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -

TRIM: Handrail- Paint

SPECIALTY:

INDEPENDENT LIVING

RESIDENTIAL LEVELS 0 -3

INTERIOR FINISH SCHEDULE

Beacon Hill

ROOM NAME: Resident Units

DATE: 4/6/15

ROOM NUMBER: Level 0 - 0004-0009, 0013-0014, 0016-0019, 0021-0023

REVISED:

Level 1 1004-1009, 1013-1014, 1016-1019, 1021-1022

Level 2 2004-2009, 2013-2014, 2016-2019, 2021-2023

Level 3 3004-3009, 3013-3014, 3016-3019, 3021-3022

FLOOR: Hall/Living/Bedroom/Closets: CPT 1 - choice of 5 colors
Bathrooms/ Laundry : Ceramic Tile, Daltile Sandalo or Brixton CT1 - choice of 3 colors. Mosaic Tile, Daltile Sandalo or Brixton CT2 - choice of 3 colors.
Kitchen: Ceramic Tile, Daltile Franciscan Slate CT3- choice of 3 colors

BASE: Base B, Wood, painted -

WALLS:

Paint -

Shower Walls: WCT1

DOORS: Paint -

CEILING: Paint -

TRIM: Crown Molding, Paint-

SPECIALTY:
Kitchen & Bath cabinetry:
Merillat: Maple, Seneca Ridge Square. Residents to select from finishes:
Chiffon, Pecan, Sedona, Toffee, or Kona

Granite Countertops Kitchen & Bath:
Residents to select from colors:
Bianco Romano , Tropical Brown, or Giallo Veneziano
Decorative Wood framed mirror:

Note: Follow IL marketing office for appliances, fixtures, faucets, light fixtures.

INDEPENDENT LIVING

RESIDENTIAL LEVEL 0

INTERIOR FINISH SCHEDULE

ROOM NAME: Residential Corridors, Elevator Vestibule

ROOM NUMBER: 0001, 0011, 0012

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT-2

BASE: Base A, Wood, paint -

WALLS:

Above Lean Rail: VWC -

Below Lean Rail: VWC -

DOORS: Paint -

CEILING: Paint -
ACT-A

TRIM: Crown A, Wood, Paint -
Casing B, Wood, Paint-
Lean Rail, Paint -

SPECIALTY:

Package Shelf: (Unit Entry to match existing)

Top: Granite -

Apron: Wood, Paint -

INTERIOR FINISH SCHEDULE

ROOM NAME: Resident Storage

ROOM NUMBER: 0003

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: ACT-B

TRIM:

SPECIALTY:

INTERIOR FINISH SCHEDULE
ROOM NAME: Elec., Tele., Janitor
ROOM NUMBER: 0011A, 0011B, 0020

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -
ACT B -

TRIM:

SPECIALTY:

INDEPENDENT LIVING

RESIDENTIAL LEVEL 1

INTERIOR FINISH SCHEDULE

ROOM NAME: Dining, Wait Station

ROOM NUMBER: 1101, 1103

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT -2
CT- 5 Daltile, Quarry Textures, 6x6, seal, use black grout. (At Wait Station 1103)

BASE: Base C, Wood, Stained - (to match existing dining room)

WALLS:

Above Chair Rail: Wainscot wood paneling, stain - (to match existing dining room)

Below Chair Rail: Wainscot wood paneling, stain – (to match existing dining room)

Columns – Raised panel, stain- to match existing in IL Commons

NORTH WALL: Decorative stone wall – to match existing stone in IL Commons

Paint – at wait station

DOORS: Stained -

CEILING: Inside coffered ceiling, wood- Stained (to match existing dining room)
Soffit, Paint -

TRIM: Crown A, Wood, Stained - (to match existing dining room)
Chair Rail A, Stained - (to match existing dining room)
Casing B, Wood, Stained - (to match existing dining room)

SPECIALTY:

Buffet:

Stained wood:

to match existing dining room, in style and finish.

Granite countertop:

Approximately 8" in length.

INTERIOR FINISH SCHEDULE

ROOM NAME: Private Dining

ROOM NUMBER: 1102

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT -2

BASE: Base C, Wood, Stained - (to match existing dining room)

WALLS:

Above Chair Rail : VWC -

Below Chair Rail: VWC -

DOORS: Stained - (to match existing dining room)

CEILING: Painted -

TRIM: Crown A, Wood, Stained- (to match existing dining room)
Casing B, Wood, Stained - (to match existing dining room)
Chair Rail A- Stained (to match existing dining room)

SPECIALTY:

Buffets:

Stained wood

to match existing dining room, in style and finish

Granite Countertop:

Buffets will fill up entire wall that backs to dining room.

INTERIOR FINISH SCHEDULE

ROOM NAME: Club Room

ROOM NUMBER:

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT -2

BASE: Base C, Wood, Paint -

WALLS:

Above Chair Rail : VWC -
Below Chair Rail: VWC -

DOORS: Paint -

CEILING: Paint -

TRIM: Crown A, Wood, Paint -
Casing B, Wood, Paint -
Chair Rail A- Paint -

SPECIALTY:

Custom Millwork:
Cabinetry – to match existing IL commons style and finish.
Countertop: Granite
Under counter fridge – ADA accessible fits under 34” counter, stainless steel

Golf Simulator – Use existing

INTERIOR FINISH SCHEDULE

ROOM NAME: Residential Corridors, Elevator Vestibule

ROOM NUMBER: 1001, 1011, 1012

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT-2

BASE: Base A, Wood, paint -

WALLS:

Above Lean Rail: VWC -

Below Lean Rail: VWC -

DOORS: Paint -

CEILING: Paint -
ACT-A

TRIM: Crown A, Wood, Paint -
Casing B, Wood, Paint -
Lean Rail, Paint -
Decorative door header, paint -

SPECIALTY:

Package Shelf: (Unit Entry) to match existing

Top: Granite -

Apron: Wood, Paint -

INTERIOR FINISH SCHEDULE

ROOM NAME: Mail
ROOM NUMBER: 1003

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CPT-2

BASE: Base A, Wood, painted -

WALLS:

VWC -

DOORS: Paint -

CEILING: Paint -

TRIM: Crown A, Wood, Paint-

SPECIALTY:

Millwork: Work Surface Island
Cabinetry – Raised wood panels, painted
Hardware –
Worksurface – Granite

Message Board:
10” Granite shelf below message board –
Wood framed cork board –

INTERIOR FINISH SCHEDULE

ROOM NAME: Men's and Women's Restroom

ROOM NUMBER: 1024, 1025

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CT-4 - Daltile, Continental Slate, 12x12

BASE: CT-4 - Daltile, Continental Slate 6x12 cove base

WALLS:

WCT4 - Wainscot with decorative tile/glass border
Daltile, Continental Slate, 12x12 w/ architectural ceramics, Skyline linear border.
Border is 12" in height, overall wainscot is floor to 48" a.f.f

VWC above wainscot -

DOORS: Paint -

CEILING: Paint -

TRIM: Casing B, Wood, Paint -

SPECIALTY:

Vanity:

Granite Countertop and splashes-

Wood apron, paint -

Undermount sink -

Decorative wood framed mirror -

INTERIOR FINISH SCHEDULE

ROOM NAME: Resident Storage

ROOM NUMBER: 1023

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: ACT-B

TRIM:

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Electrical, Tele., Passageway

ROOM NUMBER: 1011A, 1011B, 1002A

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -

TRIM:

SPECIALTY:

INDEPENDENT LIVING

RESIDENTIAL LEVEL 2

INTERIOR FINISH SCHEDULE

ROOM NAME: Residential Corridors, Elevator Vestibule
ROOM NUMBER: 2001, 2011

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CPT-2

BASE: Base A, Wood, paint -

WALLS:

Above Lean Rail: VWC -
Below Lean Rail: VWC -

DOORS: Paint -

CEILING: Paint -
ACT-A

TRIM: Crown A, Wood, Paint -
Casing B, Wood, Paint-
Lean Rail, Paint -

SPECIALTY:

Package Shelf: (Unit Entry) to match existing
Top: Granite -
Apron: Wood, Paint -

INTERIOR FINISH SCHEDULE

ROOM NAME: Resident Storage

ROOM NUMBER: 2003

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: ACT-B

TRIM:

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Electrical, Tele. Communications, Janitor

ROOM NUMBER: 2011A, 2011B, B032

Beacon Hill

DATE: 4/6/15

REVISED

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -

TRIM:

SPECIALTY:

INDEPENDENT LIVING

RESIDENTIAL LEVEL 3

INTERIOR FINISH SCHEDULE

ROOM NAME: Resident Storage

ROOM NUMBER: 3003

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: ACT-B

TRIM:

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Residential Corridors, Elevator Vestibule
ROOM NUMBER: 3012, 3011

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CPT-2

BASE: Base A, Wood, paint -

WALLS:

Above Lean Rail VWC -
Below Lean Rail: VWC -

DOORS: Paint -

CEILING: Paint -
ACT-A

TRIM: Crown A, Wood, Paint -
Casing B. Wood, Paint-
Lean Rail, Paint -

SPECIALTY:

Package Shelf: (Unit Entry) to match existing
Top: Granite -
Apron: Wood, Paint -

INTERIOR FINISH SCHEDULE

ROOM NAME: Electrical, Tele. Communications, Janitor

ROOM NUMBER: 3011A, 3011B, 3023

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -

TRIM:

SPECIALTY:

INDEPENDENT LIVING

OFFICE RENOVATION

INTERIOR FINISH SCHEDULE

ROOM NAME: Reception, Coffee Station, Corridor
ROOM NUMBER: 111A

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CPT - 2

BASE: Base C, Wood, paint -

WALLS:
VWC-

DOORS: Paint -

CEILING: ACT A -

TRIM: Casing B, Wood, Paint-
Crown B, Wood, Paint-

SPECIALTY:

Coffee Station:
Cabinetry- Merillat, Seneca Ridge, maple, finish TBD.
Plastic Laminate countertop -

INTERIOR FINISH SCHEDULE

ROOM NAME: Offices

ROOM NUMBER: 121, 122

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT - 2

BASE: Base C, Wood, paint -

WALLS:
Paint

DOORS: Paint -

CEILING: ACT A -

TRIM: Casing B, Wood, Paint-
Crown B, Wood, Paint-

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Conference Room

ROOM NUMBER: 115

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT - 2

BASE: Base C, Wood, paint-

WALLS:

Above Chair Rail: VWC -

Below Chair Rail: VWC -

DOORS: Paint -

CEILING: Paint -
ACT A-

TRIM: Casing B, Wood, Paint-
Crown B, Wood, Paint-

SPECIALTY:

INTERIOR FINISH SCHEDULE

ROOM NAME: Work Room

ROOM NUMBER: 111

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: VCT

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: ACT B -

TRIM:

SPECIALTY:

Cabinetry:
Merillat, Seneca Ridge, maple, finish TBD
Plastic Laminate countertop -
Full height refrigerator.

INTERIOR FINISH SCHEDULE

ROOM NAME: Toilet
ROOM NUMBER: 111B

Beacon Hill
DATE: 4/6/15
REVISED:

FLOOR: CT-4 - Daltile, Continental Slate, 12x12

BASE: CT-4 - Daltile, Continental Slate 6x12 cove base

WALLS:

WCT4 - Wainscot with decorative tile/glass border
Daltile, Continental Slate, 12x12 w/ architectural ceramics, Skyline linear border. Border is 12" in height, overall wainscot is floor to 48" a.f.f

VWC above wainscot -

DOORS: Paint-

CEILING: Paint -

TRIM: Casing B, Paint -

SPECIALTY:

Vanity:
Granite Countertop and splashes-
Wood apron, paint -
Undermount sink -
Decorative wood framed mirror -

INTERIOR FINISH SCHEDULE

ROOM NAME: Coat Closet

ROOM NUMBER: 116

Beacon Hill

DATE: 4/6/15

REVISED:

FLOOR: CPT 2 -

BASE: Vinyl

WALLS:

Paint -

DOORS: Paint -

CEILING: Paint -

TRIM:

SPECIALTY: