Solar Bankability Final Workshop 8th February 2017 – Session 3



Best Practices Guidelines for EPC and O&M



Caroline Tjengdrawira (3E)





TÜVRheinland® Precisely Right.





Funded by the Horizon 2020 Framework Programme of the European Union

www.solarbankability.eu

Presentation Outline




- I. Lifecycle costs and related risks in PV investment financial model
- II. Gaps in EPC and O&M technical aspects
- III. Best-practice guidelines for EPC and O&M contracting



Lifecycle Costs in PV Investment Financial Model EPC and O&M are Influential to CAPEX and OPEX



» CAPEX is dominant in
lifecycle costs
(75-90%)» Majority of CAPEX is
EPC
(70-90%)» Wide O&M range in
OPEX
(30-70%)



Data from surveys of

- 18 PV financial models (ground-mounted plants, FR-UK-DE-IT, 2011-2015)
- 8 EPC and O&M contracts (ground-mounted and rooftop plants, FR-UK-IT-NL, 2014-2016)
- 7 yield reports and scientific literature



Technical Inputs in EPC, O&M and Yield Estimation

Gaps Analysis in Technical Assumptions

Risk	Phase/field	Identified critical technical gaps
Year-0	Procurement/ product selection and testing	 Insufficient EPC technical specifications to ensure that selected components are suitable for use in the specific PV plant environment of application. Inadequate component testing to check for product manufacturing deviations. Absence of adequate independent product delivery acceptance test and criteria.
	Planning/ lifetime energy yield estimation	 The effect of long-term trends in the solar resource is not fully accounted for. Exceedance probabilities (e.g. P90) are often calculated for risk assessment assuming a normal distribution for all elements contributing to the overall uncertainty. Incorrect degradation rate and behavior over time assumed in the yield estimation. Incorrect availability assumption to calculate the initial yield for project investment financial model (vs O&M plant availability guarantee).
	Transportation	 Absence of standardized transportation and handling protocol.
	Installation/ construction	 9. Inadequate quality procedures in component un-packaging and handling during construction by workers. 10. Missing intermediate construction monitoring.
	Installation/ provisional and final acceptance	 Inadequate protocol or equipment for plant acceptance visual inspection. Missing short-term performance (e.g. PR) check at provisional acceptance test, including proper correction for temperature and other losses. Missing final performance check and guaranteed performance. Incorrect or missing specification for collecting data for PR or availability evaluations: incorrect measurement sensor specification, incorrect irradiance threshold to define time window of PV operation for PR/availability calculation.
Risks during operation	Operation	 Selected monitoring system is not capable of advanced fault detection and identification. Inadequate or absence of devices for visual inspection to catch invisible defects/faults. Missing guaranteed key performance indicators (PR, availability or energy yield). Incorrect or missing specification for collecting data for PR or availability evaluations: incorrect measurement sensor specification, incorrect irradiance threshold to define time window of PV operation for PR/availability calculation.
	Maintenance	 Missing or inadequate maintenance of the monitoring system. Module cleaning missing or frequency too low.

Gaps exist across all project phases

Data from surveys of

- 18 PV financial models (ground-mounted plants, FR-UK-DE-IT, 2011-2015)
- 8 EPC and O&M contracts (ground-mounted and rooftop plants, FR-UK-IT-NL, 2014-2016)
- 7 yield reports and scientific literature

Gaps in EPC Contracting Year-0 Risks

SOLAR BANKABILITY

Procurement, Product Selection and Testing

- Insufficient EPC technical specifications for major plant components
- Inadequate component testing
- Absence of product acceptance

Transportation

Absent standard protocol for transport and handling

Construction

- Inadequate protocol for component handling by workers
- Missing construction monitoring



Gaps in EPC Contracting

Year-0 Risks

SOLAR BANKABILITY

Provisional and final acceptance

- Inadequate visual inspection protocol
- Missing/incorrect short-term performance check at provisional acceptance
- Missing/incorrect final performance check
- Absence of guaranteed performance
- Missing/incorrect:
 - -Assumptions in performance calculation
 - Measurement sensor specification
 - Irradiance threshold



Gaps in O&M Contracting

Risks During Operation



Operation

- Inadequate monitoring system for advanced fault detection and identification
- Inadequate visual inspection protocol
- Absence of guaranteed performance
- Missing/incorrect:
 - Assumptions in performance calculation
 - Measurement sensor specification
 - Irradiance threshold


Maintenance

- Missing/inadequate monitoring system maintenance
- Module cleaning missing or frequency too low



PV Financial Model – Technical Risks

Gaps in Technical Assumptions Leading to Technical Risks Impacting PV Investment Costs



plant outage \rightarrow lowering plant

availability and yield




SOLAR

BANKABILITY

Managing PV Technical Risks Technical Aspects in EPC and O&M Contracts



Are important since they affect CAPEX, OPEX or yield.
 Need to be set up properly to minimize technical risks.



Best Practice Checklists

Tools to Minimize Technical Risks by Proper EPC and O&M Contracting and Yield Estimation

Three main checklists are:

- 1. Best Practice Checklist for EPC Technical Aspects
- 2. Best Practice Checklist for O&M Technical Aspects
- 3. Best Practice Checklist for Long-Term Yield Assessment

Three supplementary checklists are:

- 4. Checklist for As-Build Documents Type and Details
- 5. Checklist for Record Control
- 6. Checklist for Reporting Indicators



SOLAR

BANKABILITY



Best-Practice for EPC and O&M Contracting

Technical Aspects & What to Look for in The Contracts

EPC contract

- A Definitions, interpretation
- **B** Contractual commitments
- **C** Scope of works engineering
- **D** Scope of works procurement
- **E** Scope of works construction
- F Scope of works administrative and others
- **G** Manufacturer warranties
- H EPC warranty and Defect Liability Period (DLP)
- I Key performance indicators (KPIs) and guarantees
- J Commissioning and acceptance

O&M contract

- A Definitions, interpretation
- **B** Purpose and responsibilities
- **C** Scope of works environmental, health and safety
- D Scope of works operations
- **E** Scope of works maintenance
- F Scope of works data and monitoring
- **G** Scope of works spare parts management
- H Scope of works plant security
- I Key performance indicators (KPIs)
- J Contractual commitments



Best Practice Checklists

Online at www.solarbankability.eu



Best Practice Guidelines for PV **Cost Calculation**

Accounting for Technical Risks and Assumptions in **PV LCOE**

Deliverable D3.2 13/12/2016



nded by the Horizon 2020 mework Programme of the ean Union

www.solarbankability.eu



C.4. Checklist for As-Build Documents - Type and Details

Annex C - Best Practice Checklists

C.1. Best Practice Checklist for EPC Technical Aspects

4. Date of ownership and risk transfer are defined and acceptable

Construction start date and end date are defined and acceptable
 Plant Commercial Operation Date (COD) is defined and in line with

7. The EPC works should be carried in compliance with (non-exhaustive list)

3. Responsibility and accountability

dates

8

0

This annex presents 6 checklists which are aimed for use for utility-scale (ground-mounted) and commercial coothop PV installations. The checklists for residential systems are presented in the report Technical Bankabity Guidelines - Recommendations to Enhance Technical Quality of PV

No.	Minimum Requirements	Description
1	Site information	Loadon Imar / 0/9 Continues Phart access / the off Continues Access mask CoMM loading Sprey park stragg / maximboxe Source parks Source parks
2	Project drawings	Peet toput and general ansegment Cable holds generation Cable holds generation Cable holds and Cable holds Cable holds and Cable holds Cable
3	Project studies	Shaling study / simulation Energy yield study / simulation Inverter sizing study
4	Studies according to national regulation requirements	Voltage drep calculations Protection operationals Shord insult study Graunding study Graunding study Cable sing calculations Lighting preferibien study
5	PV modules	Datasheets Datasheets Datasheets Datash lat with PV modules positioning in the field (reference to string numbers and positioning in the string) Warranties and certificates
6	Inverters	OMM menual Commissioning report Warrantise and certificates Factory Acceptance Test Invotor sottinus



C.2. Best Practice Checklist for O&M Technical Aspects Is there a set of defini 2. Is the fun emental purpose (goals) of the o 3. Are the roles and responsibilities (and boundary conditions) of the mu contract clear and understood Scope of works - environ Note: The Asset Owner has the ultimate legal and amand the solar plant and for the protection of the subcontracted to the OBM contractor. 0 · Regular inspection of tra Recycling of broken panels and electric wash · Sensible water usage for module cleaning · Proper environmental management pl 5. Health and safety (HBS) Property controlled access and supervision in the solar restrictions Proper induction to ensure awareness of risks and haz · Proper training and certification on the specifics of a PV plant and voltage level Hazard identification/marking · Wiring sequence marking

- receip angework manage
 HSS legislation manage
 HSS legislation calable
 Extellished personal preserve expenses (PPE) (not exhaustive ket); solve press, which is defined proves), stack and glasses
 (objecting on the six), fire returbated and/or ant fash rated PPE where increasary · Calibrated and certified equipment full documentation available)

e of works - operations 6. Documentation Management System (DSM As-built documentation / IEC62446 (see Annex C.4)



C.5. Checklist for Record Control

No.	Activity Type	Information Type	Input Record		
1	Alarms / operation incidents	Alarms description	Date and time, affected power, equipment code / name, error messages / codes, seventy classification, curtailment period, external visits / inspections from third parties		
2	Contract management	Contract general description	Project name / code, client name, peak power (kWp)		
3	Contract management	Asset description	Structure type, installation type		
4	Contract management	Contract period	Contract start and end date		
5	Contract management	Contractual clauses	Contract value, availability (%), PR (%), materials / spare parts, corrective work labor		
6	Corrective maintenance	Activity description	Detailed takine typification, takine, fault status, problem resolution description, problem cause (*)		
7	Corrective maintenance	Corrective maintenance event	Associated alarms (with date), event status (*)		
	Corrective maintenance	Corrective maintenance event log	Date and time of corrective maintenance creation (o work order), date and lime status change (pending, open, recovered, dose), and date and time of the intervention, start date and time of the intervention, technologies and responsible names and forction (7)		
9	Corrective maintenance	Intervention equipment / element name	Affected power and affected production, equipment code / name		
10	Inventory reanagement	Warehouse management	Inventory stock count and movement, equipment code / name		
11	Monitoring and supervision	Equipment status	Date, status log (protection devices, inverters, monitoring systems, surveillance systems)		
12	Monitoring and supervision	Meteo data	Irradiation, module temperature, other meteo variable (ambient temperature, air humidity, wind velocity and direction,) (**)		
13	Monitoring and supervision	Production / consumption data	AC active and reactive power at PV plant injection po and offset subsystems or equipment, consumption the auxiliary systems, other variables (DCIAC voltages a currents, thequeercy), power from DC field (**)		
54	Monitoring and supervision	Performance data	PV plant energy production; PR; expected vs real		
15	Preventative maintenance	Intervention equipment / element name	Affected power and affected production, equipment code / name, intervention start and end date		
16	Preventative maintenance	Maintenance description	Measurements, preventative maintenance tasks performed, problems not solved during activity and its		



1/08		
٨	Solar	esource assessment
	1.	Only reliable solar imadiation data sources should be used and the name(s) and version(s) must be clearly stated. Data source(s) used must be able to provide uncertainty estimations and ideally have been extensively validated.
	2.	The period covered by the solar intellation data source(s) used must be reported. Only data sources with more than 10-year recent data should be used for LTYA calculations
	3.	The effect of long-term trends in the solar resource should be analyzed. In the presence of such trends, the long-term solar resource estimation should be adjusted to account for this effect.
	.4.	The use of site adaptation techniques is recommended to reduce the uncertainty. A measurement campaign of at least 8 months and ideally one full year is recommended
8	PV yie	id modeling
	5.	The PV modeling software and the specific version used must be clearly stated in the report
	6.	If in-house software is used, the name(s) and version(s) must also be stated
-	7.	All assumptions (e.g. solling losses, availability, etc.) and sub-models used (e.g. transposition model) must be clearly stated
ç	Degra	dation rate and behavior
		The degradation rate(s) used for the calculations must be clearly stated in the report. It is recommended to differentiate between first year effects and yearly behavior over project lifetime
	9.	Degradation behavior assumption (e.g. linear, stepwise, etc.) over time should be clearly stated an ideally backed up with manufacturer warranties
2	10	If specific manufacturer warranties are available (e.g. module warranty document or sales agreement), these can be used to fine tune the lifetime degradation calculation
0	Uncer	ainty calculation
2		All steps in the long-term yield calculation are subject to uncertainties. All uncertainties should be clearly stated and references must be provided in the report
	12	Special attention must be paid to the solar resource related ancertainties as these are among the most important elements in the contribution to the overall uncertainty.
-	13	If special methods are used to reduce some uncertainties e.g. site adaptation techniques, these should be clearly documented and ideally backed up with scientific validation
	14.	Special care must be taken when classifying each uncertainty as either systematic or variable (stochastic) since these are treated differently in overall lifetime uncertainty calculations
	. 15	When possible, exceedance probabilities (e.g. P90) for each uncertainty must be calculated using empirical methods based on available data instead of assuming normal distribution for all elements

C.6. Checklist for Reporting Indicator

	Reporting Indicators						
No.	Proposed Indicator	Predicted	Measured	Estimated			
1	Insolation	•	•				
2	Active energy produced	•	•	×			
3	Active energy consumed		×				
4	Reactive energy produced		×				
5	Reactive energy consumed		×				
6	Peak power achieved		×				
7	Performance Ratio	•	•	×			
8	Energy Performance Index			~			
9	Balance of system efficiency			 			
10	Plant external energy losses			~			
11	Plant internal energy losses			×			
12	Energy-based availability			×			
13	Time-based availability			~			
14	Inverter specific energy losses			4			
15	Inverter specific efficiency			~			
16	Module solling losses		×				
17	Module degradation			×			

SE

E

Technical Risk Flash Cards

Online at www.solarbankability.eu

Categorization based on:

- Risk impacts CAPEX/OPEX/yield
- Risk mitigation impacts on CAPEX/OPEX/yield

Risk flash cards with following info:

- Description of the risk,
- Phase at which the risk occurs,
- Key takeaway of the risk,
- Mitigations,
- Risk and mitigation impacts on LCOE

Best Practice Guidelines for PV Cost Calculation

Accounting for Technical Risks and Assumptions in PV LCOE

Deliverable D3.2 13/12/2016



Ris					Dharo	of risk occurren		
<u>Ki</u>	Risk		fficient EPC technical specif		_	Phase of risk occ		
<u>Ke</u>	Risk Key		Insufficient EPC technical sp 1. Insufficient EPC technic that selected components specific PV plant environn	al specifications to are suitable for use	ensure		k occurrence Planning Constructio	
Im F Mi	Imp	Key takeaway PV plant component specification and requirement in the EPC contract should be as detail as possible to ensure that the components procured are suited for the intended PV installation specific application, site and environment						
E	Mit	Impact of risk LCOE variables impacted by the second		his risk: CAPEX OPEX Yield V				
	Imp mit Imp		Advanced inspection Visual inspection Visual inspection Vield/performance test	 The environme be installed in snow load, any corrosion risk of For PV module materials and 	mark of compliance for all electrical components) The environmental condition the components will be installed in (temperature, humidity, wind and snow load, any special chemical exposure, corrosion risk etc.) For PV modules, module component bill of materials and the proof of IEC certification documents for these materials			
	mit		LCOE variables impacted by the mitigations:	e risk	CAPEX	OPEX	Yield	



Reports Online at <u>www.solarbankability.eu</u>





Review and Gap Analyses of Technical Assumptions in PV Electricity Cost Report on Current Practices in How Technical Assumptions are Accounted in PV Investment Cost Calculation



Deliverable D3.1 report

 "Review and Gap Analyses of Technical Assumptions in PV Electricity Cost – Report on Current Practices in How Technical Assumptions are Accounted in PV Investment Cost Calculation"

Best Practice Guidelines for PV Cost Calculation Accounting for Technical Risks and Assumptions in PV LCOE 13/122016



Deliverable D3.2 report

 "Best Practice Guidelines for PV Cost Calculation – Accounting for Technical Risks and Assumptions in PV LCOE"

Thank you

PRESENTED BY Caroline Tjengdrawira ctj@3e.eu





This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 649997. The content of this report reflects only the author's view and the Commission is not responsible for any use that may be made of the information it contains



Funded by the Horizon 2020 Framework Programme of the European Union

www.solarbankability.eu