



Cisco Collaboration Endpoint Software 9

Release notes

D15373.71

May 2022

Contents

Contents	2
Document revision history	15
Introduction to Collaboration Endpoint Software 9	19
Cisco Terms of Service	19
Permitted Commercial Use for Scheduled Meeting Join Experience:.....	19
Webex Certified and Webex Compatible vendors	20
Important notes and warnings for this software version	20
Equipment and feature considerations before upgrading to Collaboration Endpoint Software 9... 20	
CE9.15.3.x is the last software release for Room, Board and Desk series	20
WiFi Connection Consideration	21
CE9.15.X.x is the final software pipeline for SX, MX and DX series and will eventually no longer support Room, Board and Desk series	21
WebRTC calling will require RoomOS 10 after CE9.15.0.x.....	22
Filenames will change starting in CE9.15.3.17	22
COP Files added to support UCM 14.x release starting in CE9.14.6.....	22
CE9.15.X.x only supports CMS 2.8 and above	22
Notice of upcoming change in remote communication ports used for touch panels with CE9.14.3	23
CE9.13.0 – Deprecated settings are no longer persistent when upgrading and downgrading	23
CE9.12.3 – Webex Edge for Devices and CE9.10.x for new customers.....	23
CE9.12.3 – SpeakerTrack not working using Cisco TelePresence SX80 and Cisco Webex Quad Camera.....	24
CE9.10.0 – Default SNMP configuration	24
CE9.9.0/CE9.8.1 and below – Recommended upgrade path for Webex Room Systems	24
CE9.6.0 for Cisco Webex Room Kit Mini	26
CE9.6.1 – Audio Console.....	26
CE9.4.0 - Default value HTTP+HTTPS is changed to HTTPS.....	26
Briefing Room does not work as expected	26
CE9 - Notice of Deprecation: MultiStream with Cisco TelePresence Server	27
CE9.2.0 for Cisco Webex Room 70 and Room 70 Dual.....	27
Software Upgrade	28
Upgrading using the web interface	28

Upgrading using CUCM	29
Upgrading using TMS	29
Upgrading using the xAPI	29
Camera firmware	30
Camera support	35
Deferred software versions	37
Software and deferral policy	37
CE9.15.3.x deferred	37
CE9.12.x, 9.13.x, 9.14.x, 9.15.0.x deferred	38
CE9.14.3 and CE9.14.4 is deferred due to an audio processing issue with Cisco Room Panorama 70.....	38
CE9.9, CE9.10, CE9.12.3 and CE9.13.0 is deferred	38
CE9.x up to and including CE9.9.1 is deferred	38
CE9.0.1 deferred due to bug CSCvf27027	38
CE9.1.1 deferred due to bug CSCve94476	38
CE9.1.2 deferred due to potential issues with peripherals upgrade	38
CE9.1.3, CE9.1.4 deferred due to WPA2 (KRACK) vulnerability	39
CE9.1.3, CE9.1.4, CE9.1.5, CE9.2.1, CE9.2.2, CE9.2.3, CE9.2.4, CE9.3.0 deferred	39
New features and functionality in CE9.15.13.0	40
New features and functionality in CE9.15.3.26	41
New features and functionality in CE9.15.10.8	42
New features and functionality in CE9.15.8.12	43
New features and functionality in CE9.15.3.25	44
New features and functionality in CE9.15.3.22	45
New features and functionality in CE9.15.3.18	46
New features and functionality in CE9.15.3.17	47
New feature and functionality descriptions CE9.15.3.17.....	48
CMS Raise Hand	48
Background noise removal	48
Whiteboard shape support	48
Share WebApps in call	48

Webex Edge for Devices updates	49
Direct ad-hoc booking for Room devices	49
Complete keyboard language support	49
Known Issues	50
New features and functionality in CE9.15.0.19	51
New features and functionality in CE9.15.0.13	52
New features and functionality in CE9.15.0.11	53
New feature and functionality descriptions CE9.15.0.11.....	54
Web UI refresh	54
Support for upgrading the Cisco Webex Room Panorama and Room 70 Panorama displays from the web interface	54
Logs can now be anonymized when downloaded from the web interface	54
Ability to upload custom icons for the UI Extensions panel buttons	55
Background noise removal (BabbleLabs)	55
Support for admitting guests into locked CMS conferences	55
Floating toolbar for touch screen activities.....	55
Dark mode for whiteboard	56
Whiteboard overview	56
CUCM Call Management Records	56
Broadcast mode	57
Webex Edge for Devices updates	58
Cloud software upgrade	58
Webex Optimized Experience.....	59
New features and functionality in CE9.14.7	60
New features and functionality in CE9.14.6	61
New features and functionality in CE9.14.5	62
New feature and functionality descriptions CE9.14.5.....	63
Software support for Webex PTZ 4K	63
New features and functionality in CE9.14.4	65
New features and functionality in CE9.14.3	66

New feature and functionality descriptions CE9.14.3.....	67
Software support for Cisco Webex Room Navigator	67
Web UI visual updates	67
Pin participants as important in CMS calls.....	67
Music Mode	68
Mouse and keyboard re-direct (HID forwarding) for Desk Pro.....	68
Manual Camera Control for Cisco Webex Desk Pro and Board.....	68
Touch 10 on-screen button updates	69
Configurable cleanup of web data and whiteboards.....	70
Improved Wi-Fi setup UI.....	70
Call info in recent list	70
Webex Edge for Devices updates.....	71
Support for Microsoft Teams WebRTC and Cloud Video Interop (CVI).....	71
Upload logs to cloud via Webex Edge for Devices	71
Cloud Device API – Support for large body in command requests	71
SpeakerTrack View Limits.....	72
Other.....	72
Audio output may be noticeably louder after upgrade to CE9.14.3	72
New features and functionality in CE9.13.3	73
New features and functionality in CE9.13.2	74
New features and functionality in CE9.13.1	75
New features and functionality in CE9.13.0	76
New feature and functionality descriptions CE9.13.0.....	77
Collaboration Endpoint Software 9.13.0	77
Introduction.....	77
Added support for new products	77
Cisco Webex Room Panorama and Room 70 Panorama	77
Webex Edge for Devices updates.....	78
Support for Cisco Webex Control Hub configuration management.....	78
Easy join Webex Personal Meeting Rooms with user search	78
Real-time media metrics when joining Webex meetings	78
Upload custom virtual backgrounds for Cisco Webex Desk Pro	79
Use the PC input as a virtual background	79

Touch forwarding in-call for Webex Board	79
Improved Wi-Fi setup on Cisco Webex Room USB using the TRC 6 remote	79
Far End Camera Control (FECC) support when dialing into CMS (2.8) meetings	79
Add a custom text with time and data to a video stream for Room Devices	80
Bug fixes	80
New features and functionality in CE9.12.5	81
New features and functionality in CE9.12.4	82
New features and functionality in CE9.12.3	83
New feature and functionality descriptions CE9.12.3.....	84
Collaboration Endpoint Software 9.12.3	84
Introduction.....	84
Added support for new products	84
Cisco Webex Room USB	84
Cisco Webex Desk Pro	84
Support for using Cisco Webex Room Kit Mini with Samsung Flip	85
One-way whiteboard sharing in-call	85
Annotate everywhere	85
Webex Join Button: Easy join Personal Meeting Rooms (PMR) with suggestions from recent calls ...	85
HTTP Proxy support for Webex Edge for Devices.....	86
Touch forwarding in-call for Cisco Webex Desk Pro	86
Other changes	86
Hide Proximity notifications	86
Hide scheduled meeting titles	86
Manual zoom is increased from 3x to 5x for Cisco Webex Room Kit Mini, Room Kit and Room 55	87
Web UI improvements / changes	87
Bug fixes	87
New features and functionality in CE9.10.3	88
New features and functionality in CE9.10.2	89
New features and functionality in CE9.10.1	90
New features and functionality in CE9.10.0	91

New feature and functionality descriptions CE9.10.0	92
Webex Edge for Devices.....	92
Webex Edge for Devices prerequisites.....	93
Webex Join button	93
Other changes.....	94
New default password policy	94
Default self-signed certificate validity changed from 5 years to 1 year	94
Default SNMP Configurations	95
Added support for SpeakerTrack 60 for Codec Plus	95
New features and functionality in CE9.9.4	96
New features and functionality in CE9.9.3	97
New features and functionality in CE9.9.2	98
New features and functionality in CE9.9.1	99
New features and functionality in CE9.9.0	100
New feature and functionality descriptions CE9.9.0	101
Wired touch re-direct	101
Web Engine (Digital Signage, Web Views and Web Apps).....	102
Certificates	102
Digital Signage	102
API driven web views	102
Web Apps.....	103
Updates to the UI Extensions editor.....	103
Whiteboard feature additions	104
Create, edit, and move stickies on your whiteboards and annotations	104
New pen sizes available.....	104
Create copies of your whiteboard and annotations	104
Re-worked user interface for network settings.....	104
TLS Configuration Changes	104
API for fetching custom wallpaper and branding from external URL	105
Changes in ultrasound settings.....	105
New features and functionality in CE9.8.3	106

New features and functionality in CE9.8.2	107
New features and functionality in CE9.8.1	108
New features and functionality in CE9.8.0	109
New feature and functionality descriptions CE9.8.0.....	110
Support for Cisco Webex Board on-premises deployment.....	110
Switch from Webex to On-premises deployment.....	110
Infinite whiteboarding	112
Save whiteboards to e-mail.....	113
Touch 10 support	113
Known issues	113
Pre-installed list of Certificate Authorities (CA).....	113
Support for HttpClient GET / DELETE and PATCH requests.....	113
Added support for response body and headers.....	114
Add participant to CMS conference from the device UI	114
xAPI over WebSocket: Authentication using auth protocol header	115
USB Headset support for Cisco Webex Room Kit Mini, Room Kit, and Room 55	116
xCommand for Webex device activation.....	116
Support for activating a device to Webex through the web interface	117
Improved USB experience with Room Kit Mini	117
Support for more product specific configurations from CUCM 12.5 SU1	118
Other changes	118
New features and functionality in CE9.7.2	119
New features and functionality in CE9.7.1	120
New feature and functionality descriptions CE9.7.1.....	121
xAPI over WebSocket (XoWS).....	121
Privacy mode – disable or enable video in a call	121
Room Analytics – Ambient Noise reporting	122
Room Kit Mini – Support for 1080p video while used as a USB camera.....	122
Edit favorites in OSD (DX70 and DX80)	122
Support for connecting multiple Sony cameras (SRG/EVI)	122
Audio Console – Graphical Equalizer	123
New features and functionality in CE9.6.4	124

New features and functionality in CE9.6.3	125
New features and functionality in CE9.6.2	126
New features and functionality in CE9.6.1	127
New feature and functionality descriptions CE9.6.1	128
Support for Cisco Webex Room Kit Mini.....	128
Custom HTTP POST and PUT through xAPI and Macros	128
In-Room Control: Third-party USB input devices.....	129
Hide default GUI panel buttons	131
Edit favorites directly from the Touch 10.....	132
Support for HDCP on additional room devices	132
Audio Console updates	133
ICE support in MRA scenarios	134
Active Control: Ability to start a recording from the UI in a CMS meeting	134
Other changes	134
New features and functionality in CE9.5.3	135
New features and functionality in CE9.5.2	136
New features and functionality in CE9.5.1	137
New features and functionality in CE9.5.0	138
New feature and functionality descriptions CE9.5.0.....	139
Feature preview: Audio Console	139
PresenterTrack support for Cisco Webex Codec Plus	139
Presentation source composition	140
New room mode: Classroom.....	141
Keyboard localization (Korean).....	141
Cisco TelePresence SX80 and SX20 screen status monitoring (CEC).....	141
Welcome banner in Web GUI and CLI.....	141
Rebranding from Spark to Webex.....	141
New features and functionality in CE9.4.2	142
New features and functionality in CE9.4.1	143
New features and functionality in CE9.4.0	144

New feature and functionality descriptions CE9.4.0	145
Support for Cisco Webex Room Kit Pro.....	145
Rebranding from Spark to Webex in GUI	145
Re-styled time zone and language settings in GUI.....	145
Support for content sharing using H.263 in a call between Cisco Webex Room Series and legacy MXP devices	145
Increase max number of simultaneous paired Cisco Proximity clients with Cisco Webex Room Series	146
CUCM provisioning of the admin settings lockdown configuration	146
Support for Sony SRG-120DH and EVI-120DH.....	147
Enable manual backlight compensation in GUI for DX series	148
Changed default HTTP mode from HTTP+HTTPS to HTTPS.....	148
New features and functionality in CE9.3.3	149
New features and functionality in CE9.3.2	150
New features and functionality in CE9.3.1	151
New features and functionality in CE9.3.0	152
New feature and functionality descriptions CE9.3.0	153
Backup and restore settings and custom elements	153
Getting started	153
Restore or provision across multiple room devices	153
TMS provisioning	154
UCM customization provisioning.....	154
Checksum verification	155
Other information	155
In-Room Control Updates	155
Support for ISDN Link	156
One Button to Push (OBTP) Snooze	156
SX10 Screen status monitoring (CEC)	156
Adjust call rate before making a call	157
Select ringtone and adjust ringtone volume	157
Other changes.....	157
Resume a postponed upgrade.....	157
Hide sensitive information in the UI	157
Accessibility: Flashing screen on incoming calls	157

Mirrored self-view on Cisco Webex DX Series	158
New features and functionality in CE9.2.6	159
New features and functionality in CE9.2.5	160
New features and functionality in CE9.2.4	161
New features and functionality in CE9.2.3	162
New features and functionality in CE9.2.2	163
New features and functionality in CE9.2.1	164
New feature and functionality descriptions CE9.2.1	165
Macro Framework for customized endpoint behavior	165
Designed to work with In-Room Controls	165
Supported systems (Macro framework)	165
HDCP Support for Cisco Webex Room 55	166
Branding and halfwake customization	166
Halfwake.....	166
Awake.....	167
Supported systems (Branding)	167
Source composition	168
Supported systems	168
HTTP Proxy support.....	168
Touch 10 and On-screen UI features.....	169
Admin settings lockdown in UI	169
Snap to whiteboard configuration re-instated	169
IEEE 802.1x configuration UI	169
Keyboard localization (Russian, Arabic and Hebrew)	169
Right to left language support (Arabic and Hebrew).....	169
Support for Cisco TelePresence SX80 with Cisco Webex Quad Camera.....	170
Certificate upload through xAPI	170
Trigger custom input prompt through xAPI	170
USB to Serial port support for Cisco Webex Room Kit, Room Kit Plus and Room 55	170
Mute remote participants in a CMS hosted conference (Active Control).....	170
In-Room Control	171
Widgets	171

Preview mode.....	171
Briefing Room.....	172
Other features or changes	172
Removed Intelligent Proximity indicators and UI toggle	172
Changing the device activation from the UI will reset some of the system configurations.....	172
New features and functionality in CE9.1.6	174
New features and functionality in CE9.1.5	175
New features and functionality in CE9.1.4	176
New feature and functionality descriptions CE9.1.4.....	177
Support for Cisco Webex Room Kit Plus + Precision 60	177
New features and functionality in CE9.1.3	178
New features and functionality in CE9.1.2	179
New features and functionality in CE9.1.1	180
New feature and functionality descriptions CE9.1.1.....	181
Support for Cisco Webex Room Kit Plus	181
Cisco Webex Quad Camera speaker tracking.....	181
Feature parity with Cisco Webex Room Kit	181
Dual Screen Experience for CMS based meetings	182
Active control.....	182
Supported video systems.....	182
New wakeup experience	183
Bluetooth headset support for Cisco Webex DX70 and DX80	184
Bluetooth controls	184
Wi-Fi: WPA-EAP	185
Trusted CA certificates.....	185
Minor changes.....	185
Additions for Room Analytics	185
Configuration to disable the secondary network port on Cisco Webex DX70 and DX80.....	186
New features and functionality in CE9.0.1	187
New feature and functionality descriptions CE9.0.1.....	188

Support for Cisco Webex Room Kit	188
Speaker tracking	188
Best overview	188
Wi-Fi support	189
Room Analytics	189
Support for upgrading firmware with COP files.....	189
Updated user interface “Activity Circles”	190
Touch 10 updates	190
New phonebook and share tray UI	191
Keyboard improvements on Touch 10 and Cisco Webex DX70/DX80	191
Call forward on Touch 10	191
Wakeup on motion detection.....	191
Improved In-Room Control editor	191
Minor changes	191
Support for HTTPS Client certificates	191
New Briefing Room controls	192
Local Contacts is now renamed to Favorites in the web interface	192
Added language: Portuguese	192
Open and resolved caveats in CE9	193
Using the Bug Search Tool	193
Known limitations and advisories.....	200
Limitations and advisories	200
Interoperability	213
H.323 gatekeepers/traversal servers	213
SIP registrars/proxies	213
Gateway interoperability	213
MCU interoperability	214
Streaming servers	214
Management servers.....	214
Endpoint Interoperability.....	215
Cameras	217
Cisco recommended screens for best interoperability	218
xAPI Changes	219

Cisco TelePresence systems hardware dependencies	220
Introduction.....	220
Peripherals hardware dependencies	224
New hardware revisions for Cisco TelePresence Touch 10.....	224
New hardware revisions for Cisco Webex Room Navigator.....	224
New hardware revisions for Quad Camera.....	225
New hardware revisions for Webex PTZ 4K.....	225
New hardware revisions for Precision 60	226
Latest software filenames	227
Software integrity verification	229

Document revision history

Revision	Date	Description
71	May 18 th 2022	Release of CE9.15.13.0.73ffba3d9ac, minor release
70	February 17 th 2022	Release of CE9.15.3.26.19885f27907, minor release
69	February 3 rd 2022	Release of CE9.15.10.8.2be98ff5c6e, minor release
68	December 17 th 2021	Release of CE9.15.3.25.4041d7b04a3, minor release
67	November 18 th 2021	Deferral policy addition for CE9.15.0.x
66	November 2 nd 2021	Release of CE9.15.8.12.7273b3b3e84, minor release
65	September 28 th 2021	Deferral policy addition for CE9.14.x Hardware revision table update for Quad Camera 73-100746-3 to minimum versions CE9.15.3.18 and CE9.14.7 Webex Control Hub configuration management section lists clarification that customizations will be ignored from provisioning system
64	September 10 th 2021	Release of CE9.15.6.step-upgrade.a242d057b6f, step upgrade release Updates to the Important notes and considerations section
63	August 24 th 2021	Added new hardware revision 73-100746-3 to Quad Camera table Minor corrections
62	June 24 th 2021	Release of CE9.15.3.22.8ebef840687, minor release
61	May 27 th 2021	Release of CE9.15.3.18.fd1dd3b86f9, minor release
60	May 19 th 2021	Release of CE9.15.0.19.d9646d0372b, minor release Release of CE9.14.7.6e216653a72, minor release
59	April 29 th 2021	Release of Collaboration Endpoint Software CE9.15.3.17.5cbbf23b617
58	April 14 th 2021	Release of CE9.15.0.13.82cc7e2121d, minor release Release of CE9.14.6.cf0c4696851, minor release
57	March 2 nd 2021	Release of CE9.13.3.a603f7b9cdb, minor release
56	February 4 th 2021	Release of Collaboration Endpoint Software CE9.15.0.11.aec227943ed
55	December 21 st 2020	Release of CE9.14.5.42d28d6c074, minor release
54	December 9 th 2020	Release of CE9.12.5.088b83c72cb, minor release
53	November 18 th 2020	Release of CE9.13.2.55d152fe9b0, minor release
52	November 12 th 2020	Release of CE9.14.4.b72ef4b0a42, minor release
51	October 15 th 2020	Release of Collaboration Endpoint Software CE9.14.3.ecb8718a646
50	September 8 th 2020	Release of CE9.13.1.98dd07c4099, minor release

Revision	Date	Description
		Release of CE9.12.4.4aa097e0eb6, minor release
49	August 21 st 2020	Added section about Wi-Fi considerations under important notes and warnings
48	July 1 st 2020	Release of CE9.10.3.e081e4e9936, minor release
47	June 24 th 2020	Release of Collaboration Endpoint Software CE9.13.0.990355df13a
46	May 11 th 2020	Release of CE9.10.2.5adf141d8bb, minor release
45	April 30 th 2020	Release of CE9.9.4.36b2d4ba8d6, minor release
44	April 28 th 2020	Release of Collaboration Endpoint Software CE9.12.3.140cd8212ba
43	March 26 th 2020	Release of CE9.10.1.1362f527e0f, minor release
42	February 20 th 2020	Release of CE9.9.3.950ff1628bb, minor release
41	January 22 nd 2020	Software deferral due to CVE-2020-3143 Minor corrections
40	January 9 th 2020	Minor corrections in Webex Edge for Devices prerequisites Updated compatibility table
39	January 8 th 2020	Release of Collaboration Endpoint Software CE9.10.0.50f5888d087 Release of CE9.9.2.f2110f7eda7, minor release Release of CE9.8.3.0a0afc64cb, minor release
38	December 6 th 2019	Release of CE9.8.2.8f7c71a6a75, minor release Release of CE9.9.1.47f2e107480, minor release
37	October 22 nd 2019	Release of Collaboration Endpoint Software CE9.9.0.46f7ea38fda
36	September 5 th 2019	Release of CE9.8.1.0f71ac008c3, minor release
35	July 3 rd 2019	Release of Collaboration Endpoint Software CE9.8.0.be9359915d0
34	June 5 th 2019	Release of CE9.6.4.ce8365c8325, minor release
33	May 29 th 2019	Release of CE9.7.2.3f94b3cda3f, minor release
32	April 25 th 2019	Android to CE9.7.1.30bff6140aa for DX70 and DX80
31	April 15 th 2019	Minor corrections regarding "Edit Favorites in OSD"
30	April 3 rd 2019	Release of Collaboration Endpoint Software CE9.7.1.30bff6140aa Release of CE9.6.3.28ab720ff52, minor release Release of CE9.5.3.168d55f2cde, minor release
29	February 11 th 2019	Release of CE9.6.2.5672d8aee2f, minor release

Revision	Date	Description
28	January 11 th 2019	Minor corrections regarding camera software included in the release and updated information on how to identify new hardware revision of p60 camera
27	January 7 th 2019	Release of Collaboration Endpoint Software CE9.6.1.4516ae5aaa1
26	November 29 th 2018	Release of CE9.5.2.8fcb81fa38f, minor release
25	November 7 th 2018	Release of CE9.5.1.be5deaf82e6, minor release and CE9.4.2.870837998d8, minor release
24	September 24 th 2018	Release of Collaboration Endpoint Software CE9.5.0.fb56c25334b
23	September 10 th 2018	Release of CE9.3.3.655fc73f140, minor release and Android to CE9.4.1.6ae80e1f2ee for DX70 and DX80
22	August 21 st 2018	Release of CE9.4.1.6ae80e1f2ee, minor release
21	June 28 th 2018	Minor corrections
20	June 27 th 2018	Release of Collaboration Endpoint Software CE9.4.0.62bc0aa4505
19	June 8 th 2018	Release of CE9.2.6.7fa942b, minor release
18	June 5 th 2018	Release of CE9.3.2.748b9742af6, minor release
17	May 24 th 2018	Release of Android to CE9.1.6.50b2793 conversion software for DX70 and DX80
16	May 4 th 2018	Release of CE9.1.6.50b2793, CE9.2.5.9c6d387 and CE9.3.1.61bfa3834f2, minor releases
15	April 11 th 2018	Release of Collaboration Endpoint Software CE9.3.0.7394032fb9c
14	February 28 th 2018	Release of CE9.2.4.4d375bc, minor release
13	January 17 th 2018	Release of CE9.2.3.3ba381b, minor release
12	December 21 st 2017	Release of CE9.2.2.f7269d5, minor release
11	December 14 th 2017	Release of Android to CE9.1.5.d1c67fb conversion software for DX70 and DX80
10	November 24 th 2017	Release of CE9.1.5.d1c67fb, minor release
09	November 21 st 2017	Release of Collaboration Endpoint Software CE9.2.1.360d0bf
08	October 12 th 2017	Release of Android to CE9.1.4.5f64050 conversion software for DX70 and DX80
07	September 11 th 2017	Added additional feature descriptions to CE9.1.4.3ae3106
06	September 5 th 2017	Release of CE9.1.4.3ae3106, minor release

Revision	Date	Description
05	August 14 th 2017	Updated minimum software version of CUCM and VCS required for CMS dual screen experience and other minor corrections
04	July 19 th 2017	Release of CE9.1.3.75ff735, minor release with bug fixes
03	June 22 nd 2017	Release of CE9.1.2.454d186, minor release with bug fixes
02	June 21 st 2017	Release of Collaboration Endpoint Software 9.1.1.9675283
01	April 10 th 2017	Release of Collaboration Endpoint Software 9.0.1.4c1e2ba

Introduction to Collaboration Endpoint Software 9

This release note describes the features and capabilities included in the Cisco Webex Room Panorama, Cisco Webex Room Kit Mini, Room USB, Room Kit, Room Kit Plus, Room Kit Pro, Room 55, Room 70, Room 70 Dual, Board 55/55S, Board 70/70S, Board 85S, Cisco TelePresence MX200 G2, MX300 G2, MX700, MX800, MX800 Dual, SX10, SX20, SX80, Cisco Webex Desk Pro, DX80 and DX70 Collaboration Endpoint Software version 9. Collaboration Endpoint Software is only supported by the endpoints listed above.

The Collaboration Endpoint software version 9 can be downloaded from <http://www.cisco.com>.

Cisco Terms of Service

Your use of Cisco software and cloud services are subject to these [terms and conditions](#). Your use of Cisco APIs is subject to the [Cisco Webex Developer Terms of Service](#).

Permitted Commercial Use for Scheduled Meeting Join Experience:

In addition, the following use case requires separate permission for commercial use: providing a scheduled meeting join experience like one button to push. This includes use of any API that updates the device with calendar data from an external source to provide this functionality including “xCommand Bookings Put” or previous private API’s such as “bookingsputxml.” In addition, using other APIs to accomplish the same functionality would also require permission for commercial use.

If you are providing a Scheduled Meeting Join Experience you either must comply with the below permitted commercial use terms or it must be for non-commercial use. Non-commercial use is defined as being solely for your internal business operations only and not for any activities that involve you using the API as part of or in furtherance of an income-generating service or product, whether directly or indirectly.

Any use to provide a Scheduled Meeting Join Experience that does not qualify under non-commercial use requires separate permission from Cisco.

Cisco reserves the right to revoke your license to use our API if, in our sole discretion, we deem that your use is for unauthorized commercial purposes or otherwise violates the Webex Developer Terms of Service.

Please contact us at devsupport@webex.com if you have any questions about whether your intended use of the API is permitted, or to inquire about obtaining permission.

Webex Certified and Webex Compatible vendors

To view a list of Webex Certified and Webex Compatible vendors, please visit:

<https://cs.co/certifiedvendors>

Important notes and warnings for this software version

Before upgrading from TC software to Collaboration Endpoint Software it is important to check that your environment supports the changes. We recommend that you read the release note thoroughly before upgrading.

Equipment and feature considerations before upgrading to Collaboration Endpoint Software 9

Before upgrading from older versions to CE9:

- If you are not already using CE software, please read the upgrade considerations in the CE8 release note before upgrading.
- Please verify that you are not using MultiStream with Cisco TelePresence Server before upgrading. This feature is deprecated in CE9, please use CMS for a Dual Screen Experience.
- The Touch 10 has a feature gap on CE9 compared to CE8. Most of the features not available on the Touch 10 can be configured through the web interface of the codec. Please refer to the feature gap matrix in the “Touch 10 updates” section below “New feature and functionality description” in CE9.0.1 for more information.
- If you are using Briefing Room mode, please read the known limitation section under “Briefing Room”.
- Upgrading the Cisco Webex Room devices via TMS requires the use of COP files.

Upgrade and downgrade paths:

- Upgrading from TC7.3.6 and above or CE8.x to CE9 directly is supported.
- Cisco Webex Room Series is only supported from CE9 and above, see the hardware dependencies section further down in this document. For upgrades from CE9.9.0/9.8.1 it is recommended to do a two-step upgrade method using step upgrade software. See the ‘Recommended upgrade path for Webex Room Systems’ section for more details.
- You can downgrade from CE9 directly to CE8.x or TC7.3.6 and above.

CE9.15.3.x is the last software release for Room, Board and Desk series

We announced that for Room, Board and Desk series these devices will need to upgrade to RoomOS 10 after its release in 2021 going forward. CE9.15.3.x is the last release for these devices. Please see the CE9.15.X.x final software pipeline section below for more details.

WiFi Connection Consideration

Due to compliance regulations, it is required to enable 802.11d in access point for the product to operate properly within 5725 MHz – 5875 MHz. As WiFi connection can be used as a flexible option, Ethernet connection is always preferred for high performance.

CE9.15.X.x is the final software pipeline for SX, MX and DX series and will eventually no longer support Room, Board and Desk series

We will continue to release software for CE9.15.X.x containing mostly bug fixes but may also have minor features or improvements. No further bug fixes will be added on CE9.14.x. From CE9.15.0.11 and above you will notice an extra number in the software version (CE9.15.0.11). This is the maintenance number for CE9.15.X.x releases to Cisco.com. CE9.15.X.x will continue to support SX, MX and DX series for the lifecycle of these products.

- CE9.15.X.x = major.major.minor.maintenance
- There will not be a CE9.16 release
- The version number increment will vary from release to release
 - For example, a maintenance release after CE9.15.0.11 can be CE9.15.0.19
 - For example, a minor release after CE9.15.0.11 can be CE9.15.3.14

Devices that will remain on CE9.15.X.x:

Cisco TelePresence SX Series

- SX10, SX20, SX80

Cisco TelePresence DX Series

- DX70, DX80

Cisco TelePresence MX Series

- MX700/800, MX700/800 Dual, MX200 G2, MX300 G2

Important note for Room, Board and Desk series regarding future software support

CE9.15.X.x will support the Room, Board and Desk Series for some time, but several months after the release of RoomOS 10 which will be released some time in 2021, we will stop releasing CE9.15.X.x for these products and you will eventually have to upgrade the device to RoomOS 10 when the available CE9.15.X.x software packages for these products are removed from Cisco.com. This is an early heads up so you can plan accordingly.

Important note for the upcoming RoomOS 10 release (can change):

- RoomOS 10 will no longer have support for ISDN Link
- RoomOS 10 will only support the newer device portfolio, which currently is Room, Board and Desk Series

Devices that will support RoomOS 10:

Cisco Webex Board series

- Webex Board 55, 55S, 70, 70S, 85S

Cisco Webex Room series

- Webex Room 55, 55 Dual, 70 Single, 70 Dual, 70 G2 Single, 70 G2 Dual, Webex Room Kit, Webex Room Kit Mini, Webex Room Kit Plus, Webex Room Kit Pro

Cisco Webex Desk series

- Webex Desk Pro, Webex Room USB, Webex on Flip

WebRTC calling will require RoomOS 10 after CE9.15.0.x

For WebRTC calling, devices will require RoomOS 10 starting after CE9.15.0.x for continued support. Any 9.x release after 9.15.0.x will not be supported.

For example:

CE9.15.0.x is supported with WebRTC

CE9.15.3.17 and above is not supported with WebRTC

Filenames will change starting in CE9.15.3.17

Starting in CE9.15.3.17 the filenames will become shorter for CE9.15.X.x releases. This will make it easier for administrators to identify releases for each software build going forward and mitigate a 32 character limitation for the phone load field in CUCM. This change does not apply to CE9.14.x

COP Files added to support UCM 14.x release starting in CE9.14.6

Starting in CE9.14.6 there will be COP files that have a '.sha512' extension in their names instead of the '.sgn' extension. This will apply to both CE9.15.X.x and CE9.14.7 releases.

For example: cmterm-ce99_15_13_0.k3.cop.sha512.

CE9.15.X.x only supports CMS 2.8 and above

CE9.15.X.x only support CMS 2.8 and above. Due to an API update, the conference participant list will not behave as expected if the CMS version is 2.7 or below.

Notice of upcoming change in remote communication ports used for touch panels with CE9.14.3

Currently the touch panel uses port 4051 for sustained remote pairing communication. This port will be deprecated in CE9.14.x and the new port will be 4062. If you have a firewall or a similar device that has specifically opened 4051 between the codec and the touch panel you must open the new port 4062 to sustain the pairing. If this port is blocked between the touch and the codec after upgrade, the touch will not be able to connect to the codec. No action will be required otherwise, the change will be transparent.

CE9.13.0 – Deprecated settings are no longer persistent when upgrading and downgrading

Previously the devices have kept configuration entries for settings that no longer exist during upgrade and downgrade. The benefit with this has been that configuration entries would persist on downgrading back to the previous software where the setting existed.

Upgrading to CE9.13.0 and above will delete any deprecated configuration entries that no longer exists for the current version.

For example, if you upgrade from X.x.x to CE9.13.x, any settings that no longer exist in CE9.13.x will be removed from the configuration database. When you now downgrade back to X.x.x, the settings will be reset to the default value on that respective version.

Note: When downgrading from CE9.13.x to CE8.1.x or TC7.3.x (for devices that support that), the provisioning mode setting will reset to the default value even if the setting exists on both versions. The workaround is to manually configure the provisioning mode after downgrade.

The reason for this change is consistency and to avoid regression issues going forward.

CE9.12.3 – Webex Edge for Devices and CE9.10.x for new customers

Due to a bug in CE9.10.x, registering on-premises devices using Webex Edge for Devices will stop working for recently created organizations after May 2020. Attempting to link a device that is running CE9.10.x will fail.

Users that is already using Webex Edge for Devices on CE9.10.x may continue to do so, and will also be able to register new devices on CE9.10.x.

For new customers CE9.12.3 will be the minimum supported software version for using Cisco Webex Edge for Devices.

CE9.12.3 – SpeakerTrack not working using Cisco TelePresence SX80 and Cisco Webex Quad Camera

Cisco TelePresence SX80 used together with Cisco Webex Quad Camera will lose the SpeakerTrack functionality on CE9.12.3 due to a bug. This issue only affects the combination of SX80 and Quad Camera. The solution is to use the previous software version until a fix has been released with CE9.12.4.

CE9.10.0 – Default SNMP configuration

The default SNMP configuration for devices on CE9.10.0 (factory reset state) has changed so that SNMP is turned off by default and the default SNMP Community Name is blank. If you upgrade from a lower version that already has a SNMP configuration, these settings will be kept. Once the device is factory reset while running CE9.10.0 or above, it is important to note that the new default settings will take effect.

CE9.9.0/CE9.8.1 and below – Recommended upgrade path for Webex Room Systems

For upgrades from CE9.9.0/9.8.1 and below, it is recommended to use step upgrade software.

Note: Step upgrade software can *only* be used to go from one software build to another!

The step upgrade method addresses the following issues:

- When attempting to upgrade a Cisco Webex Room Device via the web interface using a COP file, you may get a file size limitation warning that the limit for uploading software is set to 1GB.
- Upgrading to CE9.12.x from CE9.7.x and below via the web interface may result in error “The Installation Failed: Installation failed”.

Each package for the step upgrade software will be in the format of ‘s5xxxxce9.15.6-step-upgrade.pkg’ (e.g. s53200ce9.15.6-step-upgrade.pkg)

Upgrading via CUCM or other methods than the web interface are not affected. The file size limitation only affects the newer Cisco Webex Room Device portfolio when upgrading using cop.sgn files via the web interface.


To use a web server, upload the latest available software package on a web server reachable by the device you are about to upgrade. Type the following command from the xAPI CLI:

xCommand SystemUnit SoftwareUpgrade URL: https://url/upgrade_file_name.cop.sgn


The device will download the package from the web server and upgrade the device automatically. If you have many devices to upgrade, this method is recommended because it does not require a step upgrade.

Step upgrade procedure:

1. Download both the step upgrade software 'CE9.15.6' and the desired version upgrading to from cisco.com for the Webex Room Series device.
2. Go to "Maintenance" -> "Software Upgrade" and upload the step upgrade software package you downloaded earlier.
3. When system restarts, you will see the following message appear on the screen:
"The system is in a two step software upgrade process. The current software can only be used for upgrading to another software version. Please upgrade to the desired software now."



Note: This will also appear as a diagnostic warning in the web interface as well as a message on any connected touch panel.



4. Go to "Maintenance" -> "Software Upgrade" and upload the desired software package you downloaded earlier. Device will restart once upgrade is completed.
5. Step upgrade complete.

CE9.6.0 for Cisco Webex Room Kit Mini

Cisco Webex Room Kit Mini is supported from CE9.6.0 and will initially ship with this software version. CE9.6.0 was released only for this system but was not posted on Cisco.com. We recommend that you use the latest software version available on Cisco.com.

CE9.6.1 – Audio Console

If you have used Audio Console on CE9.5.x, please note that the Audio Console configurations will be erased when you upgrade from CE9.5.x to CE9.6.1 or above. Make a note of the Audio Console setup before upgrading, it is not possible to restore an Audio Console backup from CE9.5.x on CE9.6.1 or above. The setup has to be restored manually on one device and can then be backed up and distributed to other devices. You can disregard this warning if you have not used Audio Console on CE9.5.x. Note that the Audio Console was introduced as a feature preview in CE9.5.0 and is fully supported from CE9.6.1.

Supported devices: Cisco Webex Room Kit Pro, Cisco TelePresence SX80, Cisco TelePresence MX700, MX800 (D), Cisco Webex Room 70G2

CE9.4.0 - Default value HTTP+HTTPS is changed to HTTPS

From CE9.4.0 the default value of xConfiguration NetworkServices HTTP Mode is changed from HTTP+HTTPS. This change is performed to increase the security of the room devices on default configuration. Please note that upgrading from earlier software versions will not automatically change the default value and will stay on HTTP+HTTPS to avoid breaking current HTTP implementations. The change will be seen on new systems running CE9.4.0 and later or if the device is factory reset on CE9.4.0. HTTP requests will then automatically redirect to HTTPS and on first visit the device will display an “Insecure connection warning” as the device is using a self-signed certificate. To proceed to the web interface, you need to create an exception in your browser. This is a one-time operation unless you access the web interface with a different browser that has never visited the device web interface or if the device is reset to factory defaults.

Briefing Room does not work as expected

There were multiple issues with Briefing Room when enabled on CE9.0.x and CE9.1.x to the point where the feature was not working as expected. Cisco recommends everyone that is using Briefing Room on these software versions to turn it off or upgrade to CE9.2.1 or the latest version available. Briefing Room is disabled by default, requires a special room setup and is only available on Cisco TelePresence SX80, MX700, MX800 and MX800D. **This issue is fixed from CE9.2.1 and above.**

CE9 - Notice of Deprecation: MultiStream with Cisco TelePresence Server

Support for TelePresence Server based MultiStream implementation is deprecated from CE9. Focused effort will be allocated to the new Dual Screen Experience for CMS based meetings (requires CE9.1.3 or above). If support for TelePresence Server based MultiStream is required, we recommend that you stay on CE8.3.x.

CE9.2.0 for Cisco Webex Room 70 and Room 70 Dual

Cisco Webex Room 70 is supported from CE9.2.0 and will initially ship with this software version. CE9.2.0 was released only for these systems but not posted on Cisco.com. We recommend that you use the latest software version available.

Other limitations and advisories

Please refer to the known limitation section in this document.

Software Upgrade

You can upgrade devices using the native web interface of the device, CUCM, TMS or using the device xAPI.

Before you start, please make sure you have downloaded software for the correct platform.

Device	Software platform identifier
	Example: <code>cmterm-s52010ce<version>.k3.cop.sgn</code>
SX10	s52030
SX20	s52010 s52011 (no crypto)
SX80, MX700, MX800, MX800 Dual	s52020
MX200 G2, MX300 G2	s52010
DX80, DX70	s52040
Room Series, Board Series, Room 55/70	s53200
Room Kit Pro, Room 70 G2, Panorama, Desk Series	s53300

Note:

You should always try to use the .cop file when upgrading devices. Using the “.pkg” file directly also works but please note that **Cisco Webex Room Series and newer devices** have separate software for the connected peripherals. The peripheral software is contained in the “.cop” file. Upgrading using “.pkg” on these devices will leave the device unable to upgrade the peripherals and you may experience error messages regarding software mismatch after upgrade. To resolve this, upgrade the software again using the “.cop” file. We only release “.cop” files for the Cisco Webex Room Series.

The above note does not apply when using step upgrade software CE9.15.6.

With device platforms such as s52010, s52011, s52020, s52030 and s52040, you can safely upgrade using the “.pkg” file as the peripheral software for these devices are included.

Upgrading using the web interface

Access the device on <https://codecliP/web/software>. Upload the correct software package by following the instructions on the web page. The upgrade will start, and the device will reboot with the new software.

If you are on a software version before CE9.9.1 or CE9.8.2 you may experience a file size warning if the file you are uploading are larger than 1GB. If you experience this, please use the step upgrade software or one of the other methods.

Upgrading using CUCM

Install the appropriate “.cop” file containing the software for the device platform you wish to upgrade according to the cop installation process on CUCM.

Go into the device default loads on the CUCM administration page and make sure the platform has populated the correct filename. With device platforms such as s52010, s52011, s52020, s52030, s52040 (see list above) the load filename can contain the “.pkg” extension.

For Cisco Webex Room devices s53200 and s53300, the load file name should not contain any extension at all if the device is running software \geq CE9.8.2.

If the device is running software lower than CE9.8.2 the above method may not work, please use step upgrade software or the xAPI method to upgrade. See below.

Upgrading using TMS

Upload the software to TMS according to the TMS instructions of software upgrade.

Upgrading using the xAPI

If none of the above methods are applicable, you can use an existing HTTP server or setup a HTTP server that is reachable by the device(s) you want to upgrade.

Log into the xAPI CLI using SSH or Serial. Type the following command to initiate the upgrade.

```
xCommand SystemUnit SoftwareUpgrade URL: http(s)://yourhttpserver/path/to/file
```

```
xCommand SystemUnit SoftwareUpgrade URL: http(s)://yourcucmserver:6970/file
```

```
xCommand SystemUnit SoftwareUpgrade URL: http(s)://yourtmserver/public/path/to/file
```

The device will download the software package and upgrade without warning. If you want the user to be warned and postpone the upgrade, add the parameter: “Forced: False” to the command as the default is “Forced: True”

Camera firmware

In the table below, you can find an overview of the camera software included in the CE software release. Only new camera software is listed. If not listed, the camera software is the same as on the previous release.

Release	Hardware name/ID	Software name/ID	Notes
CE9.15.13.0	Precision 60 55000000	HC9.15.13.0.73ffba3d9ac	
CE9.15.3.26	Precision 60 55000000	HC9.15.3.26.19885f27907	
CE9.15.10.8	Precision 60 55000000	HC9.15.10.8.2be98ff5c6e	
CE9.15.8.12	Precision 60 55000000	HC9.15.8.12.7273b3b3e84	
CE9.15.3.25	Precision 60 55000000	HC9.15.3.25.4041d7b04a3	
CE9.15.3.22	Precision 60 55000000	HC9.15.3.22.8ebef840687	
CE9.15.3.18	Precision 60 55000000	HC9.15.3.18.fd1dd3b86f9	
CE9.15.3.17	Precision 60 55000000	HC9.15.3.17.5cbbf23b617	
CE9.15.0.19	Precision 60 55000000	HC9.15.0.19.d9646d0372b	
CE9.15.0.13	Precision 60 55000000	HC9.15.0.13.82cc7e2121d	
CE9.15.0.11	Precision 60 55000000	HC9.15.0.11.aec227943ed	
CE9.14.7	Precision 60 55000000	HC9.14.7.6e216653a72	
CE9.14.6	Precision 60 55000000	HC9.14.6.cf0c4696851	

Release	Hardware name/ID	Software name/ID	Notes
CE9.14.5	Precision 60 55000000	HC9.14.5.42d28d6c074	
CE9.14.4	Precision 60 55000000	HC9.14.4.b72ef4b0a42	
CE9.14.3	Precision 60 55000000	HC9.14.3.ecb8718a646	
CE9.13.3	Precision 60 55000000	HC.9.13.3.a603f7b9cdb	
CE9.13.2	Precision 60 55000000	HC.9.13.2.55d152fe9b0	
CE9.13.1	Precision 60 55000000	HC9.13.1.98dd07c4099	
CE9.13.0	Precision 60 55000000	HC9.13.0.990355df13a	
CE9.12.5	Precision 60 55000000	HC9.12.5.088b83c72cb	
CE9.12.4	Precision 60 55000000	HC9.12.4.4aa097e0eb6	
CE9.12.3	Precision 60 55000000	HC9.12.3.140cd8212ba	
CE9.10.3	Precision 60 55000000	HC9.10.3.e081e4e9936	
CE9.10.2	Precision 60 55000000	HC9.10.2.5adf141d8bb	
CE9.10.1	Precision 60 55000000	HC9.10.0.1362f527e0f	
CE9.10.0	Precision 60 55000000	HC9.10.0.50f5888d087	
CE9.9.4	Precision 60 55000000	HC.9.9.4.36b2d4ba8d6	

Release	Hardware name/ID	Software name/ID	Notes
CE9.9.3	Precision 60 55000000	HC9.9.3.950ff1628bb	
CE9.9.2	Precision 60 55000000	HC9.9.2.f2110f7eda7	
CE9.9.1	Precision 60 55000000	HC9.9.1.47f2e107480	
CE9.9.0	Precision 60 55000000	HC9.9.0.46f7ea38fda	
CE9.8.3	Precision 60 55000000	HC9.8.3.0a0afcf64cb	
CE9.8.2	Precision 60 55000000	HC9.8.1.8f7c71a6a75	
CE9.8.1	Precision 60 55000000	HC9.8.1.0f71ac008c3	
CE9.8.0	Precision 60 55000000	HC9.8.0.be9359915d0	
CE9.7.2	Precision 60 55000000	HC9.7.2.3f94b3cda3f	
CE9.7.1	Precision 60 55000000	HC9.7.1.30bff6140aa	
CE9.6.4	Precision 60 55000000	HC9.6.4.ce8365c8325	
CE9.6.3	Precision 60 55000000	HC9.6.3.28ab720ff52	
CE9.6.2	Precision 60 55000000	HC9.6.2.5672d8aee2f	
CE9.6.1	Precision 60 55000000	HC9.6.0.4516ae5aaa1	
CE9.5.3	Precision 60 55000000	HC9.5.3.168d55f2cde	

Release	Hardware name/ID	Software name/ID	Notes
CE9.5.2	Precision 60 55000000	HC9.5.0.8fcb81fa38f	
CE9.5.1	Precision 60 55000000	HC9.5.0.be5deaf82e6	
CE9.5.0	Precision 60 55000000	HC9.5.0.fb56c25334b	
CE9.4.2	Precision 60 55000000	HC9.4.1.870837998d8	
CE9.4.1	Precision 60 55000000	HC9.4.1.6ae80e1f2ee	
CE9.4.0	Precision 60 55000000	HC9.4.0.62bc0aa4505	
CE9.3.3	Precision 60 55000000	HC9.3.3.655fc73f140	
CE9.3.2	Precision 60 55000000	HC9.3.2.748b9742af6	
CE9.3.1	Precision 60 55000000	HC9.3.1.61bfa3834f2	
CE9.3.0	Precision 60 55000000	HC9.3.0.7394032fb9c	
CE9.2.6	Precision 60 55000000	HC9.2.5.7fa942b	
CE9.2.5	Precision 60 55000000	HC9.2.5.9c6d387	
CE9.2.4	Precision 60 55000000	HC9.2.4.4de75bc	
CE9.2.3	Precision 60 55000000	HC9.2.3.3ba381b	
CE9.2.2	Precision 60 55000000	HC9.2.2.f7269d5	

Release	Hardware name/ID	Software name/ID	Notes
CE9.2.1	Precision 60 55000000	HC9.2.1.360d0bf	
	PrecisionHD 1080p 4x S2 Precision 40 53000000	S01777-2.2 RC17 ID: 20040	
CE9.1.6	Precision 60 55000000	HC9.1.6.50b2793	
CE9.1.5	Precision 60 55000000	HC9.1.5.d1c67fb	
CE9.1.4	Precision 60 55000000	HC9.1.4.3ae3106	
CE9.1.3	Precision 60 55000000	HC9.1.3.75ff735	
CE9.1.2	Precision 60 55000000	HC9.1.2.454d186	
CE9.1.1	Cisco Webex Quad Camera 0C000000	CE9.1.1.9675283	See known limitations Software version is always noted the same as the released software
	Precision 60 55000000	HC9.1.1.9675283	
	PrecisionHD 1080p 4x S2 Precision 40 53000000	S01777-2.2 RC15 ID:20038	
CE9.0.1	Precision 60 55000000	HC9.0.1.5c1e2ba	
	PrecisionHD 1080p 12x Precision 12x 5000000(1-5)	S01718-4.0 FINAL ID:40085	

Release	Hardware name/ID	Software name/ID	Notes
	PrecisionHD 1080p 2.5x 54000000	S01777-2.2 RC14 ID:20037	
	PrecisionHD 1080p 4x S2 Precision 40 53000000	S01777-2.2 RC14 ID:20037	

Camera support

Codec	Camera	Support comments
Cisco Webex Room Kit Pro	Webex PTZ 4K	Full Support from CE9.14.5
	Precision 60	Full support
	Cisco Webex Quad Camera	Full support
	SpeakerTrack 60	Full support
	Sony SRG-120DH Sony EVI-120D	Pairing over IP and basic usage with pan tilt and zoom functionality is supported
Cisco Webex Room Kit Plus	Webex PTZ 4K	Full Support from CE9.14.5
	Precision 60	Full support from CE9.1.4
	Sony SRG-120DH Sony EVI-120DH	Pairing over IP and basic usage with pan tilt and zoom functionality is supported
	Cisco Webex Quad Camera	Full support
	SpeakerTrack 60	Full support (from CE9.10.0)
SX20	PrecisionHD 1080p 2.5x	Full support
	PrecisionHD 1080p 4x S2 Precision 40	Full support
	PrecisionHD 1080p 12x	Full support
SX80	Cisco Webex Quad Camera	Full support from CE9.2.1
	Precision 60	Full support

	Sony SRG-120DH Sony EVI-120DH	Pairing over IP and basic usage with pan tilt and zoom functionality is supported
	SpeakerTrack 60	Full support
	PrecisionHD 1080p 4x S2 Precision 40	Full support
	PrecisionHD 1080p 12x	Basic usage with pan tilt and zoom functionality is supported. * Software upgrade of this camera is not supported natively by this codec. * Daisy chaining cameras may work but is not supported on SX80 due to lack of testing.

Deferred software versions

A software version is deferred when we find critical issues within the software. This is to prevent users from downloading and installing affected software versions. Replacement software will always be in place before a software version is deferred.

Software and deferral policy

Older software versions will be deferred on a regular basis from the download section on <https://www.cisco.com> to avoid providing potential vulnerable software after security fixes. As a general rule you will be able to download the latest release and the version before. Older software versions will be removed from cisco.com regularly.

Example:

From CE9.15.0.11

The deferral process will be the same for CE9.15.X.x as before but the difference is that the major version is CE9.15 and is the last major release in CE9.

We will offer the current and the previous release for download and older releases will be removed. Please read the important notes for CE9.15.X.x section above for more information about the new version numbering.

9.15.X.x = major.major.minor.maintenance

Before CE9.15.0.11

If CE9.10.0 and CE9.10.1 is released and CE9.10.2 becomes available, CE9.10.0 may be removed.

Cisco supports the latest minor release and the previous minor release CE9.10.x and CE9.9.x as a general rule.

9.X.x = major.minor.maintenance

In this case you will have CE9.10.0 and CE9.10.1 available until CE9.10.2 comes out. The same applies for CE9.9.3 and CE9.9.4 until CE9.9.5 comes out and CE9.9.3 may be removed.

Exceptions are made if supported hardware or a particular feature for deployments depend on a major release. Deferring of older maintenance releases still applies.

CE9.15.3.x deferred

The above version has been deferred based on the above deferral policy. **Note this means that Room devices will now need to use RoomOS 10 for upgrades.** See the 'CE9.15.X.x is the final software pipeline for SX, MX and DX series and will eventually no longer support Room, Board and Desk series' section for more details.

CE9.12.x, 9.13.x, 9.14.x, 9.15.0.x deferred

The above versions have been deferred based on the above deferral policy.

CE9.14.3 and CE9.14.4 is deferred due to an audio processing issue with Cisco Room Panorama 70

Due to an issue with the audio processing in call that causes the device to crash, these releases have been deferred and replaced with CE9.14.5.

CE9.9, CE9.10, CE9.12.3 and CE9.13.0 is deferred

The above versions have been deferred based on the above deferral policy.

CE9.x up to and including CE9.9.1 is deferred

All CE9.x versions up to and including CE9.9.1 is deferred due to a discovered vulnerability in the affected software versions. Please refer to the deferral notice for more information.

<https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/TC7-CE8-CE9-deferral-notice.pdf>

CE9.0.1 deferred due to bug CSCvf27027

CE9.0.1 was deferred due to a software bug, CSCvf27027. Please read the deferral notice for more information.

https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/cisco_ce901_deferral_notice.pdf

CE9.1.1 deferred due to bug CSCve94476

CE9.1.1 was deferred due to a software bug, CSCve94476, causing the Cisco Webex Quad Camera upgrade to fail. The failure occurs if there is a software mismatch between the Cisco Webex Codec Plus and the Cisco Webex Quad Camera, and the Cisco Webex Codec Plus has been factory reset before connecting the camera.

<http://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/cisco-ce911-deferral-notice.pdf>

CE9.1.2 deferred due to potential issues with peripherals upgrade

There has been identified an issue with upgrading peripherals running CE9.1.2. Issue could cause upgrade of peripherals to fail, requiring several boots. Please use CE9.1.3 that contains a fix for this issue. Please see the deferral notice by following the link below.

<http://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/cisco-ce912-deferral-notice.pdf>

CE9.1.3, CE9.1.4 deferred due to WPA2 (KRACK) vulnerability

There has been identified an issue with room devices with support for Wi-Fi that makes the systems vulnerable to the WPA2 (KRACK) vulnerability. The software has been deferred for devices with support for Wi-Fi. Please see the deferral notice by following the link below for more information.

<https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/CE830-CE831-CE832-CE833-CE913-CE914-deferral-notice.pdf>

CE9.1.3, CE9.1.4, CE9.1.5, CE9.2.1, CE9.2.2, CE9.2.3, CE9.2.4, CE9.3.0 deferred

Please see the deferral notice for more information.

<https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/CE913-CE914-CE915-CE921-CE922-CE923-CE924-CE930-deferral-notice.pdf>

New features and functionality in CE9.15.13.0

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - This release includes files with k4.cop.sha512 extension for UCM 14 and above.

New features and functionality in CE9.15.3.26

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - This release includes files with k4.cop.sha512 extension for UCM 14 and above.

New features and functionality in CE9.15.10.8

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - Room, Board and Desk series devices will not be included in this release. To get the latest software, these devices will need to upgrade to RoomOS 10.

For RoomOS 10 release notes see
https://roomos.cisco.com/print/ReleaseNotes/RoomOS_10
 - This release includes files with k4.cop.sha512 extension for UCM 14 and above.

New features and functionality in CE9.15.8.12

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - Room, Board and Desk series devices will not be included in this release. To get the latest software, these devices will need to upgrade to RoomOS 10.

For RoomOS 10 release notes see
https://roomos.cisco.com/print/ReleaseNotes/RoomOS_10
 - This release includes files with k4.cop.sha512 extension for UCM 14 and above.

New features and functionality in CE9.15.3.25

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - CE9.15.3.x will be the last release including Room, Board and Desk series devices.
 - This release includes files with k4.cop.sha512 extension for UCM 14 and above.

New features and functionality in CE9.15.3.22

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - CE9.15.3.x will be the last release including Room, Board and Desk series devices.

New features and functionality in CE9.15.3.18

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - CE9.15.3.x will be the last release including Room, Board and Desk series devices.

New features and functionality in CE9.15.3.17


- CMS Raise Hand
- Noise removal support for DX devices
- Share WebApps in call
- Whiteboard shape support
- Webex Edge for Devices updates
 - Direct ad-hoc booking from Room device
 - Complete keyboard language support
- Bugfixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
- CE9.15.3.x will be the last release including Room, Board and Desk series devices.

New feature and functionality descriptions


CE9.15.3.17

CMS Raise Hand

In CE9.15.3.17 support raise hand is added with CMS 3.2 and above. This allows users to virtually raise their hand with a button on the UI to notify the host. Raise Hand is only available in meetings with more than two participants.

When the button  is selected to raise your hand the icon will turn blue. The button text changes to 'Lower hand'. A notification in the upper right corner appears that you have raised your hand.

From the host perspective they will get a notification that the attendee raised their hand.




Only the host, cohost and user who raised their hand will see the notification in the meeting.

To lower your hand, select the Raise Hand button again.

Background noise removal

In this release we added noise removal support for DX series devices.

Whiteboard shape support

For devices that have whiteboard capability there is a new icon  in an open whiteboard to enable shapes. Current supported shapes are lines, circles, ellipses, triangles, rectangles, parallelograms, arrives and curves.

For shapes to be recognized they must be drawn in a single continuous action. Shape recognition should be disabled prior to attempting to draw text.

Share WebApps in call

Devices that support web engine on 9.15.3.17 can now share a web view in a call directly as a presentation. The presenter can then interact with the web view in call as an annotation to share with participants if the device supports interaction.

When presenting a WebApp that plays audio but does not allow volume control, the presenter will not be able to adjust audio being shared in presentation to the participants.

When selecting Web View in a call it will be automatically shared, it is not possible to preview the web view while in call.

Webex Edge for Devices updates

Starting in March 2021, Cisco Webex is moving to a new Certificate Authority, IdenTrust Commercial Root CA 1. Due to this change, customers who are managing their device software upgrades manually must upgrade their devices to minimum CE 9.14.5 and preferably CE 9.15 at the earliest in order to be supported by Webex Edge for Devices.


Failure to upgrade results in devices losing cloud connectivity and loss of all related functionality. This includes Control Hub Management, Analytics, Hybrid calendaring amongst other features. Your ability to connect and use your on-premises SIP infrastructure will not be impacted. Additionally, devices on unsupported versions lose the ability to be linked to the Webex cloud using the Webex Device Connector.

The below features are valid when your device is linked to the cloud via Webex Edge for Devices.

Direct ad-hoc booking for Room devices

Room devices linked with Webex Edge and using the Hybrid Calendar service are now able to book an ad-hoc meeting directly from the Touch10, Room Navigator or Webex Assistant. It is also possible to extend a meeting up to the time of the next meeting scheduled to take place. If the extension will overlap with the next scheduled meeting time the icon to extend will be grayed out.

This feature can be controlled from Administrator view in Control Hub.



If the meeting schedulers are not enabled for Hybrid Calendar service and the only invitees that are enabled for Hybrid Calendar service are room resources, you must ensure that delete comments are set to false in the room resource mailbox for calendar processing.

Complete keyboard language support

The keyboard has been changed to now have a native keyboard that allows users to select up to 26 different languages with complete localized support. This is supported with both Touch and TRC-6.

To enable localized keyboard, change the device to the preferred language. You can always change the keyboard to English by clicking the globe next to the space bar on the keyboard. To revert back press the globe again to go back to localized keyboard.

When using TRC-6 with SX10 or SX20 some languages are not supported:

- Chinese (Simplified and Traditional)
- Japanese
- Korean

On CUCM registered devices, the language settings may not exist in the UI as determined by CUCM.

This feature requires Control Hub to manage configurations. To enable access for Webex Edge for Devices, go to Devices > Settings > Webex Edge for Devices and toggle on 'Allow Control Hub to manage configurations'.

Note: This feature can be enabled on per device basis for on-premises devices with the following command: `xConfiguration UserInterface QtVirtualKeyboard: True`. It will become a default enabled feature for on-premises in a future release.

Known Issues

[CSCvy02938](#): On SX10s and DX series registered to CUCM there is an issue with checking self-view or taking video snapshots in the web interface. This will be corrected in an upcoming release.

New features and functionality in CE9.15.0.19

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.15.0.13

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.15.0.11

- Web UI refresh
 - Support for upgrading Cisco Webex Room Panorama and Room 70 Panorama displays from the web UI
 - Logs can now be anonymized from when downloaded from the web interface
 - Ability to upload custom icons for UI extensions panel buttons
 - The standalone UI Extensions editor has now been removed from the web interface and can no longer be downloaded
- Background noise cancellation (BabbleLabs)
- Support for admitting guests into locked CMS conferences
- Floating toolbar for touch screen activities
- Dark mode for whiteboard
- Whiteboard overview
- CUCM Call management records
- Broadcast mode
- Webex Edge for Devices updates
 - Cloud software upgrade
 - Separate software channels for SX, MX and DX devices
 - Native Webex Meeting experience
- Bugfixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New feature and functionality descriptions

CE9.15.0.11

Web UI refresh

In CE9.14.3 we updated the styling frameworks in the web interface. Now in CE9.15.0.11 we have changed the design and layout of the web interface. This means that the web interface is restructured with new navigation flow, a search field and new icons and elements.

The new search field will quickly help you find the page you are looking for, or you can navigate to the page using the menu.

The overall functionality has not changed but how it is displayed and where it is located may have been changed.

Support for upgrading the Cisco Webex Room Panorama and Room 70 Panorama displays from the web interface

For Cisco Webex Room Panorama and Room 70 Panorama you are now able to upgrade the display firmware from the device web interface. This eliminates the need for upgrading the displays using a USB interface. Display firmware can be found on Cisco.com for the supported products. Follow the instructions on the upgrade page found in the Web UI of Cisco Webex Room Panorama.

Logs can now be anonymized when downloaded from the web interface

When downloading logs from the web interface you can choose to anonymize the logs using the drop-down menu. Personal identifiable information (PII) or other sensitive information will be replaced by a "Removed for privacy" note in the logs.

Note that providing anonymized logs to support cases with Cisco may increase the time it takes to troubleshoot. Providing full logs is recommended as these logs contain more information.

Ability to upload custom icons for the UI Extensions panel buttons


In the UI Extensions editor, you will now have an option to upload a custom button.

Below where you select an icon, there is an upload button.

Supported formats are .ico, .png, .svg or .gif and supported sizes are between 60x60 and 1200x1200. When uploaded it is scaled to 256x256 and stored in this format.

Note that the standalone UI Extensions editor has been removed and can no longer be downloaded in CE9.15.0.11.

A Touch panel is required to use UI Extensions.



Known limitations

This feature is not available for Cisco Telepresence SX10.

When the overflow of buttons creates a “more” button, the custom icon is not displayed in the overflow list.

Background noise removal (BabbleLabs)

The advanced noise removal AI from the BabbleLabs acquisition is now implemented from CE9.15.0.11. While in a call you can enable the noise removal from the UI on the fly or from the configurations to eliminate background noises such as keyboard typing, traffic and other meeting-disrupting background noises. All this to keep your voice in focus at all times.

This feature is supported for the Cisco Webex Room and Cisco Webex Desk Series.

Support for admitting guests into locked CMS conferences

Requirements:

CMS 3.2 and CE9.15.0.11 or above

This feature allows meeting hosts to admit participants into locked CMS conferences.

Floating toolbar for touch screen activities

On a touch screen device while sharing a presentation or navigating a web app you will now have a floating and dock able toolbar. Depending on what scenario you are in the toolbar will show different options. You can for example, stop the presentation sharing, enable annotation, go back to the previous page or refresh the current page when navigating a web app. For devices that is touch forwarding compatible, you can also enable and disable this from the new toolbar.

Dark mode for whiteboard

This feature is supported on all devices with whiteboard capability (DX, Board and Desk Series).

You can now switch between black or white canvas for the whiteboard. The device will save the preference you select for the next time you open the whiteboard.

Note that dark mode is local for the device only and sharing to a remote site (1-way) they will see it as a whiteboard. In a 2-way whiteboard session it depends on your local preference if you see it as a blackboard or whiteboard.

Whiteboard overview

This feature is supported on all devices with whiteboard capability (DX, Board and Desk Series).

In previous versions you could zoom out 2x on your current drawing. This zoom range is now increased to 10x, so you now get a better overview of your whiteboard.

CUCM Call Management Records

New CallDiagnostics configuration to enable CE endpoints to send media statistics to CUCM.

xConfiguration Provisioning CUCM CallManagementRecords CallDiagnostics: Enabled

This feature is enabled by default and values are populated into Call Management Records (CMR) if this feature is enabled on CUCM. CMR is enabled on CUCM via "Call Diagnostics Enabled" parameter under *System > Service Parameter > CallManager service*.

Values will be taken from the last statistics snapshot prior to the call disconnect/hold in order to reflect the actual values sent/received during the call and not influenced by end-of-call changes.

Packets are counted for the duration, but information about the stream (codec, resolution, framerate etc.) is only posted if the media is active when call is disconnected/put on hold. If a media stream is muted these values will be missing.

Known limitations:

Conference: If endpoint is moved to a lobby before disconnecting then the information about the stream may be that of the lobby.

Multistream: Packets are counted across streams, but information about the streams is posted for the first active speaker stream.

Presentation: Packets are counted for the duration, but information about the stream is only posted if the presentation is active during call disconnect/hold. Multiple shares during a call are not properly reflected.

MRA: This feature is only applicable for endpoints connected on-premise to CUCM not connected through MRA (Mobile Remote Access).

Broadcast mode

Broadcast mode is designed to remove all graphic effects on the video output. When broadcasting the video output for example through a TV network, you might want to remove icons, notifications when you turn up and down the volume or mute / unmute the device or other disrupting elements. The broadcast mode feature provides this functionality.

When this mode is enabled, we hide elements such as:

- Alerts / notifications and icons in the upper right-hand corner, for example:
 - o Recording
 - o Proximity
 - o Volume
 - o Mute
 - o And more...
- All buttons on the home screen out of call and in-call
- In-call elements, for example:
 - o Leave / Join meeting
 - o "+1" or more overflow indicator for meeting participants
 - o Incoming and outgoing call indicators
 - o And more...

Some elements are still displayed in this mode, for example:

- Name labels of the meeting participants including mute indicator per participant and an icon if the participant is sharing a presentation
- When you enter a personal meeting room you will still see the lobby screen as this is considered part of the video stream
- Upgrade and boot screens are displayed
- First time wizard is displayed (you must go through it or cancel it manually)
- Maintenance mode
- A warning will be displayed if extended logging is enabled
- Web views and whiteboard sessions are visible as normal

This can be enabled on demand and is turned off by default using the web interface or the xAPI *xConfiguration UserInterface OSD Mode: Unobstructed*

Webex Edge for Devices updates

The below features are valid when your device is linked to the cloud via Webex Edge for Devices.

Cloud software upgrade

Requirements

- Device configurations must be enabled in Cisco Webex Control Hub
- The configuration “Webex > CloudUpgrades > Mode” is set to “On” on the device.
- Cloud upgrade is supported for all devices linked to the cloud and the configuration is available for devices running CE9.14.3 and above. Note that a reboot is required if you enable cloud upgrade on a device with CE9.14.x.
- A reboot is not required for CE9.15.0.11 or above

Enable cloud upgrade

While logged in to Cisco Webex Control Hub go to:

- Devices -> Settings -> Webex Edge for Devices.
- Activate “Allow Control Hub to manage configurations”.
- Once enabled click the “Manage” tab to see your device overview and locate the device you want to enable for cloud upgrades and select it. A panel will appear on the right-hand side.
- Scroll down and click on “Device Configurations”, type “CloudUpgrades” into the search field and set the “Webex > CloudUpgrades > Mode” to “On”. It may take some time until the device is provisioned with the new settings, but you can reboot the device to enable it right away.
- The device will upgrade automatically when new software is available

The device is now part of the automated software maintenance and it will get the latest bug fixes and features. The upgrade interval is approximately once every month and you can see the software deployment plan in Control Hub if you click on “Devices” in the menu and select the “Software” tab. For Webex Edge for Devices you have to select the sub-tab “RoomOS Edge”.

Note that there are now two different pipelines of software in the Webex cloud. One for the newer devices (Room, Board and Desk series) and one for the older devices (SX, MX and DX Series).

Older devices will receive RoomOS 9.15.X.x software and the newer will receive RoomOS 10.X.X.x software. SX, MX and DX series do not support RoomOS 10.X.X.x software.

We offer the same software channels for Webex Edge for Devices as we do for fully Webex registered devices.

Note: TAC only supports devices with cloud upgrade enabled that is getting software from the Stable channel. If you decide to disable cloud upgrade on a device, please make sure you downgrade the software to the latest available version on Cisco.com to ensure you are in a supported state.

Webex Optimized Experience

Requirements

- You must have cloud upgrade enabled (see above section) on your device linked to Webex Edge for Devices.
- The configuration for “Conference Multipoint Mode”, must be set to “Auto” or “Off” on the device.
- The configuration for “Webex Meetings JoinProtocol” must be set to “Webex”
- Requires that you meet the same network criteria’s as fully registered Webex devices so the device can reach the necessary services.
 - o <https://help.webex.com/en-us/WBX000028782/Network-Requirements-for-Webex-Services>

Webex Optimized Experience means that you can have your device registered on-premises and at the same time join Webex meetings natively from your device and reaching out to Webex directly just as it was fully registered on cloud.

When the endpoint meets the requirements for the Webex Optimized Experience the device will always make a Webex call if you use the “Join Webex” button or use the Webex Assisant to join a Personal Meeting Room.

If no protocol is specified, the device will automatically decide how to make a call. For example, calls to *@webex.com, *@*.webex.com or *@meet.ciscospark.com domains will automatically be native Webex calls. Otherwise, the device will use the specified protocol or fallback to the default protocol (i.e., SIP).

When joining Webex meetings like this, the call will be a “true” Webex call and you gain the benefits of 2-way whiteboarding for devices that support whiteboarding, face recognition (if enabled), layout control and other advanced meeting features that previously only was available for fully Webex registered devices.

Known limitations:

This feature is for joining Webex Meetings and PMR’s and does not include ad-hoc 1:1 calling between users and other cloud devices.

This feature is not supported for Cisco Webex Room Panorama or Room 70 Panorama.

New features and functionality in CE9.14.7

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.14.6

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.14.5

- Added Support for Webex PTZ 4K
- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New feature and functionality descriptions

CE9.14.5

Software support for Webex PTZ 4K

The Cisco Webex PTZ 4K (EVI-X200C) is the latest camera in the Collaboration peripherals portfolio. It is compatible with the Cisco Webex Codec Plus and Codec Pro. This camera includes artificial intelligence-based face and upper body detection and tracking that allows for keeping presenters visible in the video conference and at a high zoom level while they move around in a predefined presentation area. The Webex PTZ 4K can be sold as a bundle with the Codec Plus and Codec Pro.

Features

Codec camera features	Supported?
PresenterTrack	No for CE* (Support included in RoomOS 10 for Room, Board and Desk series devices running 10.3.x and later)
Device Inventory in Control Hub	Yes
Zoom	Yes (20x optical zoom + 12x digital zoom, 240x total)
Camera Control	Yes via IP (LAN Port)
Supports PoE	Yes
SpeakerTrack	No
Pan, tilt and zoom (PTZ)	Yes
Software Upgrades	Yes (From CE9.15.3)
Presets	Yes (15 presets can be stored)

Lights

Power	Standby	Reason
OFF	OFF	No Power
Flashing slowly	OFF	Startup (Initializing)
ON	OFF	Power On
OFF	ON	Standby Mode
Flashing slowly	Flashing slowly	Firmware Upgrade
ON	Flashing	Pan tilt position error

Flashing quickly	Flashing quickly	Internal error
------------------	------------------	----------------

The Camera Setup switch is for selecting the video signal format to be output from the HDMI OUT terminal. This should always be set to 6 to be controlled by the Cisco Codec.

Important Notes: Do not use a VISCA cable as it will cause severe damage to the camera.

Software upgrades are supported from CE9.15.3 and later.

For more information about the Webex PTZ 4K, please visit:

<https://www.cisco.com/c/en/us/products/collateral/collaboration-endpoints/collaboration-peripherals/webex-ptz-4k-camera-ds.html>

New features and functionality in CE9.14.4

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.14.3

- Software support for Cisco Webex Room Navigator
- Web UI visual updates
- Pin participant as important in CMS calls
- Music mode
- Manual camera control for touch screen devices
- Mouse and keyboard re-direct (HID forwarding)
- Touch 10 menu button updates
- Configurable cleanup of web data and whiteboards
- Improved Wi-Fi setup UI
- Call info in recent list
- Webex Edge for Devices updates
 - MS Teams WebRTC and CVI interop
 - Upload logs to cloud
 - Multiline body now supported via cloud xAPI
- Speaker Track View Limits
- Other
 - Audio output may be noticeably louder after upgrade to CE9.14.3

New feature and functionality descriptions

CE9.14.3

Software support for Cisco Webex Room Navigator

The Cisco Webex Room Navigator is the new touch panel in the Cisco Webex Room Series. This intuitive, touch panel offers instant connections to video conferences, room controls, content sharing, and room booking.

Cisco Webex Room Navigator comes in two versions, with a table stand or wall mount. The Room Navigator has multiple intelligent sensors that can gather environmental data for example, humidity, temperature, and ALS (Ambient Light Sensor).

Sensor data is available in the connected Room Device APIs or in Cisco Webex Control Hub.

For more information about the Cisco Webex Room Navigator, please visit:

<https://www.cisco.com/c/en/us/products/collaboration-endpoints/webex-room-navigator/index.html>

Software Compatibility Note and Upgrade Guide:

<https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/software-upgrade-room-navigator.pdf>

Web UI visual updates

The web interface has been updated with modern styling frameworks. The functionality provided by the web interface is still the same but the colors and interaction forms (i.e. buttons and text input fields) has been updated with new styles that also has better overall support for smaller / mobile devices. This is the first part of a larger update of the web interface.

Pin participants as important in CMS calls

In a CMS meeting the meeting host can now pin a meeting participant to show up as important for all meeting participants. This way the participant will be displayed even when not being the active speaker.

In a call, tap the participant list and locate the participant you want to pin. Tap the participant and select "Pin for all".

Participants will receive a notification on-screen when they are pinned / unpinned. Note that pinned audio only participants will not affect the layout.

This feature works in a CMS call with active control enabled.

Music Mode

Previously, room devices filtered out additional noises by default and reduced sound level variations, which helped cater for meeting use and distracting noise. This feature (Music Mode) enables the dynamic range of music to go through while being in or out of a call with a controllable UI setting. Music Mode is useful for remote music lessons, testing musical instruments, and other situations where it's important to hear the full range of music. The device still uses its echo cancellation and environmental background noise reduction capabilities to avoid the need for external equipment, without detracting from the performance. Note: Music mode is automatically turned off when the call ends. The next call will be optimized for speech.

Please note that Music Mode only works for the microphones and is not supported with audio from other input sources including HDMI inputs. This means that content audio played from a laptop will not have any effect from Music Mode.

Mouse and keyboard re-direct (HID forwarding) for Desk Pro

You can now plug in a USB receiver or keyboard and/or mouse directly to the Desk Pro and forward this behavior to your laptop connected with USB-C. This is an expansion of the docking station capabilities with USB-C.

Manual Camera Control for Cisco Webex Desk Pro and Board

This feature allows manual adjustment of the camera, including manual zoom, as well as turning off the automatic framing feature.


Cisco Webex Desk Pro: digital zoom up to 2x.

Cisco Webex Board: digital zoom up to 5x.


Note: FECC is not available *from* Cisco Webex Board or Desk Pro, but other devices can control these devices using FECC.

Touch 10 on-screen button updates

The Touch 10 and Room Navigator now supports pages of buttons, which can display up to eight buttons per page (five when previewing a presentation). Additional pages are indicated by small dots below the buttons. Slide your finger over the buttons to the left or right to change the page. This feature removes the “more” button that would previously display the overflowing buttons in out-of-call scenarios.



For in-call scenarios you will still see a “More” button that will now display the overflowing actions in a scrollable list.



Configurable cleanup of web data and whiteboards

With the new configurable cleanup feature, you can now set a time of the day where the device will clean up all the web and whiteboard data. In previous releases the Webex Board would start the clean-up process every time it went into Halfwake mode.

Example:

```
xConfiguration RoomCleanup AutoRun ContentType WebData: Daily
```

```
xConfiguration RoomCleanup AutoRun ContentType Whiteboards: Daily
```

```
xConfiguration RoomCleanup AutoRun HourOfDay: 0
```

With the default configuration, the device will attempt to clean up the data at midnight every day. By turning off cleanup of either Whiteboards or Web Data, the device will not clean up until performed manually.

When you have stored whiteboard or web data, a button will appear on the screen saying, “End session”. This will allow you to manually select what you want to clean up. If the device is unused (in standby) at cleanup time, the device will clean up the data automatically.

If the device is in use at time of cleanup, the device will not perform the cleanup but wait until left unused. If the device is about to enter Halfwake during cleanup time (00:00-00:59 by default) you will get a 60 seconds warning saying, “Cleaning up for the next user” with a button to abort. If aborted, the device will not attempt to clean up until the next day at the same hour.

Improved Wi-Fi setup UI

In CE9.13.0 we introduced a new and improved UI for setting up Wi-Fi for the Room USB only. The new Wi-Fi setup is now implemented for all devices that has support for Wi-fi. You must unplug the Ethernet cable from the device to configure Wi-Fi.

Call info in recent list

View information about a call that recently took place on the device. View the packet loss / jitter and other data collected for the call. While this is technically not a new feature, the information has become more visible as you can now view this data from the Touch panel.

Click on the green “Call” button and select the “Recents” tab. Click on a call and select the “More” button. Then click “Call details” to view the call statistics.

This is useful in scenarios where you might have experienced bad quality video and with this, quickly identify if there were any issues with packet loss during the call.

Webex Edge for Devices updates

Support for Microsoft Teams WebRTC and Cloud Video Interop (CVI)

Microsoft Teams WebRTC and CVI was recently announced for devices registered on Webex. Support is now added to devices linked through Webex Edge for Devices and running CE9.14.3 or higher.

To use WebRTC calling, it is required to have a hybrid calendar deployment in Cisco Webex Control Hub and a MS Teams meeting invite to generate a One Button to Push on the device. WebRTC will use the embedded web engine on the device to make the call. Web engine is a configuration that allows the device to create web views. When linked to Webex Edge for Devices, web engine will be turned on automatically. Note that if you turn off web engine manually, WebRTC will not work.

If you have enabled Cloud Video Interop (CVI) in your organization, you can dial into the MS Teams meeting directly. In such cases the web engine and hybrid calendar are not required but note that you need a hybrid calendar deployment to join the meeting using One Button to Push.

Upload logs to cloud via Webex Edge for Devices

Devices that are fully cloud registered has always been able to upload logs to the cloud by pressing the “Send logs” button from the UI under Settings -> Issues and Diagnostics. We are now allowing devices registered through Cisco Webex Edge for Devices the same option. This feature is not enabled by default and has to be enabled on each device for the “Send logs” option to appear.

When sending logs to the cloud, the logs will be filtered for PII information to protect the privacy of the users and is used to simplify the process of providing the Cisco Technical Assistance Center with the necessary logs in case of an issue. A log id will be visible in the UI after a successful upload. This id can be provided to your Cisco support representative.

Cloud Device API – Support for large body in command requests

While the cloud device API is not new, it previously did not support commands that required additional multiline input. With CE9.14.3 you can issue commands with a multiline body containing for example certificates, branding images, macros, UI controls, sign-in banners, or other multiline commands.

Read more about the cloud device API and how to use it on <https://developer.webex.com>.

For developer support, please contact devsupport@webex.com.

SpeakerTrack View Limits

You can now narrow down the SpeakerTrack View Limits in the room. A new configuration wizard has been added to the settings on the touch panel to set a new overview image. You can zoom in and adjust the image to not include parts of the room in the image.

When SpeakerTrack diagnostics is enabled you can see if view limit is active and the frame that is used as the overview image.

SpeakerTracking and framing will still work within the limited overview image.

This feature only works while SpeakerTrack is active and have view limits enabled and configured.

Other

Audio output may be noticeably louder after upgrade to CE9.14.3

In previous versions a bug caused *xConfiguration Audio Output <HDMI|Line> Level* to be applied as twice the number of decibels configured. For example:

0 gives 0dB gain

-1 gives -2dB gain

-24 gives -48dB gain

Depending on how these settings has been configured in a previous release you may experience that the audio output is louder than before after the upgrade as this issue is now resolved. This note is to inform you that the volume increase is a result of the bug fix and not the other way around.

This issue may affect Cisco Telepresence SX80, Cisco Webex Codec Pro and Codec Plus, based devices.

New features and functionality in CE9.13.3

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.13.2

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.13.1

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.13.0

- Support for Cisco Webex Room Panorama and Room 70 Panorama
- Webex Edge for Devices
 - Support for Cisco Webex Control Hub configuration management
 - Easy join Personal Meeting Rooms with user search
 - Real Time Media Metrics when joining Webex calls
- Upload custom virtual backgrounds for Cisco Webex Desk Pro
 - Use PC input as virtual background
- Improved Wi-Fi setup on Cisco Webex Room USB using the TRC remote
- Touch forwarding in-call for Webex Board
- Far End Camera Control when dialing into CMS (2.8) meetings
- Add a custom text with time and date to a video stream

New feature and functionality descriptions

CE9.13.0

Collaboration Endpoint Software 9.13.0

Introduction

Collaboration Endpoint Software 9.13.0 is the first software version that comes with support for Cisco Webex Room Panorama, our new first-class collaboration system. We are adding new features for devices registered via Webex Edge for Devices. CE9.13.0 is ready for configuration management from Webex Control Hub and will also support real-time media metrics when joining Webex meetings for easy troubleshooting from Control Hub.

Read the new feature descriptions for more information below.

Added support for new products

Cisco Webex Room Panorama and Room 70 Panorama

Cisco Webex Room Panorama is a new first-class collaboration system built for the modern C-suite. The Room Panorama provides immersive video experience, rich content sharing, and co-creation experience within the Cisco Webex Room Series portfolio.

The Room Panorama is built on the powerful Cisco Webex Room Kit Pro technology platform. The Room Panorama comprising a powerful codec, a Cisco Quad Camera, dual 82-inch 8K video displays, and a 65-inch 4K presentation display is ideal for rooms that seat up to 14 people.

It offers sophisticated camera technologies that bring panorama video, speaker-tracking, and auto-framing capabilities to medium to large-sized rooms.

For more information about the Cisco Webex Room Panorama, please follow the link below

<https://www.cisco.com/c/en/us/products/collateral/collaboration-endpoints/collaboration-room-endpoints/datasheet-c78-743064.html>

Webex Edge for Devices updates

Support for Cisco Webex Control Hub configuration management

CE9.13.0 is ready to let Cisco Webex Control Hub take care of the configuration management for devices linked via Webex Edge for Devices. Configuration Management (write) is disabled in Control Hub by default and must be enabled to take effect. If disabled, you will only be able to read the configuration from the devices. To change configurations on the device from Control Hub you must enable it in Control Hub.

When Control Hub is set to manage configurations, the devices under such control will no longer accept most configurations from CUCM except configurations not exposed in Control Hub. This also means customization (such as macros or branding) will no longer be accepted from CUCM. The other settings are mostly related to network services and is to avoid making the device unreachable from Control Hub. The device will continue to accept these settings from CUCM. Please see a list below for the most significant ones:

```
xconfig networkServices http proxy
xconfig networkServices h323
xconfig networkServices https
xconfig networkServices snmp
xconfig networkServices ssh hostkeyalgorithm
xconfig networkServices upnp
xconfig networkServices wifi
xconfig conference defaultcall protocol
xconfig conference encryption mode
xconfig phonebook
```

Easy join Webex Personal Meeting Rooms with user search

This is an addition to the feature released in CE9.12.3, please read the feature description in the CE9.12.3 section for more information about the Easy Join PMR feature.

Devices linked via Webex Edge for Devices can now search directly for users in the Webex organization where it's linked and are not limited to finding recent PMR calls. A button to easily to join their Personal Meeting Room will be displayed in the search result next to the user's name.

Real-time media metrics when joining Webex meetings

Devices linked through Webex Edge for Devices will be visible in the media troubleshooting section in Control Hub in the same way fully Webex registered devices are today. This will make it easier to troubleshoot media quality issues.

Upload custom virtual backgrounds for Cisco Webex Desk Pro

You can now upload your own custom virtual backgrounds to your Cisco Webex Desk Pro. The image can be uploaded via the web interface of the device and selected as a virtual background from the GUI.

Note: Use of custom virtual backgrounds is considered a technology preview. The feature is turned off by default, but it can be turned on in the camera configuration.

Use the PC input as a virtual background

If you have a device connected to your Cisco Webex Desk Pro input (HDMI or USB-C), for example your laptop, you can select this input as a virtual background in the GUI. The virtual background will then mirror what you are currently displaying on your laptop.

Touch forwarding in-call for Webex Board

Previously, touch forwarding was not supported in-call but can now be activated / deactivated using the floating toolbar on-screen.

Improved Wi-Fi setup on Cisco Webex Room USB using the TRC 6 remote

The UI for setting up Wi-Fi using the TRC 6 remote control has been improved. This will make it easier to configure Wi-Fi when navigating using the TRC 6 remote control. In previous versions, the UI for setting up Wi-Fi was not optimal. With this improvement the challenges have now been resolved.

Far End Camera Control (FECC) support when dialing into CMS (2.8) meetings

FECC has until now, not been supported when dialing in to meetings hosted by the CMS. Pressing the participant list, you will now see a button to control the far-end camera of the current active speaker.

Note: If the active speaker is frequently changing it may be challenging to control the camera of the intended participant. You cannot manually select a participant for far end camera control.

Note that some devices do not support FECC, such as DX80, Desk Pro, Room Kit and devices using Quad Camera.

Add a custom text with time and data to a video stream for Room Devices

A new xAPI command, *xCommand Video Graphics Text Display*, has been added in order to add time, date and a custom text string to a video stream. You can add this line to the main video, presentation and/or local output. This feature is only supported on the newer device portfolio such as, the Cisco Webex Room Series.

Note: The name label of the remote device sending the custom text will sometimes render on top of the text. This is a known limitation and will be resolved in a future release.

Please refer to the API guide for more information about new xAPI commands and features.

Bug fixes

- Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.12.5

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.12.4

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.12.3

- Support for Cisco Webex Room USB
- Support for Cisco Webex Desk Pro
- Support for Cisco Webex Room Kit Mini on a Samsung Flip
- One-way whiteboard sharing in-call
 - “Annotate everywhere”
- Webex Join Button: Easy Join Personal Meeting Rooms with suggestions from recent calls
- HTTP Proxy support for Webex Edge for Devices
- Touch forwarding in-call for Cisco Webex Desk Pro
- Other changes
 - Hide Proximity notifications
 - Hide scheduled meeting titles for privacy
 - Manual zoom is increased from 3x to 5x for Cisco Webex Room Kit Mini, Room Kit and Room 55
 - Web UI improvements
 - Added button to deactivate / activate SpeakerTrack from Call Control
 - Microphone button in Call Control is now properly displaying mute status
 - Presets are now highlighted when selected
 - DefaultMainSource will now be displayed when a composed image is detected in main video
 - Number of displayed directory entries are now increased from 50 to 100 in Call Control

New feature and functionality descriptions

CE9.12.3

Collaboration Endpoint Software 9.12.3

Introduction

Collaboration Endpoint Software 9.12.3 is now available. CE9.11.0 has been skipped and will not be released. CE9.12.0, CE9.12.1 and CE9.12.2 has been used as manufacturing software for the new supported products and is not available on cisco.com. If you receive a product that is running one of these software versions, you are encouraged to upgrade to the latest version available for your product on cisco.com. If you are registering your product to Webex, the device will upgrade automatically after activation. The manufacturing builds (CE9.12.0, CE9.12.1 and CE9.12.2) are not supported by TAC for on-premises deployment.

Added support for new products

Cisco Webex Room USB

Cisco Webex Room USB is a new entry-level room device in the Cisco Webex Room Series that can only be used in USB mode. You can register the Room USB device to Webex Control Hub for management and use it for wireless content sharing or digital signage.

The Room USB is the same hardware as the Cisco Webex Room Kit Mini and can be upgraded from Room USB to Room Kit Mini with a valid product key.

Read more about Cisco Webex Room USB here:

<https://www.cisco.com/c/en/us/products/collateral/collaboration-endpoints/webex-room-usb/datasheet-c78-743383.html>

Cisco Webex Desk Pro

Cisco Webex Desk Pro is the most advanced, AI powered device for desk. Support for Desk Pro is added in CE9.12.3 and you can register the device on-premises or cloud for a greater experience with whiteboarding, face recognition, digital signage, touch forwarding and much more!

You can read more about the device by following the link below:

<https://www.cisco.com/c/en/us/products/collaboration-endpoints/webex-desk-pro/datasheet-c78-743105.html>

You may need an updated device pack in order to register the device to your CUCM.

Support for using Cisco Webex Room Kit Mini with Samsung Flip

If you have a Samsung Flip device and a Cisco Webex Room Kit Mini with CE9.12.3 or later, you can connect them and take full advantage of the Flip Touch screen. By connecting the Webex Room Kit Mini to the Samsung Flip you will automatically get a touch interface (the UI becomes comparable with Cisco Webex Board) and unlock the whiteboard feature. No configurations are needed, just connect the cables and the two devices will work seamless together. When connected you can easily switch between Samsung Flip and the Room Kit UI using the new “Flip” button that appears on the screen.

It is important to note that Cisco TAC will not support issues found to be related to the Samsung Flip device. Cisco TAC will only support issues related to the Cisco Webex Room Kit Mini. Please contact your Samsung support representative if you are experiencing issues with the Samsung Flip device.

One-way whiteboard sharing in-call

Previously, the whiteboard button would not be available in a call (grayed out), only local whiteboards was enabled.

With CE9.12.3 the whiteboard function is enabled also while you are in a call. In order to share the whiteboard in-call you have to click the home button and then press the whiteboard button. The share will start as soon as you enter editing mode, either if you are selecting an on-going drawing or starting a new one.

To stop the whiteboard sharing, press the “Done” button and then press “Stop sharing”.

Note that the whiteboard share is one-way. Only the device sharing the whiteboard can draw on the whiteboard. Remote participants can only observe and not participate.

Annotate everywhere

You can start annotation on web views as well as on shared content in or out of a call on devices with whiteboard functionality.

Webex Join Button: Easy join Personal Meeting Rooms (PMR) with suggestions from recent calls

The Webex Join Button now supports dialing Personal Meeting Room IDs, previously you could only dial meeting numbers using the Webex Join Button. You can type in the user and site name only (short) or the full PMR URI.

For example *user.sitename* or user@sitename.webex.com

If you have previously dialed a Personal Meeting Room (and is present in your recent calls list), this will show up as a suggestion with a join button as you type in the PMR ID.

On your personal device or if you are paired to a shared device you will also see a button at the bottom to quickly join your own Personal Meeting Room.

HTTP Proxy support for Webex Edge for Devices

HTTP Proxy support has until now only been supported for full Webex deployment. The feature has been re-worked in order to support Webx Edge for Devices, which means part on-premises and part cloud.

When you are linked via Webex Edge for Devices:

- All HTTP requests to the Webex Cloud will use the configured HTTP Proxy.
- Any HTTP requests targeted for provisioning (CUCM/TMS) or phonebook will bypass the proxy settings.

In addition to this we have also added configurations that will allow you to choose if the following services should use the configured HTTP Proxy or not, respectively:

- xConfiguration HttpClient UseHttpProxy
- xConfiguration HttpFeedback UseHttpProxy
- xConfiguration WebEngine UseHttpProxy

No changes to Proxy Auto Config (PAC) and WPAD support. Note: Cisco TAC is not responsible for providing or creating PAC file setups.

Touch forwarding in-call for Cisco Webex Desk Pro

Previously, touch forwarding was not supported in-call but can now be activated / deactivated using the floating toolbar on-screen.

Other changes

Hide Proximity notifications

You can now hide the Proximity notifications. This includes the Proximity icon that is visible on-screen when someone is paired with Proximity and the notification that appears when someone has just paired. This is a configuration and can be set via the xAPI, Web UI or be provisioned for example via TMS.

Hide scheduled meeting titles

The meeting title usually says something about the meeting agenda. For those who wants the extra privacy, we have now added a configuration setting that will hide the title of the meeting and just

display “Scheduled meeting” where the meeting title would normally be displayed on both the Touch 10 interface and on-screen.

Manual zoom is increased from 3x to 5x for Cisco Webex Room Kit Mini, Room Kit and Room 55

In previous releases the manual zoom range for the Cisco Webex Room Kit Mini, Room Kit and Room 55 was limited to 3x. With CE9.12.3 this range has been increased to 5x. Please note that this change only affects the products mentioned and in manual zoom mode only.

Web UI improvements / changes

The following improvements are implemented on the Call Control page

- Previously, on a SpeakerTrack enabled device you would only see the current SpeakerTrack status, but you could not alter the state. The button is now clickable and will disable or enable SpeakerTrack accordingly.
- Previously, the mute button would always show that the device was unmuted. In CE9.12.3 the mute button will correctly reflect the mute status of the microphones.
- Previously, when you selected a preset, you would not get any indication that the preset was selected successfully. In CE9.12.3 the preset you selected will be highlighted in blue if the preset was accepted by the codec. It will also detect when a preset is selected from, for example the Touch 10 panel. Note that preset highlighting and detection occurs only if the “Camera Positions” window is open. When you open the “Camera Positions” window it will always initiate with no highlighting.
 - PresenterTrack can now be enabled from the “Camera Positions” window if PresenterTrack is supported and configured on the device.
- Requires the remote monitoring option key: Previously when main video consisted of a composited image of more than one input source you would only see a black image on the call control page. With CE9.12.3 we will instead display the DefaultMainVideo source, which by default is the main camera.
- Previously the max number of directory entries that could be displayed at a time was set to 50. With CE9.12.3 this number is increased to 100. Use the search field to narrow down the list. The new limit also applies to recent call and favorite entries.

Bug fixes

- Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.10.3

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.10.2

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.10.1

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.10.0

- Webex Edge for Devices
- Webex Join button
- Android to CE9.10.0 conversion software released for DX70 and DX80 (January 17th 2020)
- Other changes
 - Default passphrase policy
 - Replaces “Strong Security Mode”
 - Default self-signed certificate validity changed from 5 years to 1 year
 - Default SNMP Configurations
 - Added support for SpeakerTrack 60 for Codec Plus
 - Resolved security issues related to CVE-2020-3143
 - CSCvs67680
 - CSCvs45241

For more information please read the official Security Advisory

- <https://tools.cisco.com/security/center/content/CiscoSecurityAdvisory/cisco-sa-telepresence-path-tr-wdrnYEZZ>

Earlier affected software versions have been removed and is no longer available to download, please read the software deferral notice for further details.

- <https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/TC7-CE8-CE9-deferral-notice.pdf>

New feature and functionality descriptions

CE9.10.0

Webex Edge for Devices

Important note: For new customers with organizations created after May 2020 CE9.12.3 is the minimum supported software version for Webex Edge for Devices. Attempting to link devices using CE9.10.x will fail. For customers already using Webex Edge for Devices with CE9.10.x may continue to do so and also link new devices using CE9.10.x.

CE9.10.0 comes with support for Webex Edge for Devices that allow you to link on-premises devices to the Webex cloud. This can be done with any registration or provisioning method that aligns with the prerequisites. Linking a device will enable a subset of optional cloud features while the device configuration management, registration, calling, and media services remain on-premises.

You need the Cisco Webex Device Connector tool that can be downloaded from Webex Control Hub > Devices > Resources. The Webex Device Connector app is targeted for release early 2020 and will allow you to link devices in bulk via your CUCM, TMS device export or by using a CSV file.

In order to link a device to Webex Edge for Devices, the device must have an encryption option key installed.

When the devices are successfully linked to Webex Edge for devices, they will be visible in Webex Control Hub together with the other cloud registered devices you may have. The following cloud features are currently available for a linked device:

- Cloud xAPI
 - Allow you to use the device xAPI via the Webex Teams API
 - Visit <https://developer.webex.com> for more comprehensive information and documentation
- Online / Offline and diagnostic status in Webex Control Hub
 - Support for receiving device alerts via the Control Hub Alerts if the online / offline or diagnostics status is changed
- Device historical analytics will be available in Webex Control Hub
- Hybrid Calendar support
- Webex Assistant

It is recommended that you first register your device on-premises service before you link it to Webex Edge for devices.

If your device is linked to Webex Edge for Devices, it should not be downgraded to an unsupported software version such as CE9.9.x or below. It is recommended that you first factory reset the device before downgrading to a software version that do not support Webex Edge for Devices.

Please refer to the Administrator Guide the Webex Help Center (help.webex.com) for more information on how to link your devices.

Webex Edge for Devices prerequisites

- Software version 9.10.0 or later (CE9.12.3 for new customers with organizations created after May 2020)
- The device you are linking must have the encryption option key installed in order to successfully connect to Webex. On most of the Room Series devices this key is embedded in hardware. If the encryption key is listed as not installed on the web interface, please contact your Cisco licensing representative to acquire this key. Encryption keys are prohibited in some countries.
- CUCM 12.5su1, or 11.5.x with the latest device pack installed
- Webex Control Hub administrator access
- Webex Device Connector tool that can be downloaded from Webex Control Hub
- A cloud services license (Cisco Collaboration Flex Plan)
 - You will require an active device subscription delivered through a Flex or Enterprise Agreement for the device which is being linked to Webex Edge for Devices.

A-FLEX-DEVICE or A-FLEX is the flex agreement PID you need to order from your partner or have an Enterprise Agreement or Active Host Agreement which gives Webex Control Hub entitlement for your devices


Webex Join button

Added a new native button for simplifying joining Webex meetings. Type in the meeting number to join a Webex meeting.

The button is enabled by default but can be disabled on demand from the device configuration in the web interface or xAPI.

This feature requires that your infrastructure is successfully able to route the webex.com domain.

Please note that the Join Webex Button is not available for devices operated by the TRC 6 remote control.




Other changes

New default password policy

A new set of xConfigurations has been added to make it easier to define a passphrase policy for your deployment. The device default password has not changed, but the policy for new passwords has changed to require minimum 8 characters by default.

Please refer to the administrator guide for more details about the new passphrase policy xConfigurations. You can also modify these via the device configuration in the web interface under UserManagement > PasswordPolicy.

A new “info” icon has been added to the user management site (Security > Users) to display the current password policy. You will get an error if the new password do not respect the password policy.



The new password policy configuration replaces the “Strong Security Mode” which is no longer available from CE9.10.0 and above.

Default self-signed certificate validity changed from 5 years to 1 year

The default time on the device self-signed certificate has changed to one year compared to 5 year in CE9.9.x.

Default SNMP Configurations

The default SNMP configurations has changed in CE9.10.0. When you upgrade from a lower version to CE9.10.0 your existing settings will be preserved. However, if you reset the device to factory default or receive a new device with CE9.10.0 or above, the default settings are now that SNMP is turned off and has no default Community Name.

Added support for SpeakerTrack 60 for Codec Plus

From CE9.10.0 the Codec Plus has added support for SpeakerTrack 60

New features and functionality in CE9.9.4

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.9.3

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.9.2

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - Resolved security issues related to CVE-2020-3143
 - CSCvs67680
 - CSCvs45241

For more information please read the PSIRT security advisory

- <https://tools.cisco.com/security/center/content/CiscoSecurityAdvisory/cisco-sa-telepresence-path-tr-wdrnYEZZ>

Earlier affected software versions have been removed and is no longer available to download, please read the software deferral notice

- <https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/TC7-CE8-CE9-deferral-notice.pdf>

New features and functionality in CE9.9.1

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - Fixes an issue with uploading large cop files on Cisco Webex Room Series devices via the web interface (CSCvr90764).

New features and functionality in CE9.9.0

- Wired Touch Re-direct
- Web Engine (Digital Signage, Web Views and Web Apps)
 - Digital signage
 - API driven web views
- Updates to the UI Extensions editor
 - In-Room Control renamed to UI Extensions
 - Web apps
- Whiteboard feature additions
 - Create, edit, and move stickies on your whiteboard and annotations
 - New whiteboard pen sizes
 - Create copies of whiteboards and annotations
- Re-worked user interface for network settings
- TLS configuration changes
- API for fetching custom wallpaper and branding from external URL
- Changes in ultrasound settings

New feature and functionality descriptions

CE9.9.0

Wired touch re-direct

Introducing support for wired touch re-direct, allowing you to control a PC running Windows using the on-screen touch interface on the Webex Board. This feature is only available on the second generation of boards (Webex Board 55S, 70S, and 85S).

To use touch re-direct, connect a PC to the Webex Board with a HDMI cable (wired sharing) and a USB-C to USB-C or a USB-A to USB-C cable. The feature is enabled by default, share your screen as normal when not in a call, to get started.

To make the PC easier to control on the Webex Board, you can switch your PC into tablet mode. This is normally achieved by selecting the action center on the taskbar next to the time and date. Here you can select tablet mode.

Note: To use touch forwarding for drag and drop on your installed browser you normally need to enable this manually in your browser.

For example the settings in Microsoft Edge would be:

In "about:flags": Enable Touch Events = always on

These settings are specific to your browser so you may need to refer to online help pages on how to enable these settings in your browser.

For known limitations, please refer to the known limitations and advisories section in this document.

Web Engine (Digital Signage, Web Views and Web Apps)

Devices supporting this feature: Webex Board series, Webex Room series and Desk Pro

The new web engine feature allows you to create web views on your device by opening web pages, which is displayed on-screen. This is the base feature that drives Digital Signage, Web Apps, and the API driven web views.

All the newer room devices in the portfolio supports Web Views but currently only Webex Board supports interactive mode, which means that you can interact with the web view on screen.

Standard video codes are supported, such as WebM and mpeg4. Decoding is done through software so it is not recommended to go beyond 1080p resolution, as this may lead to choppy performance.

Audio is also supported but must be enabled in the configuration as it is disabled by default. Volume will follow the device volume levels, but you can of course enforce volume and mute control on top of this using the JavaScript audio frameworks.

More information about this feature and xAPI commands is available in the administrator guide.

Certificates

The web engine will use the pre-installed list of known certificate authorities. Custom certificate authorities are currently not supported.

Digital Signage

Digital Signage is a feature that uses the web engine to create automatic web views when the device goes into half-wake. Instead of showing the half-wake screen it will open a specified URL and display the content until the device enters standby mode. It is possible to configure the standby timer to display the web page on screen for longer periods before entering standby.

This feature is great for re-purposing screens that are currently not in use to display information about your company, upcoming events or simply an image. You may use this feature with integrations, such as AppSpace or customize behavior with the macro framework.

Using a device that supports interactive web views, such as a Webex Board, the user may interact with the displayed content while digital signage is active.

Digital signage is not enabled by default and must be configured with a URL and requires that the Web Engine is enabled.

API driven web views

You may open web views using the xAPI, which makes it easy to create custom behavior together with UI Extensions, macros or external integrations.

Web Apps

You can use the UI Extensions editor to create web apps. Please see the section describing the UI Extensions editor, previously the In-Room Control Editor, below for more information.

Updates to the UI Extensions editor

In-Room Control is now renamed “UI Extensions”. You will now access the editor directly when clicking the link in the web interface. The pre-launch page has been removed and the link to download the editor locally has been moved into the menu of the editor itself.

While the editor looks and feels the same, it has a few updates that will simplify the creation of UI panels and allow you to work more efficiently.

- Colors have been added to the panel list so it’s easier to identify the panel and which color has been assigned.
- Widgets has been moved below the editor window, so you no longer have to switch between widgets and properties.
- Added a new Web App button. Currently only supported on all Webex Board models, you will get an option in the UI Extensions editor to create a Web App button.
 - To use the Web App button, it’s required that web engine is enabled on the device.
 - No macro is required to make the button open the web view on screen. Type in a valid external URL the Web App button should open on the screen.
 - The Web App icon will be automatically selected based on the site icon, normally the favicon of the site. You may also link directly to a specific icon using the Web app icon URL field that will be displayed as the button icon.

Supported icon types: .ico, .png, .jpg, .svg, .gif

Size: min 60x60, max 1200x1200 (square images for best results).
 - Pressing the newly created Web App button opens the specified URL on-screen.
 - Using this feature, you can make it easier for users to open web apps such as Jira, Miro, Office 365 and Google docs directly from a Webex Board.
- The different types of buttons (extensions) are highlighted. The editor first offers you the choice to create an Action Button, a Panel or a Web App.
- The export to codec button has been highlighted so it’s easier to see how to export the settings to the codec.

Whiteboard feature additions

Create, edit, and move stickies on your whiteboards and annotations

Sticky notes are now available in the whiteboard feature. Attach sticky notes of different colors, group them up and move them around. When you create a sticky note you can add a limited amount of text to the note using the on-screen keyboard. This feature is perfect for Kanban boards and interactive workshops or brainstorming. Note that you cannot draw on the sticky notes and they will be layered on top of each other in the order of creation.

New pen sizes available

Select between three pen sizes while drawing on the whiteboard by pressing the pen icon. You will be able to select between, small medium and thick. The line behavior has also been adjusted to give a better feel that you are drawing with a real marker, which means that the thickness of the lines may vary a bit depending on your drawing movement and speed.

Create copies of your whiteboard and annotations

By creating a copy of your current whiteboard, you can continue to draw without having to worry about overwriting the original drawing or annotation. If you quickly need to point out something in a drawing or annotation you can simply create a copy of the drawing and then go back to original when you are done. The copy of the whiteboard or annotated snapshot is stored in the Whiteboard menu.

“Create a copy” is found at the same place as send a copy to e-mail.

Re-worked user interface for network settings

The network settings page on the device user interface has changed. You will first see the current network setup, then you can open the Ethernet or Wi-Fi settings if you want to change them. A few settings, which were not available from the GUI before, are now added.

TLS Configuration Changes

For security reasons we have made some changes to the TLS configuration on HTTPS client, syslog, and SIP connections:

- You must explicitly turn off certificate verification if you don't want to perform a certificate check. By default, certificates are checked on all TLS connections.
- The minimum TLS version is increased from version 1.0 to 1.1 (exceptions for CUCM and SIP, which still allow version 1.0). Also note that the Webex cloud is using TLS version 1.2.
- You can configure certificate verification for provisioning, phonebook, and other HTTP servers separately. The former NetworkServices HTTPS VerifyServerCertificate setting, which

covered all these server types, are replaced by three settings: Provisioning TLSVerify, Phonebook Server [1] TlsVerify, and HTTPFeedback TlsVerify.

- You can configure certificate verification for external logging (both audit logging and regular logging).
- For SIP, the certificates are verified against the Custom CA list, which is uploaded to the device manually using the web interface or API. For other connections, the certificates are verified against either the Pre-installed CA list on your device, or the Custom CA list.
- We support TLS 1.3

NOTE: This change may affect your TMS connection if you have not enabled TLS1.1 or TLS1.2 on the server that is hosting the TMS deployment.

API for fetching custom wallpaper and branding from external URL

An xAPI command path has been added to allow the room device to download an image from an external URL and enable it as a branding image or a custom wallpaper. This command path makes it easier to automate the distribution of images without having to upload the image, but rather ask the device to download it. The device must be able to connect to the image URL from the network, and the resolution recommendations have not changed. More recommendations can be found in the web interface under personalization.

Supported image formats are .png and .jpg.

Please refer to the administrator guide to see the new xAPI commands for fetching branding and custom wallpaper from external URLs.

Note: Webex Boards do not support custom wallpaper.

Changes in ultrasound settings

All products now have the same default value for the *Audio Ultrasound MaxVolume* setting. The volume range is now also aligned between the different products, but we have not made any changes to the sound levels that are played out from a device.

New features and functionality in CE9.8.3

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - Resolved security issues related to CVE-2020-3143
 - CSCvs67680
 - CSCvs45241

For more information please read the PSIRT security advisory

- <https://tools.cisco.com/security/center/content/CiscoSecurityAdvisory/cisco-sa-telepresence-path-tr-wdrnYEZZ>

Earlier affected software versions have been removed and is no longer available to download, please read the software deferral notice.

- <https://www.cisco.com/c/dam/en/us/td/docs/telepresence/endpoint/software/ce9/release-notes/TC7-CE8-CE9-deferral-notice.pdf>
- Added HTTP rate limiting, please see the known limitations and advisories section in this document for more information.

New features and functionality in CE9.8.2

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
 - Fixes an issue with uploading large cop files on Cisco Webex Room Series devices via the web interface (CSCvr90764).

New features and functionality in CE9.8.1

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.8.0

- Support for Cisco Webex Board on-premises deployment
 - Infinite Whiteboard
 - SMTP support for saving whiteboards to e-mail
 - Touch 10 support
- Pre-installed list of Certificate Authorities (CA)
- HttpClient now supports GET / DELETE and PATCH requests
 - Added support for response body and headers
 - Now tries to validate the remote server certificate using the pre-installed list of Root Certificate Authorities
- Add participant to CMS conference from the room device UI
- xAPI over WebSocket
 - Added support for authentication using an auth protocol header
- USB Headset support for Cisco Webex Room Kit Mini, Room Kit, and Room 55
- API for onboarding devices to Webex Teams
 - Support for registering a device to Webex Teams in the web interface
- Improved USB experience with Room Kit Mini
- Support for more product specific configurations from CUCM 12.5 SU1
- Other changes

New feature and functionality descriptions

CE9.8.0

Support for Cisco Webex Board on-premises deployment

With the CE9.8.0 release you can now register the Cisco Webex Board (55/55S, 70/70S, 85S) to CUCM, TMS or VCS/Expressway in the same way as other room devices described in this document. Note that the Cisco Webex Board can also be deployed as a standalone H323 / SIP device and it will function as a local whiteboard even if the device is not registered anywhere.

Important: For Cisco Webex Board to support on-premises deployment the device must have the specific version of CE9.8.0 or later (downloaded from [cisco.com](https://www.cisco.com)) installed. Cisco TAC will only provide support for Webex Board in on-premises deployment if it has a supported software version installed and a valid service contract. Note that an on-premises registered Webex Board does not have the same features as you would have with Webex registration, with for example pairing with Webex Teams clients and opening Webex Teams spaces.

Switch from Webex to On-premises deployment

Go to [Cisco.com](https://www.cisco.com) and download a supported software version for your Cisco Webex Board model, the latest version is always recommended.

If the device is already registered to Webex you must first factory reset the Cisco Webex Board. You can do this from the web interface of the device by accessing it through Cisco Webex Control Hub or on the device itself. Standing in front of the device, hold one finger on the touch screen and tap the home button three times. In the Technical support screen, select “Factory Reset” button in the bottom left corner.

Once the device is reset, it should be displaying the “Welcome” screen. Now access the web interface on <https://<device-IP>> (replace the <device-IP> with the actual IP address of the device). Login with username “admin”, by default the password is blank.

Go to “Maintenance” → “Software Upgrade” and upload the supported software package you downloaded earlier. When you see the “Welcome” screen again after the upgrade you can follow the on-screen instruction to register the device in your on-premises environment or follow existing procedures as you would register any other device in your environment.

Please note that you may need a new device pack for your CUCM or a new version of TMS. Please see the below table for versions that has support for Cisco Webex Board.

Provisioner	Minimum Version	Note
CUCM	10.5 or higher	You may require a CUCM device pack that provides support for Cisco Webex Board on the version you are currently running.
VCS/Expressway	X8.6 or higher	
TMS	15.9 or higher	

The Cisco Webex Board has support for most of the features already available for other devices that has support for Collaboration Endpoint Software 9.8.0 with some exceptions. Some features are only available when pairing a Touch 10 to the Cisco Webex Board. Please see the matrix below for a list of features deemed significantly relevant:

UI Feature	On-screen UI	Touch 10	Not supported
Local multisite (add more participants)		x*	
Hold / Resume		x	
Transfer call		x	
Shared line appearance		x	
Local layout selection			x
CMS Layout selection		x	
ISDN dialing (ISDN Link)		x	
Save local favorites / Edit favorites (Phonebook)		x	
List favorites / recent calls	x (search only)	x	
Do not disturb		x	
Ringtones (three ringtones)	x	x	
In-Room Control	x**	x	
Minimizing remote presentation			x
Local preview of presentation – in call			x
Remote sharing of presentation	x	x	
Ad-hoc conferencing		x	

Far end camera control		x	
Self-view	x***	x	
Custom Wallpaper			x
Custom Text in awake state			x
Branding	x	x	
Extended input sources (virtual sources)			x
USB Input devices (keyboards)			x
Local whiteboarding and annotations (out-of-call)	x		
In-call whiteboarding			x****
Infinite whiteboard canvas	x		
Save whiteboard to e-mail (requires SMTP configuration)	x		
Basic calling features	x		
Advanced calling features		x	

* Requires the MultiSite option key installed. The Webex Board supports up to three remote participants.

** In-Room Control panels are displayed on the Cisco Webex Board screen only if it does **not** have a Touch 10 connected.

*** You can move the self-view around using the on-screen UI, but you can only enable self-view from the Touch 10.

**** It is currently not possible to do whiteboarding in a call.

Option keys that are supported (can be purchased separately):

MultiSite: Allows the device to host a call with up to three remote participants. Note that an additional audio participant on top of that is not supported.

RemoteMonitoring: Allows an admin to remotely capture snapshots of the input devices

Other than what is listed above the UI and settings are the same as when the device is registered in Webex. Cisco Webex Board also supports Macros, Backup and Restore (provisioning), xAPI access (CLI via SSH, XMLAPI, WebSocket, Console access using MicroUSB to USB-A serial) and Cisco Proximity.

Infinite whiteboarding

This is a feature that allows for a much larger whiteboard canvas. By holding two or more fingers on the whiteboard, you can extend the canvas to get a larger drawing area. You can use “Pinch and Zoom” to navigate through the bigger canvas.

Save whiteboards to e-mail

As the Cisco Webex Board is now registered on-premises it does not have the advantage of saving the whiteboard to a Webex Teams space. To save a whiteboard, you must connect the device to an SMTP server. This could be your enterprise own SMTP service, or a cloud service, such as Gmail or Office365.

Please follow the “Email Settings” wizard found on the Cisco Webex Board web interface (“Setup” → “Email Settings”) or set it up through the xAPI. Please note that if you are using a custom SMTP service you may need to upload a valid CA. A cloud service, such as Gmail should work without the need of uploading any certificates.

Touch 10 support

You can remotely pair one Touch 10 to the Cisco Webex Board. Only network pairing is supported.

By connecting a Touch 10 to the Cisco Webex Board you will gain more control of the device features. Using the Webex Board without a Touch 10 will give you limited call control and UI features. Please see the matrix above.

Known issues

There have been a few observations of touch sensitivity loss in CE9.8.0 on the Cisco Webex Board 70S. This can be noticed especially when using the stylus. It will be difficult to draw on the Webex Board. If this issue happens, please reboot the device. The issue is rare and will be resolved in CE9.8.1 in early August. Bug reference: CSCvq37645

Pre-installed list of Certificate Authorities (CA)

When configuring SMTP for saving Cisco Webex Board whiteboards to e-mail or using the HttpClient to send requests, the device will now try to validate the remote server certificate using a pre-installed list of certificate authorities. This list is similar to one you can find in a normal browser.

This list is currently only used by the SMTP configuration and HttpClient. For other services or custom Certificate Authorities, please follow the normal procedure by uploading these to the codec manually.

Support for HttpClient GET / DELETE and PATCH requests

CE9.8.0 comes with an update to the existing HttpClient feature for even more flexibility. We have added support for GET / DELETE and PATCH requests. The HttpClient now tries to automatically validate the remote server certificate using the pre-installed list of certificate authorities.

Added support for response body and headers

In addition to adding new request methods, response headers and body are now supported. The device can receive up to 100KB (100 000 Bytes) of response data when issuing a request to an external server that can be accessed through the Macro Framework. The response data is received regardless of the request type, but if the Content-Length exceed the supported amount of data it will display an error.

Add participant to CMS conference from the device UI

With this feature a user can seamlessly add additional participant to an ongoing CMS conference. When you are in a CMS conference call and add a new participant, the device tells the CMS to dial the participant using the Active Control mechanism. The CMS will then dial directly to the participant you want to add (the URI you typed in the address field in the UI of the room device). When the participant accepts the call, the participant will be added to the same CMS conference. Active Control needs to be enabled on the device.

Regardless of the multipoint mode configuration the participant will be added to the CMS conference and not create a cascaded conference as it would do in previous releases. This feature is on by default.

For this feature to work, the CMS must be on version 2.4 or higher and it will only work with SIP, Active Control is not available with H.323.

Note: The behavior of the add button has changed a bit in CE9.8.0/CE9.8.1 from previous versions. Please refer to the administrator guide for an overview of how the add button works in different conference scenarios.

	Multipoint mode		
Scenario	Auto	CUCMMRGL	Multisite
Calling CMS conference that supports add	Add button will show and will add the participant into the CMS conference	Consultative add Doing a consultative add will create a cascaded conference in this scenario.	No add button will be displayed (CE9.8.x), from CE9.9.0 the add button will be displayed again.
Calling CMS conference that does not support add	No add button will be displayed	Consultative add Doing a consultative add will create a cascaded conference in this scenario.	No add button
Calling another endpoint 1:1	No add button	Consultative add The call is escalated to a conference with three participants. Adding more participants to the same conference is allowed.	Add button is displayed and you can add participants to the call hosted by the endpoint itself up to the device limitation.

Please note that when you upgrade to CE9.8.1 the multipoint mode will automatically change to “Auto” for SX10 and DX80 unless you have the latest device pack installed. Without the device pack, UCM will not know about this configuration and the device will follow the default value (Auto). This may cause unexpected lack of add button in scenarios where this was previously available. If this happens, please change the configuration accordingly or update the UCM with the latest device pack.

xAPI over WebSocket: Authentication using auth protocol header

Added support for authentication using an auth protocol header. The complete header looks like this:

```
Sec-WebSocket-Protocol: auth-YWRtaW46cGFzc3dvcmQ
```

“YWRtaW46cGFzc3dvcmQ” is the base64 representation of admin:password. Because browser-based clients do not have direct control over headers, you can use the auth protocol header to authenticate to a device directly from a browser using Javascript.

Example JavaScript (WebSocket module):

```
webSocket = new WebSocket(webSocketURL, "auth-" + btoa(username + ":" + password).replace(/[\/+]=]/g, function(c){return {'+':'-','/':'_','=':''}[c]}));
```

Note that the base64 encoded username and password must be “url safe”, hence the character replace function.

USB Headset support for Cisco Webex Room Kit Mini, Room Kit, and Room 55

The same USB Headset support as for the DX Series is now enabled for the Cisco Webex Room Kit Mini, Room Kit, and Room 55. This means that you can connect a USB Headset, Handset or USB Bluetooth dongle to the USB-A input on these devices. Please refer to the below link for a list of tested headsets and handsets that have been tested to work with the above devices.

<https://help.webex.com/nkiifbo/>

xCommand for Webex device activation

In previous versions you had to be in front of the device to activate it to the Webex Cloud service. The new xCommand allows programmatic / remote Webex activation. If you have many devices already registered on-premises you can use this API to issue the activation code. The device will switch to Webex automatically.

```
xCommand Webex Registration Start
  ActivationCode(r): <S: 16, 19>
  SecurityAction(r): <Harden, NoAction>

xCommand Webex Registration Start ActivationCode: 1234-1234-1234-1234
SecurityAction: Harden

xCommand Webex Registration Start ActivationCode: 1234123412341234
SecurityAction: Harden
```

Note: If SecurityAction is set to “Harden” the device will lock down the device as it would when you register the device to Webex normally and remove any customizations on the device along with other configurations. By specifying NoAction, it will keep the customizations you have (In-Room Control and Macros) and not remove any local accounts on the device.

If this command is issued from a factory reset state, it will not remove the “Welcome” screen as the device is not initially configured yet. But it will skip the “Activation step” as the device is already activated and go straight to time zone configuration and other configuration steps for the device.

Support for activating a device to Webex through the web interface

If the device is not registered anywhere and you log into the web interface, you will get an option to register the device to Webex on the landing page. You will only get the option to type in the activation code to register the device. Note that when you use the web interface for registering the device, it will use “Harden” by default. Your current web session will be terminated once the device is successfully activated. If you need to access the web interface after the activation must do that through Control Hub.

H323

Status	Inactive
Gatekeeper	-
Number	-
ID	-

SIP

Status	Inactive
Proxy	-

This video system is not registered

In order to place calls with this video system, it needs to be registered to a call service.

[Click here to register to Webex](#)

Improved USB experience with Room Kit Mini

The Room Kit Mini can now be used as normal while being connected through USB. This means that it will no longer always be in “Do not disturb” mode when connected to a computer. As soon as you start using it as a web camera (start the camera in a desktop application) or speaker (playing audio from a desktop application), the device will go into “Do not disturb” mode as in previous software versions as long as it is not already in a call.

This is now the default behavior and the configurations related to this setup has been removed.

Support for more product specific configurations from CUCM

12.5 SU1

A device running CE9.8.0 now supports being provisioned with a wider range of product specific configurations when registered to a CUCM with version 12.5 SU1 and higher. Please refer to the release notes below for more information.

https://www.cisco.com/c/en/us/td/docs/voice_ip_comm/cucm/rel_notes/12_5_1/SU1/cucm_b_release-notes-for-cucm-imp-1251su1/cucm_b_release-notes-for-cucm-imp-1251su1_chapter_01.html#reference_7E7941433CC7035A179DD556C1F2E9E9

Other changes

Reduced the accepted expiration time length for uploaded certificates. If you have a certificate has a longer lifetime than 10 years, you will not be able to upload the certificate. The change has been done to confirm on the Cisco PSB (Product Security Baseline) requirements that does not allow certificates with lifetimes over 10 years.

New features and functionality in CE9.7.2

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.7.1

- xAPI over WebSocket (XoWS)
- Privacy mode – disable or enable video in a call
- Room Analytics - Ambient noise reporting
- Room Kit Mini - Support for 1080p video when used as a USB camera
- Edit favorites in OSD
- Support for connecting multiple Sony cameras (SRG/EVI)
- Audio Console – Graphical Equalizer
- Android to CE9.7.1 conversion software released for DX70 and DX80 (April 25th 2019)

New feature and functionality descriptions

CE9.7.1

xAPI over WebSocket (XoWS)

Added support for accessing the xAPI using WebSocket. A WebSocket is a bi-directional persistent connection between a client and the server where information can flow back and forth without the overhead of initiating a new TCP connection / authentication for every request.

From CE9.7.1 the room device will act as a WebSocket server with direct access to the xAPI using JSON RPC 2.0 as the data transport. After establishing a WebSocket connection to the room device, you can register feedback, execute configurations, commands or get the status of the device by sending JSON documents over the WebSocket connection. The client will also receive unsolicited data from the server for example, feedback events if registered.

This feature is mainly targeted integrators and is a modern alternative to access the xAPI compared to for example, SSH or serial.

For more information on how to get started with xAPI over WebSocket, please refer to the official xAPI over WebSocket guide found here:

<https://www.cisco.com/c/en/us/support/collaboration-endpoints/spark-room-kit-series/products-command-reference-list.html>

Privacy mode – disable or enable video in a call

This feature adds a new button on the Touch 10 or in the on-screen UI that allow you to disable video while in a call. The far-end participants will only see a placeholder image indicating that you have disabled the video on your device. On the local end, an icon will be displayed on the screen, indicating that you are currently not sending video.

Room Analytics – Ambient Noise reporting

Ambient Noise reporting will use the device microphones to estimate the ambient / background noise. The value is an A weighted decibel value of the ambient noise level (dBa). Note that the value is not a calibrated sound pressure level (SPL) so it has to be evaluated as a relative value of the ambient sound level in the room.

The feature is disabled by default and can be enabled by setting the Ambient Noise reporting to “On” in the xAPI. *xConfiguration RoomAnalytics AmbientNoiseEstimation Mode: On*

The estimated value is accessible through the xAPI with the following command, *xStatus RoomAnalytics AmbientNoise Level*.

Room Kit Mini – Support for 1080p video while used as a USB camera

In previous version only 720p video resolution was supported. 1080p resolutions are supported from CE9.7.1 when the Room Kit Mini is used as a USB camera.

Edit favorites in OSD (DX70 and DX80)

This feature allows a user to edit the contact information in their local favorites from the OSD interface of the DX70 and DX80 in the same way that was introduced for the Touch 10 in CE9.6.1. Note that this feature is not available when using the TRC6 remote control.

Support for connecting multiple Sony cameras (SRG/EVI)

Connect multiple Sony SRG / EVI cameras to room devices that has support for the camera. The number of cameras is limited by the device you are connecting the cameras to. For example, Cisco Webex Room Kit Pro supports up to seven connected cameras, and Cisco Webex Room Kit Plus supports up to three connected cameras. Support for these cameras was added in CE9.4.0, please refer to the 9.4.0 section in this document for more information.

Audio Console – Graphical Equalizer

Audio Equalizer is already available in previous software versions through the command line interface (xAPI) only. From CE9.7.1 we now added a graphical equalizer in the Audio Console to simplify usage and modifications. The graphical equalizer setup is available in the Audio Console app on the room device web interface.

Allows you to create up to eight different equalizer setups and attach them to an output or a microphone input.

An equalizer can for example, be used in scenarios where the user wants to tweak the audio experience on microphone inputs or if the output equipment is expressing too much bass or treble. The graphic equalizer makes it easier for users to customize the overall audio experience on the analog line in and outputs.

Note: You can only attach an equalizer to an analog input, i.e. microphones or output

New features and functionality in CE9.6.4

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.6.3

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.6.2

- Minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.6.1

- Support for Cisco Webex Room Kit Mini
- Custom HTTP POST and PUT through xAPI and Macros
- In-Room Control: Third-party USB input devices
- Hide default GUI panel buttons
- Edit favorites directly from the Touch 10
- Support for HDCP on additional room devices
- Audio Console updates
- ICE support in MRA scenarios
- Active Control: Ability to start a recording from the UI in a CMS meeting
- Other changes
 - Added configuration for prioritizing presentation bandwidth
 - Ability to enable true color on branding in awake state

New feature and functionality descriptions

CE9.6.1

Support for Cisco Webex Room Kit Mini

Cisco Webex Room Kit Mini is a new room device in the Cisco Webex Room Series that can be registered to use the Webex Teams cloud service or existing on-premises infrastructure. For UCM registration, please make sure you have installed the latest device pack.

The Room Kit Mini has USB passthrough that provides video, microphone and speakers over one USB cable to a connected computer.

For more information on the Cisco Webex Room Kit Mini hardware and technical specifications, please refer to the [product data sheet](#).

Please see the “Known Limitations and advisories” section further down in this document under “Software upgrade” on how to upgrade software.

Custom HTTP POST and PUT through xAPI and Macros

Added support for custom HTTP POST and PUT requests through the xAPI and Macros. This feature enables you to send outgoing HTTP POST or PUT to a third-party HTTP server on-demand with custom payloads.

This integration feature is designed to provide more flexibility in terms of data collection or to enable your third-party devices as part as your integration setup. Adapt your HTTP POST or PUT requests to your existing services.

```
xConfiguration HttpClient Mode: Off / On
```

The HTTP request is made using the xAPI and supports up to ten headers and the payload can be constructed using multiline input. The xAPI command can also be utilized with a Macro to create dynamic and event-based requests.

As an administrator you can also control which host (IP or FQDN) the device is allowed to send requests to by using the allow lists configurable through the xAPI.

This feature only allows you to send outbound HTTP PUT or POST. GET requests or processing incoming POST or PUT response payloads is not supported but you will be able to see the status code of your request to verify delivery.

Certificate verification is performed by default on all outgoing HTTPS requests. This requires that you manually upload the CA certificate to verify the remote host. A standard list of CA certificates is not present by default. You can enable certificate verification bypass (not recommended):

```
xConfiguration HttpClient AllowInsecureHTTPS: False / True
```

All requests will still be verified by default but with the above configuration enabled you can explicitly bypass the verification for the particular request.

Please follow the below link for developer examples:

<https://developer.cisco.com/site/roomdevices/>

```
xCommand HttpClient Post Header: "Content-Type: application/json" Url: https://host
AllowInsecureHTTPS: True
```

For known limitations, please refer to the known issues and limitations section in this document.

In-Room Control: Third-party USB input devices

You can now connect third-party USB input devices such as USB keyboards or wireless media remotes that comes with a USB Bluetooth dongle. The connected device must be seen by the codec as a generic keyboard, connecting a USB mouse or other non-keyboard devices is not supported.

By default the device is configured to not detect USB input devices. Enable through the web interface or using the xAPI:

```
xConfiguration Peripherals InputDevice Mode: Off / On
```

Once the feature is enabled and a USB input device is connected, each key press will generate an event in the xAPI about which button was pressed or released. Based on the generated event you can trigger actions the same way as with the In-Room Control design on the Touch 10 panel, for example pressing the letter "O" on a connected keyboard will generate the following events:

```
*e UserInterface InputDevice Key Action Key: KEY_O
*e UserInterface InputDevice Key Action Code: 24
*e UserInterface InputDevice Key Action Type: Pressed
** end
*e UserInterface InputDevice Key Action Key: KEY_O
*e UserInterface InputDevice Key Action Code: 24
*e UserInterface InputDevice Key Action Type: Released
** end
```

This feature is designed to be used in combination with macros or third-party control systems.


Supported only for Cisco Webex Room Series devices, DX70 and DX80.

Please follow the below link for developer examples:

<https://developer.cisco.com/site/roomdevices/>

Hide default GUI panel buttons

In CE9.6.1 you can customize the default UI buttons. Hide the default Call, Share or all the buttons at once including Meetings and Messages. See below for an example Touch 10 view with all default buttons hidden, note that custom buttons like In-Room Control buttons will not be hidden:



Hiding the default buttons do not remove the sharing or call functionality, you can still share content or make calls if you pair your Proximity client to the device or execute the equivalent API commands.

You can only exclusively hide the Call, Share, Mid-Call Controls and the End Call button. To hide other buttons that are related to provisioned features such as, Meetings or Messages (Voicemail) you must hide **all** the buttons or do not provision these features to the device. In-Room Control buttons are removed using the In-Room Control editor.

If you hide all the buttons without adding In-Room Control panels, the user will be presented with a blank user interface without buttons.

The settings menu can currently not be hidden.

Note: You can rearrange the ordering of the In-Room Control buttons, but you cannot do this for the default panel buttons.

Edit favorites directly from the Touch 10

When you select a contact in your list of favorites you will see a “More” button. By pressing this button, you are given the option to edit the contact entry. You can modify the video address and the name of the contact. In previous versions, favorite entries could only be edited from the codec web interface.

Support for HDCP on additional room devices

Room 55 already have support for HDCP and from CE9.6.1 we added HDCP support for additional devices, please see the matrix below.

Device	HDCP Support	I/O*	HDCP Version
Cisco Webex Room 55	Yes	Input 3 Output 1	1.4
Cisco Webex Room 55 Dual	Yes	Input 2 Output 1	1.4
Cisco Webex Room 70	Yes	Input 2 Output 1	1.4
Cisco Webex Room 70 G2	Yes	Input 5 Output 1 and 2	1.4
Cisco Webex Room Kit Pro (Codec Pro)	Yes	Input 5 Output 1 and 2	1.4
Cisco Webex Room Kit Plus (Codec Plus)	Yes	Input 2 Output 1	1.4
Cisco Webex Room Kit	No	N/A	N/A

* The input number above refers to the xAPI input number where you can configure HDCP. The physical input connector number may differ from the xAPI input number.

We require that the screen that is connected to the output is HDCP compliant and the same restrictions applies:

- You cannot share content from a HDCP enabled input in a call, regardless of what you have connected to it (even a PC). This also applies for source compositing HDCP enabled inputs in the main video or content stream, which will result in a black frame.
- When sharing content using a HDCP enabled input on a dual screen device that only have HDCP support for one output, will only allow you to see content on one screen.

Please see the known limitation section for more information

Audio Console updates

Audio Console was introduced in CE9.5.0 as a preview feature and is now fully supported from CE9.6.1. A few updates have been applied to increase usability.

Important changes:

- **Warning:** Before upgrading to CE9.6.1, make sure you note down the Audio Console setup as the will be reset to default when upgrading from CE9.5.x to CE9.6.1. If you have not used the Audio Console in CE9.5.x, you can disregard this warning.
- Audio Console is disabled by default and must be enabled. You can enable it by Accessing
- By default, the Audio Console is In Automatic Setup and the codec decides the best audio layout (default). If you have misconfigured the Audio Console you can re-enable Automatic Setup to restore the default audio layout by clicking “Switch to automatic” in the Audio Console.

Other changes:

- New UI to edit gains and delete connections
 - Right click the connection link to edit the gain or delete the link.
- Improved drag and drop
 - You can now drop a connector on the whole group. Drop zones are clearly indicated while dragging and when you can drop the connection link.
- Support for remote groups
 - In alignment with “TC-Console” you cannot set connections with remote groups until the device is actively in a call.
- Improved scrolling behavior
 - Sidebars can now be scrolled independently from the area in the center which should make the Audio Console easier to use on smaller screens.

Fixes:

- Disable echo cancelling and noise reduction when the group mode is set to “Direct”
- Removed the “Beta” label in the Audio Console title area
- Display mute and DelayMeasurement status on groups and connectors
- Display a warning prompt before deleting an entire group of input or output connectors

Supported devices: Cisco Webex Room Kit Pro, Cisco TelePresence SX80, Cisco TelePresence MX700, MX800 (D), Cisco Webex Room 70G2

ICE support in MRA scenarios

Added support for using ICE in MRA scenarios where ICE configurations can be provisioned through UCM. To see these configurations in UCM you may need to install a new device pack.

Active Control: Ability to start a recording from the UI in a CMS meeting

A recording button will appear on in the UI that lets you initiate a recording in a CMS meeting if the CMS is correctly configured with a recorder and active control is successfully negotiated between the CMS and the room device. Active control is enabled by default on the room device, but if you are experiencing issues with this, make sure the configuration is set to "Auto".

Other changes

- Added configuration for prioritizing content channel bandwidth and is similar to the previous "xConfiguration Conference VideoBandwidth MainChannel Weight" configuration that was removed. The new configuration is "xConfiguration Video Presentation Priority: Equal or High". See below for bandwidth division in percent for both configurations:
 - Equal: 50/50 same as previous releases
 - High: 25/75 in favor of the content channel
 - Due to an issue, this configuration can currently only be configured through the web interface, this will be resolved in a later version.
- Ability to enable true color on branding in awake state. If this is enabled the system will not do any visual modifications to the colors of uploaded brand images (awake state only).
 - xConfiguration UserInterface Branding AwakeBranding Colors: Auto or Native

New features and functionality in CE9.5.3

- This is a minor release and contains bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.5.2

- This is a minor release and contain one bug fix (CSCvn35929)

New features and functionality in CE9.5.1

- This is a minor release and contain bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.5.0

- Feature preview: Audio Console
- Presentation source composition
- PresenterTrack support for Cisco Webex Codec Plus
- New room mode: Classroom
- Keyboard localization (Korean)
- Cisco TelePresence SX80 and SX20 Screen status monitoring (CEC)
- Welcome banner in Web GUI and CLI
- Rebranding from Spark to Webex

New feature and functionality descriptions

CE9.5.0

Feature preview: Audio Console

The java-based CE Console application is no longer maintained and is replaced with a new web application (Audio Console). The Audio Console will replace the existing CE Console and is natively available from the web interface of Cisco TelePresence SX80 and Cisco Webex Room Kit Pro only in CE9.5.0. Audio console is found in the web interface under *Setup - Audio Console*.

The Audio Console is delivered in CE9.5.0 as a feature preview and is labeled as such in the web application, the reason behind this is because we would like feedback on the interaction model regarding setting up local reinforcement and the persistency model.

The Audio Console provides embedded UI for modifying the audio routes on the device in the same fashion as the CE Console with drag and drop interaction. The Audio Console will generate a macro with the configured settings, which means that Macros are required to run while using Audio Console, this will be enabled automatically when you save the Audio Console layout.

For known limitations in this version, please check the Known limitations section in this document.

For more information on how to get started with the Audio Console, please refer to the Customization Guide for CE9.5.0.

PresenterTrack support for Cisco Webex Codec Plus

The PresenterTrack feature is now available for Cisco Webex Codec Plus. The feature requires a Precision 60 camera connected to the Codec Plus and is configured through the web interface. The steps to configure are not different from the room devices that already support this feature, please refer to the administrator guide for more information about the configuration of PresenterTrack.

Presentation source composition

In CE9.2.1 we introduced a feature allowing image composition in the main video channel.

Presentation source compositing allows you to do the same compositing in the presentation channel.

With presentation source composition, you can compose up to four input sources into one image (the number of input sources you can compose is also dependent on available physical input sources on the codec).

For example:


Cisco TelePresence SX80 / Cisco Webex Room Kit Pro: **4**

Cisco Webex Room Kit Plus: **3**

Cisco Webex Room Kit / Cisco TelePresence SX20: **2**

This image will be sent in the presentation video stream to the far end in a call. Source composition can only be enabled through the xAPI, so we recommend creating an In-Room Control UI combined with a macro to control the compositions on demand while you are in a call.

Please see below for the supported layouts (single source sharing is the same as before).



The above illustration shows how the images can be stitched together. The frame placement is depending on which order you issued the input sources in the command.

Please refer to the administrator guide for more information on the xAPI operations.

New room mode: Classroom

Classroom is a new room mode, similar to Briefing Room, that builds on PresenterTrack and SpeakerTrack. When activated, it will automatically switch between a camera filming the presenter and a camera filming the audience. Unlike Briefing Room, it does not require a specific number of screens, and it does not automatically switch local layouts.

This mode is supported by Cisco Webex Room Kit Pro, Codec Plus, Room Kit Plus, Room 70 and Cisco Telepresence SX80.

Classroom mode can be customized using monitor roles and macros. Please visit <https://developer.cisco.com/site/roomdevices/> for more information on macros and integrations.

Keyboard localization (Korean)

Support for keyboard localization for Korean. When you select Korean as the preferred language the keyboard will be localized as well. This is valid only for the Touch 10 and not the On-screen UI.

Cisco TelePresence SX80 and SX20 screen status monitoring (CEC)

CEC is disabled by default on the SX10 and must be enabled through the web interface. SX10 had a CEC implementation in previous releases. The CEC implementation is now in parity with the Cisco Webex Room Series. New CEC xCommands are available. Please refer to the CE9.5.0 admin guide for more information.

Welcome banner in Web GUI and CLI

Enable welcome banner in the device command line interface (xAPI) and Web GUI. After you have logged into the device CLI or Web interface, a welcome banner will be displayed if configured. The welcome banner can currently only be configured through the xAPI using the command:

xCommand SystemUnit WelcomeBanner Set

The above command is a multiline command. For more information about multiline commands and how to use this feature, please refer to the CE9.5.0 Administrator Guide.

Rebranding from Spark to Webex

Rebranding of elements from Spark to Webex continues. The product id in the web interface has now been rebranded.

New features and functionality in CE9.4.2

- This is a minor release and contain bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.4.1

- This is a minor release and contain bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.
- Android to CE9.4.1 conversion software released for DX70 and DX80

New features and functionality in CE9.4.0

- Support for Cisco Webex Room Kit Pro
- Rebranding from Spark to Webex in GUI
- Re-styled time zone and language settings in GUI
- Support for content sharing using H263 in a call between Cisco Webex Room Series and legacy MXP systems
- Increase max number of simultaneous paired Cisco Proximity clients with Cisco Webex Room Series
- CUCM provisioning of the admin settings lockdown configuration
- Support for Sony SRG/EVI-120DH
- Enable manual backlight compensation in GUI for Cisco Webex DX series
- Changed default HTTP mode from HTTP+HTTPS to HTTPS

New feature and functionality descriptions

CE9.4.0

Support for Cisco Webex Room Kit Pro

Cisco Webex Room Kit Pro is a powerful new room device in the Cisco Webex Room Series that can be registered to use the Webex Teams cloud service or existing on-premises infrastructure. For UCM registration, please make sure you have installed the latest device pack.

For more information on the Cisco Webex Room Kit Pro hardware and technical specifications, please refer to the product data sheet when it becomes available.

Please see the “Known Limitations and advisories” section further down in this document under “Software upgrade” on how to upgrade software.

Rebranding from Spark to Webex in GUI

GUI elements that displayed Spark is now changed to Webex. In the GUI activation flow you will now see Webex Teams instead of Cisco Spark. Room devices that were previously named Cisco Spark is now Cisco Webex, for example Cisco Spark Room Series is now Cisco Webex Room Series.

Re-styled time zone and language settings in GUI

The time zone and language settings in GUI has a new look and the configuration flow has been updated.

Support for content sharing using H.263 in a call between Cisco Webex Room Series and legacy MXP devices

Cisco Webex Room Series had a limitation in earlier software versions where it could not receive or share content in a separate content channel due to lack of H.263 support. Sharing content from Cisco Webex Room Series to a MXP device would in earlier versions compose the presentation into the main video stream, sharing from the MXP would not work.

Support for H.263 content sharing between MXP and Cisco Webex Room Series is now available in CE9.4.0. Please see below for the tested and supported scenarios where H.263 content sharing works as expected:

- Direct H.323 calls (IP dialing) between a Cisco Webex Room Series device and a MXP device.
- MXP registered on VCS on H323 and a Cisco Webex Room Series device registered to the same VCS on either SIP or H.323. Note that making a H.323 to SIP call on a VCS requires an interworking option key installed on the VCS.

Note that there are limitations on other scenarios:

SIP in general or other SIP scenarios where the Cisco Webex Room Series device is registered on CUCM or performing direct SIP calls between itself and the MXP (IP dialing) is not considered supported scenarios for the scope of this interoperability feature.

Support is limited to calls to legacy MXP devices for the specific scenarios mentioned above. Dialing to legacy third-party devices that has support for the H.263 protocol in the content channel, for example older Polycom devices, may work but is not considered as supported by Cisco.

MPX is a legacy product that is no longer supported by Cisco in any way. This software feature is added for those who has MPX devices in a mixed environment with newer devices while the old devices are waiting to be phased out.

Increase max number of simultaneous paired Cisco Proximity clients with Cisco Webex Room Series

A Cisco Webex Room Series device can have up to 30 paired clients simultaneously as long as the Proximity service “ContentShare ToClients” is disabled. The Proximity services “CallControl” and “ContentShare FromClients” can be enabled and the room device will be able to pair up to 30 clients. If “ContentShare ToClients” is enabled, the client limit is decreased to 7, which is equal to earlier software releases.

CUCM provisioning of the admin settings lockdown configuration

CE9.4.0 has added support for CUCM provisioning of the admin settings lockdown configuration that was introduced in CE9.2.1 (please see the CE9.2.1 feature description in this document for more information). The settings menu can now be locked down on all the endpoints using bulk configuration through CUCM.

Note that your CUCM may require the latest device pack in order to expose the new fields for this configuration.

Support for Sony SRG-120DH and EVI-120DH

Added support for a specific Sony camera model (SRG-120DH/EVI-120DH). The EVI-120DH is only sold together with Cisco Webex Codec Plus as a bundle but will work with any other device that also support a standalone Precision 60 camera for example, Cisco Webex Room Kit Pro and Cisco TelePresence SX80.

Please see below for some of the supported and not supported scenarios.

Codec camera features	Supported?
Pan, tilt and zoom (PTZ)	Yes
Presets	Yes
Positional resets and xCommand camera controls	Yes
xStatus with specific camera details	Yes (Serial number will not be shown)
Use as PresenterTrack camera	No
Software upgrades	No
Use together with other cameras (Cisco Webex Quad Camera, Precision 60)	Yes
FECC	Yes
Camera flip (upside down)	No
Mirror	Yes

In order to pair the camera over IP to a device the camera must have the dip-switch 1, located underneath the camera base, set to "On" for IP communication. System select must be set to position 7 (selection wheel located on the side of the camera) to enable Visca control. Connect the camera to one of the local switch ports of the device (same procedure as pairing a Precision 60) and the camera should automatically pair to the room device. If necessary, please connect a switch to extend the switch ports on the room device in order to connect the camera.

Note: Do not use the IR remote that comes with the camera, use the built-in camera control on the room device. Controlling the camera using the camera remote control may cause the codec to lose the cameras current position. Turning off the camera using the camera remote control causes the camera to go into standby. The EVI-120DH camera is shipped without a remote control. The codec is not able to wake up the camera from this state.

Enable manual backlight compensation in GUI for DX series

A new setting is now available in the main menu of the DX that will enable or disable backlight compensation. This is a fixed setting that will increase (on) or decrease (off) the sensors brightness levels in order to compensate for sunlight or other bright light sources behind the user.

Note that the backlight compensation is a manual setting (on or off) and will set the sensor to a fixed level and is not auto adjusted to the backlight.

Changed default HTTP mode from HTTP+HTTPS to HTTPS

Please read more about this change in the “Important notes and warnings for this software version” section for more information as it may affect factory new or factory reset devices in an environment that has existing HTTP implementations for managing the room devices.

New features and functionality in CE9.3.3

- This is a minor release and contain bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.3.2

- This is a minor release and only contain bug fixes
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.3.1

- This is a minor release and only contain fix for CSCvj32935
 - Please see the “Open and resolved caveats” section for a link to the resolved defects in this release.

New features and functionality in CE9.3.0

- Backup and restore settings and custom elements
- In-Room Control updates
- Support for ISDN Link
- One Button to Push Snooze (OBTP)
- SX10 Screen status monitoring (CEC)
- Adjust call rate before making a call (UI)
- Select ringtone and adjust ringtone volume (UI)
- Other changes
 - Resume postponed upgrades (UI)
 - Hide sensitive information (UI)
 - Accessibility: Flashing screen on incoming call
 - Mirrored self-view for Cisco Webex DX Series

New feature and functionality descriptions

CE9.3.0

Backup and restore settings and custom elements

CE9.3.0 includes a new and improved version of “Backup and Restore”. In Previous versions, you could backup your room device by saving the configuration file but not include other elements, such as Branding, Macros, Favorites (Local phonebook), Sign-In Banner and In-Room Control panels.

The solution implemented in CE9.3.0 will allow you to backup and restore all of these features in a bundle. By provisioning a non-system specific backup bundle, you can setup multiple room devices with the same setup of Macros, Branding images and more using TMS, CUCM or third-party integrations.

Getting started

The UI is available on the room device web interface at “Maintenance → Backup and Restore”. By default, it includes all configured elements available but you can simply uncheck elements before you create the backup. This process generates a zip file that contains all the information and content necessary to restore.

Restore or provision across multiple room devices

The backup file can either be restored manually through the same page (for system specific settings) or you can generalize it as a template with the purpose of provision it across multiple room devices using UCM, TMS, or third-party integrations using existing API interfaces.

In CE9.3.0 you can include the following in the backup bundle if configured:

- Favorites (Local phonebook)
- Sign-In Banner
- Branding images (Halfwake Background, Halfwake Branding, Branding)
- Macros (Select all or pick single macros you want to backup)
- In-Room Control Design
- Configuration document (Select configurations you want to backup)

Requirements

The backup bundle can be hosted on the UCM TFTP file service, TMS or a custom web server reachable by the room device on HTTP or HTTPS.

Note: Currently the room devices only support fetching the bundle from a web service (GET).

Important: If you back up a room device with the intention of distributing it across multiple devices, you should remove all device specific configurations from the configuration document. On the same

page as you create the backup, there is a button that can remove these configurations for you. If you provision a backup bundle to multiple devices with device specific configurations (containing network information) you may end up with multiple unreachable devices. Provisioning using UCM will currently not restore the configuration document at all to avoid these scenarios. See the UCM provisioning section.

TMS provisioning

TMS can provision the command necessary for the room device to fetch the backup bundle from the web service where the bundle is hosted. This is done by creating a configuration template with a custom command containing the following XML string:

```
<Command><Provisioning><Service><Fetch>
<URL>https://host/backup.zip</URL>
<Checksum>c9d1feb...</Checksum>
<Origin>Other</Origin>
</Fetch></Service></Provisioning></Command>
```

Replace the URL content with your web server path to the backup bundle and the sha512 checksum of the backup bundle located on this URL. Note that the URL can be different depending on where you choose to host the backup bundles. The origin field is optional and tells the device if it should restore the configuration file or not, default is “Other” which will restore configurations, while “Provisioning” will not restore configurations.

There is no TMS version requirement to issue this command as all newer versions of TMS has support for this. Please follow the TMS version requirement for CE9.x room devices if in doubt.

When the configuration template is applied to a room device the room device will download and restore the backup bundle automatically.

UCM customization provisioning

UCM provisioning requires a new device template that adds a bulk customization section to the product specific configuration layout. In these fields, you apply the URL to where the backup bundle can be downloaded, hash type (sha512) and hash (checksum) respectively. When applied, the room devices will download and restore the backup bundle once. In order to re-provision a backup bundle, you must either factory reset the device and re-provision or upload a new backup bundle with a different checksum and apply configuration accordingly from UCM.

UCM can host the files by uploading the bundles through UCM OS Administration to the TFTP service. The files will be available on HTTP (<http://ucmhost:6970/path/to/backup.zip>) and from UCM 11.5/12.x HTTPS (<https://ucmhost:6971/path/to/backup.zip>). The checksum is required regardless of HTTP or HTTPS when provisioning through UCM.

Limitation: To avoid misconfiguration scenarios of system specific network and registrar info, the configuration.txt will be intentionally **ignored** when provisioning using UCM (not applicable for TMS or

Third-party provisioning unless “Origin” specifies “Provisioning”, please see the TMS provisioning section above). UCM provisioning of the backup bundle will currently only setup Branding, Macros, Sign-In banner, Local phonebooks, and In-Room Control designs if those are included in the backup bundle.

Checksum verification

When the device receives the command to download a backup-bundle on HTTP, it will require a sha512 checksum of the backup bundle in the request to avoid man in the middle attacks. With HTTPS, the checksum is not required with the exception of UCM provisioning but recommended.

At the end of this document there are instructions on how to generate sha512 checksums for files.

Note: If you open the restore section on the room device web interface and select the newly created backup bundle, the room device will generate and display the sha512 checksum of the selected file.

Other information

If the backup that is restored contains Macros, the Macro runtime will be set to enabled, restarted and all the Macros are automatically activated.


If the backup contains branding images the Wallpaper configuration will automatically be set to “Auto”. This will enable the branding images to be displayed if you were previously using custom wallpapers.

Note: The room device will always try to verify the server certificate if HTTPS is used and the sha512 checksum is not provided.

In-Room Control Updates

Highlighted updates:

- The In-Room Control editor and the UI is now updated to support up to 20 In-Room Control panels
- A few new icons are available in the editor (Cisco Webex, Proximity and Webex logo)
- Set the color of the In-Room Control panels from a selection of colors in the editor
- Double click on the text elements to edit text directly on the design in the editor
- Drag and drop exported In-Room Control XML files directly into the editor to load
- Mechanism for creating standalone trigger-buttons
- The global entry point (top right corner) has been removed



All the panels are now displayed on the home/in-call screen. A “More..” button appears if the amount of panels exceeds the available space on the UI. Note that the In-Room Control panel is removed from the top menu bar. By pressing “More...” a scrollable pane with the exceeding panels is displayed.

The availability concepts of out-of-call only, in-call only or always still applies.

You can create as many panels as you want in the editor but only a total of 20, depending on priority, will be available in the home screen as well as for the in-call scenario.

With the trigger button functionality, you can choose if the panel button should open a panel design or trigger an event directly without opening a panel. This is done by deleting the linked design of the panel and giving the panel a unique ID in the editor. The panel button will then only trigger an event in the xAPI when pressed.

A selection of colors is available in the In-Room Control editor that can be applied to the panel buttons. Because you can create up to 20 panel buttons, setting different colors on the buttons makes them easier to recognize. Choose the colors carefully to avoid confusing users as the same colors are used for other features as well. When you hover the mouse pointer on a color in the In-Room Control editor you will see what theme that color is used for.

Support for ISDN Link

ISDN Link version IL1.1.7 is supported for all room devices that supports CE9.3.0. ISDN Link has previously been supported with CE8 and requirements are the same from CE9.3.0.

In order to pair the ISDN Link, you must enable IPv6 on the room device.

One Button to Push (OBTP) Snooze

The meeting reminder will now provide the option to snooze for 5 minutes. The reminder will typically appear if you are already in a call and a scheduled meeting that is about to start. You can snooze the reminder for 5 minutes each time it appears.

SX10 Screen status monitoring (CEC)

CEC is disabled by default on the SX10 and must be enabled through the web interface. SX10 had a CEC implementation in previous releases. The CEC implementation is now in parity with the Cisco

Webex Room Series. New CEC xCommands are available. Please refer to the SX10 API guide for more information.

Adjust call rate before making a call

From CE9.3.0 you can adjust the call rate when making a call from the on-screen UI or Touch 10.

Select ringtone and adjust ringtone volume

In the settings menu, you can now select the preferred ringtone and adjust the ringtone volume separately from the system volume.

Other changes

Resume a postponed upgrade

When you get a notification that an upgrade is available and you choose to postpone the upgrade for 6 hours, you can now resume the upgrade when you are done using the system. If you do not manually resume the upgrade, the system will automatically start the upgrade after 6 hours.

Hide sensitive information in the UI

Hide sensitive information in the UI by enabling UserInterface Strong Security mode. This feature will hide system IP information, for example the IP address of the room device, Touch 10 and the Registrar (UCM/VCS). The feature will only be active if the admin password is not blank, settings menu is locked, and User Interface Strong Security mode is enabled.

Note that while this feature is active you will not see the system IP address on the screen if you disconnect the Touch 10 from the system.

You must authenticate with the admin password to see the information.

This feature is added as part of being JITC compliant but can be enabled as a separate feature without setting the system into full Strong Security Mode.

Accessibility: Flashing screen on incoming calls

This feature is mainly targeting hearing impaired users, making it easier to notice an incoming call. The screen and the Touch 10 will flash red/gray approximately once every second. The feature is disabled by default and can be enabled in the web interface of the room device. Supported by all devices that supports CE9.3.0.

Mirrored self-view on Cisco Webex DX Series

Invert the self-view on the Cisco Webex DX80 or DX70 to create a mirror effect. This feature was available on the Cisco Webex DX series on Android software and is now available from CE9.3.0. The feature is enabled by default and can be disabled from the web interface of the room device.

New features and functionality in CE9.2.6

- This is a minor release and contains only bug fixes
 - Please see the “Open and resolved caveats” section in this document

New features and functionality in CE9.2.5

- This is a minor release and only contain fix for CSCvj32935

New features and functionality in CE9.2.4

- This is minor release and contains only bug fixes
 - Please see the “Open and resolved caveats” section in this document

New features and functionality in CE9.2.3

- This is minor release and contains only bug fixes

New features and functionality in CE9.2.2

- This is minor release and contains only bug fixes

New features and functionality in CE9.2.1

- Macro framework
- HDCP Support for Cisco Webex Room 55
- Branding and Halfwake customization
- Source composition
- HTTP Proxy support
- Touch 10 and On-screen UI features
 - Admin settings lockdown in UI
 - Snap to whiteboard configuration UI
 - IEEE 802.1x configuration UI
 - Keyboard localization (Russian)
 - Right to left language support (Arabic and Hebrew)
- Support for Cisco TelePresence SX80 with Cisco Webex Quad Camera
- Certificate upload through xAPI
- Trigger custom input prompt through xAPI
- USB to serial port support for Cisco Webex Room Kit and Room Kit Plus
- Mute remote participants in CMS conference (Active Control)
- In-Room Control
 - Widgets
 - Preview mode
- Briefing room mode
- Other features or changes
 - Removal of Cisco Proximity indicators and UI toggle
 - Changing device activation will factory reset the video system

New feature and functionality descriptions

CE9.2.1

Macro Framework for customized endpoint behavior

CE9.2.1 introduces a new powerful macro development framework. This feature allows users and integrators to write small macro scripts using standard JavaScript in order to automate scenarios and customize endpoint behavior to suite individual requirements.

You can create your own custom features that triggers specific actions based on status changes or xAPI events. For example, you can automate reset of all the configurations on a video system a few minutes after the system has entered standby, leaving the room ready for the next group of people.

If you can do the actions in the xAPI you can in most scenarios automate it using the macro framework. You can create up to 10 individual macro scripts on a supported system.

The macro development editor can be found on the video system web interface and has features, such as appearance, key bindings (Emacs or Vim), syntax checks, auto-complete and a debug console. The macros run natively on the codec and can be started from the same editor.

To get started, visit the macro editor, review the help section and the embedded tutorial that contains all the information and code examples you need to start writing macros.

If you do not have the capacity or knowledge to create your own macros, a collection of downloadable pre-written macros can be found here: <https://developer.cisco.com/site/roomdevices>.

Visit Cisco TelePresence Support Forums to share ideas and to get help.

Designed to work with In-Room Controls

Combining a macro script together with the In-Room Control allow you to create user-friendly graphical user interfaces for your local custom features without connecting third-party devices. You can create your own mini-panels with associated behavior, such as speed dial, custom layout controls, language selectors, Proximity toggle, call quality surveys etc. If you require to control external room peripherals or perform other external actions a control system is still required.

For known limitations, please see the Limitations and advisories section in this document.

Supported systems (Macro framework)

All systems that support CE9.2.1 except Cisco TelePresence SX10 due to platform stability issues

Macro framework support disclaimer:

Cisco Technical Assistance Center (TAC) will only be able to assist in support cases if there are issues with the macro runtime framework or issues with the editor itself. TAC is not obligated to provide assistance with debugging macro code or code that otherwise do not give the expected experience. To get the most out of this feature, we assume you are versed in writing standard JavaScript or otherwise familiar with integration scripting and programming.

To provide support for a video system that currently have active macros, TAC may ask you to disable all macros before they will move on with the case. For help with ideas and debugging macros, please seek out the Cisco support forums for assistance from the Cisco TelePresence community.

HDCP Support for Cisco Webex Room 55

You can enable High-bandwidth Digital Copy Protection (HDCP) support for one of the input sources on the Cisco Webex Room 55. By enabling HDCP you can connect a consumer grade device for example, an AppleTV, HD TV-Decoder or a gaming console to re-purpose the integrated 4k screen when not used for conferencing calls.



Note that you can only view content from the HDCP enabled input source locally. You cannot share anything from the HDCP-configured input while in call. This includes when content from a laptop is not actually HDCP protected, nor when composing video from the HDCP input into the main video stream. This will only produce a black frame sent to the far-end.

Branding and halfwake customization

Upload your own company branded images to be placed on the on-screen UI including the Touch 10. This feature extends the flexibility of the halfwake state and allow you to customize its appearance.

Halfwake

Upload a background brand image to replace the default animated halfwake background. You can also upload your own company's logo and put your own brand on the video system.




The screenshots show an example system in halfwake with custom branded images. The left image shows how it looks like on-screen and the right image is the Touch 10.

If you have third party integrations, the text that is displayed on-screen can be customized to say for example, “Use the Crestron touch panel on the stage podium”. By changing the halfwake text it will remove the Touch 10 panel or the TRC6 remote control illustration displayed below the text as well. You cannot modify the text “Tap this screen to get started” on the Touch 10.

Awake

Upload your own branded image logo that will be placed in the lower right corner of the screen and the Touch 10 while the system is awake.



The screenshots above show an example system in awake with a branded logo in the lower right corner. You can also place a custom text line in the bottom left corner from the web interface.

All of the images can be uploaded through the video system web interface under personalization. Please follow the user-friendly instructions presented on the web interface. All the branded images you upload will be previewed and displayed in the web interface as it would be presented on the screen. From this page, you can manually trigger halfwake to see the results on the system instantly. Upload Base64 encoded branded images through the xAPI and the XMLAPI, please see the CE9.2.1 administrator guide for more information.


Supported systems (Branding)

All systems that support CE9.2.1 except Cisco TelePresence SX10 due to platform stability issues.

Source composition

This feature replaces some of the functionality that was previously provided with TC-Console for legacy products. With source composition, you can compose up to four input sources into one image (the number of input sources you can compose is also dependent on available physical input sources on the codec). This image will be sent in the main video stream to the far end in a call. Source composition can only be enabled through the xAPI, so we recommend creating an In-Room Control UI combined with a macro to control the compositions on demand.

Note that source composition does not provide the same flexibility as TC-Console did but is easier to use. The composition has two layouts: Equal and Picture in Picture (PIP). Equal layout can have up to four sources composed into the main video while PIP is limited to two sources. You can decide what source should be displayed in which frame, but you cannot modify the frame positions or size as this is decided by how many sources you are composing with and the layout you choose. See below for example main video source compositions.



Please refer to the administrator guide for more information on the xAPI operations.

Supported systems

All systems that supports CE9.2.1 except Cisco TelePresence SX10, DX80 and DX70 due to hardware limitations.

HTTP Proxy support

When you register a video system to Webex Teams, you can configure the system to go through a HTTP Proxy if required in your environment for communication over HTTP(S). The HTTP Proxy feature can be configured through the Touch 10 panel when registering to Webex Teams or through the web interface. Media will still be direct and not through the proxy.

Note that if your proxy server requires authentication the video system only support digest authentication.

HTTPS inspection is supported by uploading a valid CA certificate to the system.

Touch 10 and On-screen UI features

Some of the features that was missing when moving from CE8 to CE9 has now been re-instated for the new UI.

Admin settings lockdown in UI

Adds the possibility to lock administrative settings on the Touch 10 or in the on-screen UI. The feature is unlocked by default and can be locked through the xAPI or through the web interface. When the admin password is configured on the video system and the SettingsMenu Mode is “Locked”, you must present the admin credentials to configure a locked setting. The settings that are locked will be marked with a padlock icon on the Touch 10 or on-screen UI respectively. If the admin password is blank, the settings will be open even if the SettingsMenu Mode is “Locked”.

Search for “SettingsMenu” from the web interface on the endpoint configuration pages to configure.

Snap to whiteboard configuration re-instated

If you have a video system with SpeakerTrack, you can setup the Snap to whiteboard feature from the Touch 10. This includes the following systems that have a SpeakerTrack unit installed:

- Cisco TelePresence SX80 (with SpeakerTrack 60 or Cisco Webex Quad Camera), MX700, MX800 and MX800 Dual
- Cisco Webex Room Kit, Room Kit Plus and Room 55

Note that if the system does not have a SpeakerTrack camera you will not be able to configure this feature.

Follow the instructions on the Touch 10 to setup Snap to Whiteboard.

IEEE 802.1x configuration UI

From the Touch 10 network settings you can setup IEEE 802.1x. Note that if a certificate is required for authentication you must still upload this through the web interface or the xAPI.

Keyboard localization (Russian, Arabic and Hebrew)

Support for keyboard localization for some languages. When you select Russian, Arabic or Hebrew as the preferred language the keyboard will be localized.

Right to left language support (Arabic and Hebrew)

Selecting Arabic or Hebrew as the preferred language the user interface will be inverted (right to left) in addition to keyboard localization.

Support for Cisco TelePresence SX80 with Cisco Webex Quad Camera

Cisco Webex Quad Camera can be used together with the SX80 from CE9.2.1. By using the Cisco Webex Quad Camera, you will free up one extra HDMI input compared to the SpeakerTrack 60 and gain the People Count feature with the limitation that it will only work while you are in a call and not out of call as supported with Cisco Webex Room Kit Plus. The Cisco Webex Quad Camera will also work in Briefing Room mode together with a Precision 60 camera for PresenterTrack.

Certificate upload through xAPI

A PEM formatted certificate can be installed directly through the xAPI using a new multiline command or through the XMLAPI. Please read the CE9.2.1 admin guide for more information about xAPI commands.

Trigger custom input prompt through xAPI

Enable an on-demand custom input prompt in the UI. The prompt can only be enabled through the xAPI so it is recommended that functionality is created through the Macro framework in combination with an In-Room Control UI or auto-triggered after an event. For example, you can prompt a user to leave feedback after an ended call. The input prompt will generate an event in the xAPI when submitted. Please refer to the CE9.2.1 admin guides for more information about xAPI commands.

USB to Serial port support for Cisco Webex Room Kit, Room Kit Plus and Room 55

For third party integrations, you can connect a USB (Type A) to serial (D-sub 9) adapter to support, for example a Crestron panel. Most USB to serial should work but Cisco recommends the UC232R-10 USB to RS232 (FTDI) adapter for the most tested and stable serial connection.

Mute remote participants in a CMS hosted conference (Active Control)

When a video system is enabled for Active Control in a CMS (2.3) conference you can mute remote participants from the participant list on the Touch 10 or on-screen UI (also required to be enabled on the CMS). If the remote system is on CE9.2.1 the mute state will be reflected on the CMS and locally on the Touch 10 and microphone mute state LED.

You cannot un-mute a remote participant on CE9.2.1 that is also muted locally for privacy reasons, but when requested a message will pop up on the remote system saying that the remote participant requested you to un-mute your microphone. The remote user must manually un-mute.

You can mute third-party far end participants and participants that are running unsupported software as well, but then it will not be reflected locally, and they will be muted on the CMS side only.

Please see the CMS API documentation on how to enable this feature on the CMS by following the link below.

<https://www.cisco.com/c/en/us/support/conferencing/meeting-server/products-programming-reference-guides-list.html>

In-Room Control

New features added to In-Room Control where you can enable a custom text, pin or password input prompt from the xAPI. The In-Room Control editor now also has a virtual Touch 10 where you can try out your features from the web interface.

Widgets

The widgets with state (toggle button, slider and group button) now set their state in xStatus immediately when an action occurs, such as a user toggling the toggle button or moving the slider. Previously the GUI updated itself 'optimistically' without reflecting it in the xStatus and relying on the controller to confirm the change explicitly by setting the xStatus widget value. This change fixes some confusing GUI behavior, since if you forgot to set the state the GUI and xStatus values could easily get out of sync.

It also solves a design bug that you sometimes were not able to override the GUI state from your controller.

Note that you must still make your controller/macro update the widget values as before to reflect what happens on the controller side for example, someone turns on the light using the light switch on the wall or someone changes a configuration in the xAPI.

Because the codec will update the xStatus value before the UI event occurs it will not cause race conditions between the codec and the controller. So, if the controller decides to override a widget value, this command will always arrive after the update done by the codec earlier.

Preview mode

The In-Room Control editor has a new preview mode. A virtual Touch 10 panel will be available for you to see how the design looks like on the Touch 10 panel. The UI is interactive and lets you test the functionality as well as print out the widget values when interacted with in the console located on the same page. This will make it easier to create In-Room Control functionality remotely and test the functionality on demand. When the virtual Touch 10 is interacted with, it will also produce real events on the video system to trigger any functionality you have created with a third-party control system or with a macro. The console will also display any control system feedback messages, to be sure that the control system and In-Room Control UI is in sync. Keep in mind that some widgets, as mentioned in

the Widgets section above, now also updates the xStatus values when interacted with and will appear in the console (under “Control system”) before the actual GUI event. This is the expected behavior.

To access the preview mode, locate and click the “eye” icon in the In-Room Control editor.

Briefing Room

Briefing Room mode is not a new feature but is re-instated to be supported from CE9.2.1. Briefing room mode is now also supported with Cisco TelePresence SX80 connected to a Cisco Webex Quad Camera. All briefing room mode requirements still apply, please read the administrator guide for more information.

Note: Briefing Room layouts will be controlled by In-Room Controls that will overwrite any existing In-Room Control panels on the video system. Please make sure to back up any In-Room Control designs before enabling Breifing Room mode. These can be added to the In-Room Control setup after Briefing Room mode is enabled.

Briefing Room Mode is only supported on Cisco TelePresence SX80, MX700 and MX800 Dual with three screens, SpeakerTrack 60 or Quad Camera (SX80) and an additional Precision 60 camera for PresenterTrack.

Note: Content Share to Clients, which is an Intelligent Proximity service, will be disabled to avoid high load scenarios that may affect other use cases when Briefing Room mode is enabled.

Other features or changes

Removed Intelligent Proximity indicators and UI toggle

The video system will no longer display the Proximity icon in the top left corner of the screen when enabled. The button for toggling the Proximity services on and off is also removed.

Proximity will still be configurable from the xAPI and the web interface. When a client is paired to the video system you will see the Proximity icon right part of the screen to indicate that one or more clients are paired to the system with Cisco Proximity.

Tip: If Cisco Proximity controls are required, it can be solved for example, with In-Room Controls together with the new Macro framework as with many other scenarios. A collection of downloadable pre-written macros for scenarios like this will soon be available.

Changing the device activation from the UI will reset some of the system configurations

A behavioral change in CE9.2.1 is that the system will now erase all the call service settings and reboot to ensure that all settings are correct before changing the device activation method for

example, from VCS to UCM activation. This will avoid conflicting configurations when you are provisioning your video system to a new service.

Please note that this will also erase all contacts and call history. Make sure you take a backup of these before changing the device activation.

New features and functionality in CE9.1.6

- This is a minor release and only contain fix for CSCvj32935
- Android to CE9.1.6 conversion software released for DX70 and DX80

New features and functionality in CE9.1.5

- Minor release and contains bug fixes
- Fixes WPA2 related vulnerabilities (KRACK) – CSCvf71761
- Android to CE9.1.5 conversion software released for DX70 and DX80

New features and functionality in CE9.1.4

- Minor release and contains bug fixes
- Support for Cisco Webex Room Kit Plus + Precision 60
- Android to CE9.1.4 conversion software released for DX70 and DX80

New feature and functionality descriptions

CE9.1.4

Support for Cisco Webex Room Kit Plus + Precision 60

Cisco Webex Codec Plus paired with a Cisco Webex Quad Camera is Cisco Webex Room Kit Plus.

Support for connecting Precision 60 cameras to the Cisco Webex Codec Plus is available with the release of CE9.1.4. Precision 60 cameras can be used in addition or replace the Cisco Webex Quad Camera up to a total of two cameras.

Please note that connecting multiple cameras to Cisco Webex Room Kit Plus require an external switch to be connected to the camera control port.

New features and functionality in CE9.1.3

- Minor release and contains mostly bug fixes
- Software support for Cisco Webex Room 55
- Applied a filter to increase speech intelligibility on G.729 codec.

New features and functionality in CE9.1.2

- No new features are introduced with CE9.1.2.
 - Contains a fix for bug CSCve94476

New features and functionality in CE9.1.1

- Support for Cisco Webex Room Kit Plus
 - Cisco Webex Quad Camera speaker tracking
 - Feature parity with Cisco Webex Room Kit
- Dual Screen Experience for CMS based meetings
 - Active Control
 - Supported video systems
- New wakeup experience
- Bluetooth headset support for DX70 and DX80
 - Bluetooth controls
- Wi-Fi: WPA-EAP
 - Trusted CA certificates
- Minor changes
 - Additions for Room Analytics

New feature and functionality descriptions

CE9.1.1

Support for Cisco Webex Room Kit Plus

Cisco Webex Room Kit Plus is a new room device in the Cisco Webex Room Series that can be registered to use the Webex Teams cloud service or existing on premises infrastructure. For UCM registration, please make sure you have installed the latest device pack.

For more information on the Cisco Webex Room Kit Plus hardware and technical specifications, please refer to the product data sheet here:

<http://www.cisco.com/c/en/us/products/collateral/collaboration-endpoints/spark-room-kit-series/datasheet-c78-738752.html>

Please see the “Known Limitations and advisories” section further down in this document under “Software upgrade” on how to upgrade software.

Cisco Webex Quad Camera speaker tracking

Cisco Webex Room Kit Plus comes with an external camera module with integrated loudspeakers and four 5k lenses that enhances the SpeakerTrack experience.

Look behind the scenes by enabling the SpeakerTrack diagnostics mode directly on the Touch 10 panel. In this mode, it is easy to see how the image is cropped, how many people is detected in the room currently and which lens is currently in use.

Feature parity with Cisco Webex Room Kit

As with Cisco Webex Room Kit the Cisco Webex Room Kit Plus supports the following features

- Speaker tracking
- Best overview
- Wi-Fi
- Room Analytics
- Support for upgrading firmware with COP files
- Cisco recommended screens for the best 4K experience

Dual Screen Experience for CMS based meetings

Dual screen video systems can now utilize both screens for video in a CMS based meeting for an optimal meeting experience. The video system receives two transcoded video streams and one content stream from the CMS and utilizes both screens to render the streams.

Active control

With Active Control enabled on the video system you get the best meeting experience including a participant list that shows all the participants in the meeting and their current activity status, such as mute, sharing and active speaker indication for each participant.

You can change the layouts seamlessly from the Touch 10 panel using the familiar layout selection panel (no DTMF tones required).

Supported video systems

To enable this feature, you need a CMS 2.2 or above, CUCM 11.5 / VCS X8.7 or above and a dual screen video system.

See the support matrix below:

Supported video systems	Unsupported video systems
Cisco TelePresence SX80	Cisco TelePresence MX200 G2 and MX300 G2
Cisco TelePresence MX800, MX800D and MX700	Cisco TelePresence SX10 and SX20 Quick Set
Cisco Webex Room Kit	
Cisco Webex Room Kit Plus	
Cisco Webex Room 55	
Cisco Webex Room 70	

The supported room devices must be in a two-screen setup and have the Conference MultiStream configuration set to "Auto". The default value for this setting is "Auto".

Note: When the system is in a three-screen setup, for example the Cisco TelePresence SX80, MX700 or MX800, the third screen will be reserved for content while in a dual screen call.


Please refer to the CMS deployment guides on how to enable this feature on the CMS.

New wakeup experience

The new wake-up experience in CE9.1.1 introduces a Halfwake state, which leads to a calmer wake-up of the system, and gives users better guidance on how to get started. This feature builds upon the wake up on motion detection feature introduced in CE9.0.1.

When wake-up on motion detection is enabled (not available for DX70 and SX10) the system will automatically wake to the Halfwake state when people enter the room. Also, the system will wake to this state when a user pairs a Cisco Proximity client to the system (all systems).

The video system will wake up with a greeting before going into the “Halfwake” state with simple guidance how to get started.



Depending on the system, whether it is controlled by a TRC6 remote control or a Touch 10 panel the guidance text will automatically adapt to the current configuration. If you have a Touch 10 panel connected and wake up the system by tapping the touch screen further guidance will be displayed on-screen instead of the large clock that was displayed in earlier software versions.

Note that Proximity mode must be enabled to use the WakeUpOnMotionDetection feature. No other Proximity services needs to be enabled. Please see the limitation section in this document for known limitations.

Bluetooth headset support for Cisco Webex DX70 and DX80

The video system has a built-in Bluetooth module. The user can enable Bluetooth in the settings menu from the on-screen UI to set the video system in pairing mode. Please read the instruction manual on how to set the headset in pairing mode. Select the headset from the list on the video system when it is discovered to start pairing. When the headset is showing status as “connected” you can start using it.

- Note that you can select between handset, Bluetooth headset, USB headset and speaker by pressing the icon in the top right corner next to the self-view icon on the home screen.
- You can have paired several headsets that will be stored in the pairing list, but only one can be connected at a time. If you pair and/or connect a new headset while already using a different headset, the new headset will take over as the active headset.
- The headset must support HFP (Hands Free Protocol) and A2DP in order to be supported. This can be verified in the documentation that came with the headset. Please note that there may be some detourments in the HFP and A2DP implementation for some headsets. This may cause pairing or audio playout to fail so we cannot guarantee that all headsets in the market supporting these protocols will work.
- The DX70 and DX80 currently only support narrowband audio. For wideband audio, we recommend connecting the Bluetooth dongle to video system. Then the headset will be detected as a USB headset. This will be fixed in a future software release.

Bluetooth controls

Some headsets have extra controls for volume up/down, answer/hang up call and mute. The video system supports the following depending on the headset implementation of these controls:

- Volume up, Volume down, Answer call, Disconnect call, Mute

Please see the limitation section in this document for known limitations.

Wi-Fi: WPA-EAP

This applies to video systems that currently have Wi-Fi support, Cisco Webex DX70, Cisco Webex DX80, Cisco Webex Room Kit, Cisco Webex Room Kit Plus, Cisco Webex Room 55.

Added support for the WPA-EAP framework with the below methods.

Supported WPA-EAP methods	Supported inner methods
PEAP	EAP-MSCHAPv2
EAP-TLS	EAP-GTC
EAP-TTLS	
EAP-FAST	

Trusted CA certificates

A trusted CA certificate may be required for connecting to a WPA-EAP enabled Wi-Fi network. Use of CA certificate for validation is highly recommended to avoid man in the middle scenarios. The CA certificate can be uploaded through the web interface of the video system. Note that in order to upload the certificate the system must be connected to either a wired network or a WPA-PSK Wi-Fi network before connecting to the WPA-EAP enabled network that requires a trusted certificate. There is currently no support for mass distribution of CA certificates to the video systems, but this may become available in a future software version.

You can configure the video system to require a CA certificate in order to connect to a WPA-EAP enabled Wi-Fi network. If there is no CA certificate installed on the video system when selecting Wi-Fi configuration in the GUI, a warning will be displayed. This setting is turned off by default.

Minor changes

Additions for Room Analytics

Two additional features are available for the Room Analytics feature in CE9.1.1.

Detect people presence in the room

The video system has the capability to find whether people are present in the room. It takes a minimum of two minutes to detect whether people are present or not in the room, and for the status to change. This feature is based on ultrasound. It will not keep record of who was in the room, only whether the room is in use or not.

The feature is supported for all systems supporting ultrasound except for the Cisco TelePresence SX10 QuickSet and Cisco TelePresence DX70 for the same reasons it does not support wake up on motion detection. The feature can be enabled through the web interface of the video system.

People count

People count was introduced in CE9.0.1 for the new Cisco Webex Room Series and could only count

the people present in the room while the video system was in a call or when it displayed the self-view picture. In CE9.1.1, this feature can be enabled to count the number of people present in the room when the system is outside of a call, as long as the system is not in standby. It will not keep record of who was in the room, only the number of faces that were detected.

Configuration to disable the secondary network port on Cisco Webex DX70 and DX80

You can disable the secondary network port on the Cisco Webex DX70 and Cisco Webex DX80 with the following configuration: xConfiguration NetworkPort 2 Mode: <On, Off>.

New features and functionality in CE9.0.1

- Support for Cisco Webex Room Kit
 - Speaker tracking
 - Best overview
 - Wi-Fi support
 - Room Analytics
 - Support for upgrading firmware with COP files
- Updated user interface “Activity Circles”
 - Touch 10 updates
 - New phonebook and share tray UI
 - Keyboard improvements on Touch 10 and Cisco Webex DX70/DX80
 - Call forward on Touch 10
- Wakeup on motion detection
- Updated In-Room Control Editor
- Minor changes
 - Support for HTTPS client certificates
 - New Briefing Room controls
 - Local Contacts is renamed to Favorites in the web interface
 - Added language: Portuguese

New feature and functionality descriptions

CE9.0.1

Support for Cisco Webex Room Kit

Cisco Webex Room Kit (Room Kit) is a new room system in the Cisco Webex Room Series that can be registered to use the Webex Teams cloud service or existing on-premises infrastructure. For UCM registration, please make sure you have installed the latest device pack.

For more information on the Room Kit hardware and technical specifications, please refer to the product data sheet here:

<http://www.cisco.com/c/en/us/products/collateral/collaboration-endpoints/spark-room-kit-series/datasheet-c78-738729.html>

Speaker tracking

SpeakerTrack is a feature that has been around for a while and has only been available on SX80, MX700, MX800 and MX800 Dual.

Cisco Webex Room Kit comes with a non-movable integrated camera that has digital speaker tracking functionality to locate and frame the active speaker in the room using the integrated microphones.

Best overview

Cisco Webex Room Kit uses digital face detection to automatically create the best view of a single person or a group of people in the conference room. If people are moving around in the room or additional participants enters the conference room, the feature will adopt to the changes and automatically adjust the view to include all persons in the picture. This feature works together with speaker tracking to provide the best possible conferencing experience.

Wi-Fi support

Cisco Webex Room Kit has support for Wi-Fi connectivity. Touch 10 must be directly paired to the Cisco Webex Room Kit in order to configure Wi-Fi.

Supported IEEE standards	Supported security protocols
IEEE802.11ac, IEEE802.11n, IEEE802.11a, IEEE802.11g, IEEE802.11b	WPA-PSK (AES), WPA2-PSK (AES)

Support for additional enterprise security protocols will come in a later Collaboration Endpoint Software release. Please refer to the product data sheet for more detailed information.

Access the network settings through the Touch 10 panel and connect to a wireless network. To use the Wi-Fi, you must disconnect the Ethernet cable if connected. A notification will be displayed if the system detects that you are connected with an Ethernet cable and that you cannot proceed until you have disconnected the Ethernet cable.

Ethernet will always take precedence over Wi-Fi if connected.

If you are connecting to an unsupported network, a notification will be displayed on the Touch 10 panel that the system does not support the specific network.

Room Analytics

Room Analytics is a feature that uses the face detection to count the average number of people present in the conference room during a video call. The data can be used to generate room usage reports. The room system will collect data that can be retrieved through the system API or from the Call History, manually or automatically by third party integrations.

Support for upgrading firmware with COP files

Cisco Webex Room Series can be upgraded directly using COP files through the web interface. This is the only package format released for the Cisco Webex Room Series.

Updated user interface “Activity Circles”

Activity Circles is the name of the new UI released with CE9.0.0 to align the user interface across the collaboration portfolio, including Room OS UI and other Webex Teams platforms for example, the Cisco Webex Board.

The UI updates includes a change of default background image, new icons, and visual design.

Touch 10 updates

Cisco Touch 10 has a new user interface that is identical to the Touch 10 UI for Webex Teams registered endpoints and similar to the on-screen user interface of a Cisco Webex DX70 or Cisco Webex DX80 that is running Collaboration Endpoint Software 9.

Compared to the UI in CE8 the Touch 10 panel is currently missing some features that may be added in a later release. Please see below for a list of features that is currently missing from the Touch 10 panel with the new UI.

Feature gaps

Features	CE8	CE9
Subset of settings has password protection (Factory reset, network, un-pairing of Touch 10, provisioning)	Yes	From CE9.2.1
Localized keyboard	Yes	From CE9.2.1 (Russian, Hebrew, Arabic)
Adjust call rate in phonebook	Yes	From CE9.3.0
Snap to whiteboard configuration	Yes	From CE9.2.1 (Requires a SpeakerTrack enabled system)
Arabic and Hebrew (Inverted UI and text direction)	Yes	From CE9.2.1
Manual clock adjustments, duplex settings, network DNS domain, auto answer, default call rate, camera white balance, exposure and backlight compensation, DVI output mode, main source selection, speaker track adjustments (tracking mode), multipoint mode configuration, change ringtone* and key tones on/off.	Yes	Can be configured through the codec web interface * Available in the latest software

New phonebook and share tray UI

As part of the new UI update, the phonebook and share tray have been updated. The phonebook and share tray are rendered in full screen and has a refreshed look.

Keyboard improvements on Touch 10 and Cisco Webex DX70/DX80

The Touch 10 keyboard has been updated to be larger and include a dial pad button. An additional page of special characters has also been added.

Call forward on Touch 10

Call forward can be configured on Touch 10 and display a notification that all calls are being forwarded while active. UCM is required to utilize this feature.

Wakeup on motion detection

Wakeup on motion detection is a feature that will sense when a person walks into the conference room using audio technology. The system will wake up automatically. This feature is turned off by default, and when enabled you will not be able to manually place the system in standby.

Improved In-Room Control editor

The In-Room Control editor is updated with a new look, improved logic, and usability for producing a control interface more efficiently. In addition, a new directional pad widget is added.

An In-Room Control simulator is also added to demonstrate some of the functionality you can gain with the power of In-Room Controls together with third party equipment. The virtual simulation room has a number of common peripherals that you can control using the virtual Touch 10 panel or export directly to your physical Touch 10 and control the virtual room using this. This feature is only for demonstrational and inspirational purposes.

The simulator is available in the codec web interface under Integrations → In-Room Control.

Minor changes

Support for HTTPS Client certificates

By enabling HTTPS client certificate verification, the system will ask the user for a client certificate when they attempt to access the login page of the codec. CA certificate is required and must be uploaded to the codec.

The client certificate is used automatically to verify the LDAP user when LDAP authentication is utilized. A user DN can be manually configured on a local user to match a client certificate.

New Briefing Room controls

With the new UI, Briefing Room mode now enables In-Room Control panels for controlling the Briefing Room layouts. Please note that Briefing Room must be enabled after you have upgraded to CE9. If you have upgraded with Briefing Room enabled, you must disable and re-enable the feature to enable the controls. See the known limitation section for more information.

Local Contacts is now renamed to Favorites in the web interface

To align the naming convention on the Touch 10 and the web interface for contacts stored locally, Local Contacts has been renamed to Favorites in the web interface. Functionality has not changed.

Added language: Portuguese

To align the naming convention on the Touch 10 and the web interface for contacts stored locally, Local Contacts has been renamed to Favorites in the web interface. Functionality has not changed.

Open and resolved caveats in CE9

Using the Bug Search Tool

You can use the Bug Search Tool to find information about caveats (bugs) for this release, including a description of the problems and available workarounds. The Bug Search Tool lists both open and resolved caveats. **No subset of open or resolved bugs will be listed in the release notes.** A pre-defined link will provide the correct list of all open or resolved bugs. Please note that the "Series/Model" listed in the pre-defined search is universal and will list all relevant bugs relating to all products that runs Collaboration Endpoint Software.

To use the Bug Search Tool, follow these steps:

Step 1 Access the Bug Search Tool by navigating to <https://bst.cloudapps.cisco.com/bugsearch/>

Step 2 Log in with your Cisco.com user ID and password.

Step 3 To look for information about a specific problem, enter the bug ID number in the 'Search for bug ID' field, then click 'Go'.

Use the below links to access the open and resolved caveats lists for a specific software release.

Software version	Resolved caveats	Open caveats
CE9.15.13.0	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&kw=*&rls=9.15.13.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&sb=af&kw=*&bt=custV&rls=9.15.13.0&svr=3nH&sts=open&srtBy=recMdf
CE9.15.3.26	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&kw=*&rls=9.15.3.26&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&sb=af&kw=*&bt=custV&rls=9.15.3.26&svr=3nH&sts=open&srtBy=recMdf
CE9.15.10.8	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&kw=*&rls=9.15.10.8&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&sb=af&kw=*&bt=custV&rls=9.15.10.8&svr=3nH&sts=open&srtBy=recMdf
CE9.15.8.12	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&kw=*&rls=9.15.8.12&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&sb=af&kw=*&bt=custV&rls=9.15.8.12&svr=3nH&sts=open&srtBy=recMdf
CE9.15.3.25	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&kw=*&rls=9.15.3.25&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch/arch?pf=prdNm&sb=af&kw=*&bt=cust

		V&rls=9.15.3.25&svr=3nH&sts=open&srtBy=recMdf
CE9.15.3.22	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.3.22&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&sb=af&kw=*&bt=custV&rls=9.15.3.22&svr=3nH&sts=open&srtBy=recMdf
CE9.15.3.18	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.3.18&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.3.18&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.15.3.17	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.3.17&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.3.17&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.15.0.19	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.0.19&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.0.19&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.15.0.13	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.0.13&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.0.13&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.15.0.11	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.0.11&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.15.0.11&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.14.7	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.7&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.7&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.14.6	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.6&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.6&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.14.5	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.5&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.5&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.14.4	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.4&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.14.4&bt=custV&sb=anfr&sts=open&svr=3nH

CE9.14.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.14.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.14.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.13.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.13.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.13.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.13.0	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.13.0&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.12.5	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.12.5&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.12.5&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.12.4	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.12.4&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.12.4&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.12.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.12.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.12.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.10.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.10.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.10.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.10.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.10.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.10.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.10.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.10.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=&rls=9.10.1&bt=custV&sb=anfr&sts=open&svr=3nH

CE9.10.0	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.10.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.10.0&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.9.4	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.4&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.4&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.9.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.9.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.9.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.9.0	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.9.0&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.8.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.8.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.8.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.8.0	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.8.0&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.7.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.7.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.7.2&bt=custV&sb=anfr&sts=open&svr=3nH

CE9.7.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.7.0,9.7.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.7.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.6.4	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.4&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.4&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.6.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.6.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.6.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.6.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.5.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.5.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.5.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.5.0	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.5.0&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.4.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.4.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.4.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.4.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.4.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.4.1&bt=custV&sb=anfr&sts=open&svr=3nH

CE9.4.0	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.4.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.4.0&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.3.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.3.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.3.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.3.0	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.0&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.3.0&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.2.6	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.6&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.6&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.2.5	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.5&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.5&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.2.4	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.4&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.4&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.2.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.2.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.2.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.2.1&bt=custV&sb=anfr&sts=open&svr=3nH

CE9.1.6	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.6&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.6&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.1.5	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.5&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.5&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.1.4	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.4&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.4&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.1.3	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.3&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.3&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.1.2	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.2&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.2&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.1.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.1.1&bt=custV&sb=anfr&sts=open&svr=3nH
CE9.0.1	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.0.1&bt=custV&sts=fd&sb=fr	https://bst.cloudapps.cisco.com/bugsearch?pf=prdNm&kw=*&rls=9.0.1&bt=custV&sb=anfr&sts=open&svr=3nH

Known limitations and advisories

Limitations and advisories

System Behavior During Times of Network Congestion

Anything that degrades network performance can affect Cisco TelePresence voice and video quality and, in some cases, can cause a call to drop. Sources of network degradation can include, but are not limited to, the following activities:

Administrative tasks such as an internal port scan or security scan

Attacks that occur on your network, such as a denial-of-service attack

To reduce or eliminate any adverse effects to a TelePresence conference, schedule any administrative network tasks during a time when the Cisco TelePresence system is not being used, or exclude TelePresence systems from the testing.

Equipment / Feature	Summary
Webex Teams activation	<p>To activate a system on Webex Teams with a LAN paired Touch 10 panel, you must pair the Touch 10 before you activate the system on Webex Teams.</p> <p><i>Note: In newer versions you can now create new user accounts to pair a Touch 10 after registration.</i></p> <p>We recommend that you upgrade to the latest available CE version before activating your device on Webex Teams.</p> <p>Encryption option key is required to register the device to Webex.</p>
CUCM	<p>H.323 and SIP consideration when provisioned by CUCM</p> <p>When using CUCM provisioning, the endpoint cannot register to a VCS (SIP or H.323) at the same time. This use-case is not supported. When CUCM provisioning is active, H.323 mode is disabled. We recommend TelePresence customers to migrate from H.323 to SIP.</p> <p>Please note that being registered to CUCM without having provisioning mode set to "CUCM" is not a supported scenario.</p>
NTP	<p>The collaboration endpoints do not support broadcast NTP servers from CUCM, unicast only.</p>

Mobile Remote Access	<p>Clustered CUCM failover does not work as expected with VCS X8.10 CE software and MRA</p> <p>Failover between clustered CUCM nodes does not work as expected on all current CE versions including CE9.1.2 and below. This is fixed in CE9.1.3.</p> <p>Provisioning a backup bundle is currently not supported over MRA</p>
Cisco TelePresence DX70 and DX80	<p>Scheduled meetings in TMS</p> <p>From CE9.1 and above the value space for bandwidth was changed from 6000 to 3072, which causes the DX system call to fail as TMS (<=15.6) uses 6000Kbps as a default hardcoded value. It can be worked around by changing the bandwidth in the meeting from TMS or have the bridge dial the systems instead of the DX systems dialing in.</p> <p>DX do not support whiteboarding when registered on-premises (The DX do not have the hardware to do the transcoding)</p>
Cisco TelePresence SX10 Quick Set	<p>Feature limitations</p> <p>Due to platform stability issues, some features may not be supported with SX10. In CE9.2.1 the Branding and Macro framework feature is currently not supported but may be added in the future.</p> <p>UI Extensions require a touch controller and will not function with a TRC6 remote control with the device.</p>
Cisco TelePresence SX20 Quick Set	<p>Microphone mute button</p> <p>It is a known issue that the SX20 Quick Set with PID CTS-SX20CODEC microphone mute button is still lit (red or green) when the system is not in a call. This is resolved in newer hardware revisions of the SX20 Quick Set with PID CTS-SX20N-CODEC running CE9. The PID number is located on the bottom side of the codec.</p> <p>UI Extensions require a touch controller and will not function with a TRC6 remote control with the device.</p>
Cisco Telepresence MX300 G2 / PrecisionHD 1080p 4x S2	<p>Camera is making noise</p> <p>After fixing a camera focus issue, the camera will do a recalibration whenever it is going into standby. This calibration may sometimes produce noise from the camera motor. This noise does not indicate a hardware issue, and the noise level characteristics may differ from camera to camera. The calibration process can also produce camera error messages in the logs. If you are experiencing these issues in other scenarios (other than when the system is entering/leaving standby), please reach out to TAC for further troubleshooting.</p>

Cisco TelePresence SX80, MX700, MX800, MX800D	<p>Bandwidth limitation</p> <p>The maximum available bandwidth for these systems is limited to 6000 kbps (previously 10000 kbps) due to a limitation related to high load on the endpoints. A fix for this is planned for a future release.</p>
SIP	<p>SIP Listen Port diagnostics warning</p> <p>When registered to a SIP proxy and SIP Listen Port is enabled, a diagnostics warning will be displayed in the web interface “SIPListenPortAndRegistration”. We recommend that SIP Listen Port is turned off when registered to a SIP proxy</p>
H.265	<p>H.265 will only work with SIP</p> <p>The H.265 protocol will only work with SIP and is currently only supported with SX80/MX700/MX800/MX800D and Cisco Webex Room Series (p2p).</p>
Multistream with Cisco TelePresence Server	<p>This feature is deprecated and no longer supported with CE9.0.0 and above.</p>
Cisco Intelligent Proximity	<p>Please refer to the Cisco Support Forums for questions and support</p> <p>http://www.cisco.com/web/go/proximity-support</p> <p>Troubleshooting guide</p> <p>https://supportforums.cisco.com/document/12159326/troubleshooting-guide-cisco-proximity</p> <p>Strong Security mode (JITC)</p> <p>If strong security mode is enabled, Proximity traffic will intentionally be blocked by the Collaboration Endpoint. Proximity should be turned off while the system has Strong Security mode enabled.</p> <p>Sharing through Proximity in a meeting and sending resolution of 1440x900 can potentially crash the codec. This issue will be resolved in CE9.1.3. The workaround is to set a different resolution on your PC or MAC.</p> <p>Content Share to Clients are disabled when SX80/MX700/MX800 are in Briefing Room mode due to high load issues.</p>
Cisco Webex Room Navigator	<p>Cisco Room Navigator must be connected with a supported device running a supported software version (see hardware revision section) in order to successfully pair.</p> <p>In some cases, for example, in case of replacement the codec may not have the software for the Room Navigator installed. The solution is to install the codec firmware again using the downloadable .cop file from Cisco.com. For bulk deployment, CUCM will also</p>

	<p>provide software for the Room Navigator if the .cop file has been installed correctly on CUCM.</p>
<p>Touch 10</p>	<p>Bug ID: CSCum67440</p> <p>An area may appear dead on the Touch 10 controller's screen if this area has been touched during start-up of the panel. In the start-up phase, a touch calibration process takes place. If something is in contact with the touch panel at this time, this area may lose its function until the Touch 10 has been restarted. Do not touch the touch panel during boot to avoid this.</p> <p>After upgrading from TC to CE the Touch 10 may need to be rebooted</p> <p>A limitation with the software may cause a remotely paired Touch 10 to hang after an upgrade from TC to CE. In order to resolve this issue, unplug the Touch 10 and re-plug it so the Touch 10 will reboot.</p> <p>Facility service</p> <p>Facility service is only supported with Touch 10.</p>
<p>Web Engine</p>	<p>Bug ID: CSCvv64571</p> <p>If downgrading from CE9.13.x to CE9.9.3, CE9.10.1 or lower you may experience that sessions / cookies are not being saved. A symptom can be that you have to keep logging into the web areas that you recently logged into in the same session.</p> <p>The workaround is to factory reset the device or upgrade to a fixed version.</p> <p>CE9.9.4 or higher</p> <p>CE9.10.2 or higher</p> <p>CE9.12.3 or higher</p>
<p>Web interface</p>	<p>Bug ID: CSCul35568</p> <p>Due to lack of cipher suite support in IE8 running on Windows XP, HTTPS access is not possible due to Cisco security requirements. Chrome, Firefox, and Opera browsers work fine. These browsers have the necessary cipher suite support. IE8 works fine with Windows Vista, Windows 7 and Windows 8.</p> <p>Support for TLS 1.0 has been deprecated</p> <p>Please use a browser that supports TLS 1.1 and above.</p> <p>HTTP Mode changed from HTTP+HTTPS to HTTPS from CE9.4.0</p> <p>Please see the "important notes and warnings for this software version" section for more information on how this change may impact you.</p>

	<p>IE11 has issues rendering the web interface on CE9.7.1 (fixed in CE9.7.2)</p> <p>Please note that the Audio Console may experience issues with IE11 and in future software releases, also the Macro Editor due to updates not handled correctly by the browser. Please use a different browser.</p> <p>Uploading cop files via the web interface throws a warning saying that the file size is too large.</p> <p>This is an issue with the newest cop files that are larger than 1 GB. The web interface had an upload limit of 1 GB. This issue is resolved in CE9.8.2, CE9.9.1 and above. If you have this issue, upgrade using the step upgrade software before you upgrade to a later version. This issue only affects the Cisco Webex Room Series devices when upgrading via the web interface with cop files. Upgrading via UCM or other methods are not affected by this.</p> <p>HTTP Rate limiting</p> <p>To increase endpoint stability and security we have introduced changes on how the HTTP server handles requests, rate-limiting being one of them from CE9.8.3 and above.</p> <p>Max processed requests per second:</p> <p>Authenticated: 1 (queue 30)</p> <p>Using session cookies (normal): 15 (queue 90)</p> <p>To explain what these numbers mean, let's take for example the "authenticated" method:</p> <p>If you send 30 authenticated HTTP requests at once, it will take minimum 30 seconds before you get a response to the last request. If you send 31 requests, assuming all is coming in at the same time, the 31st request will get a http 503 response.</p> <p>If you hit the rate-limiting (max requests per second), the request is queued until others are processed. This happens until the queue is full, and then new requests will get http 503 instead of being queued. In newer software (CE9.12.x and above) the logs will show when the requests are being rate limited.</p>
<p>SNMP</p>	<p>CE9 has basic support for SNMPv2. Custom MIBs are not supported.</p> <p>Bug ID: CSCtq44757</p> <p>The Collaboration Endpoint Software is configured with the default SNMP community strings. This is needed for "plug and play" functionality. SNMP community strings should be treated as credentials, and therefore these must be changed after initial configuration.</p> <p>SNMPv1 Not supported in CE9</p>

	SNMPv1 is not supported in CE9, Cisco recommends using other versions of SNMP.
Security	<p>Bug ID: CSCtr32420</p> <p>The codecs shipped with Collaboration Endpoint Software do not meet the Cisco standard passphrase policy. Cisco recommends users to set a passphrase on the system when installed to avoid the system from being compromised.</p>
Encryption	<p>Bug ID: CSCvd33159</p> <p>The AES-256 encryption algorithm (supported for SIP from CE8.3.0) may cause some interoperability issues with endpoints that do not have support for this, for example E20. From CE8.3.3 and CE9.1.3 this algorithm can be filtered away by adding it to the codec cap set filter to work around these issues.</p>
IPv6	<p>Bug ID: CSCuo94615</p> <p>Option 242 from DHCPv6 is not supported on endpoints running Collaboration Endpoint Software.</p>
Management	<p>TLS 1.0 for HTTPS not supported by endpoints running CE8.1.0 and above.</p> <p>If the system after upgraded to CE8.1.0 or above (including CE9.x) is showing no HTTPS response in TMS, please make sure that TLS1.1 or TLS1.2 is enabled on the TMS server.</p>
Camera Presets	<p>Bug ID: CSCux71105</p> <p>When upgrading from TC software to CE software all camera presets are lost. This is a hard limitation and will not be resolved in software.</p>
PresenterTrack	<p>PresenterTrack is disabled in MultiSite calls</p> <p>The PresenterTrack feature is not available in MultiSite calls.</p> <p>Note that PresenterTrack will work in a Dual Screen call with CMS from CE9.</p> <p>Trigger zone configuration</p> <p>There is a known limitation when configuring the trigger zone through the web interface; whenever the blue squared is moved around and placed the trigger zone will be saved (regardless if the "save" button is pressed or not. The blue square that is displaying in the selfview on the endpoint do not disappear until the configuration has been saved manually from web or activated the PresenterTrack preset from the Touch 10.</p>

<p>SpeakerTrack</p>	<p>Face masks</p> <p>SpeakerTrack 60 (and SX80 with Quad Camera) will have difficulties detecting faces on people that is wearing a face mask, especially in poor light conditions.</p> <p>SpeakerTrack (Quad Camera and integrated cameras, for example on Room Kits) with the Cisco Webex Room Series has been improved with an additional “head detector” that will detect the head instead of the face. Note that this may also increase the frequency of detecting objects with a “head” in the room. This functionality will give an improved experience in a meeting where the people in the room are wearing face masks.</p>
<p>Briefing Room</p>	<p>Briefing Room does not work properly in CE9.0.x and CE9.1.x</p> <p>There are multiple issues with Briefing Room in the mentioned software to the point where the feature does not work as expected. Cisco recommends everyone that is using Briefing Room on these software versions to turn it off or downgrade to the latest CE8.3.x version available. This is resolved in CE9.2.1.</p> <p>Bug ID: CSCvd83107</p> <p>If you have upgraded from CE8.x or lower to CE9.x with briefing room mode enabled before performing the upgrade, you are required to disable and re-enable briefing room mode for the controls to appear.</p> <p>Also, make sure you have a backup of your existing In-Room Control configurations if any as this operation will overwrite any existing panels you may have on the home screen or in-call. Briefing Room is utilizing In-Room Controls to control the layouts. Any new In-Room Controls must be supplemented to the existing briefing room control panel.</p> <p>Downgrading back to CE8 while In-Room Control is enabled on CE9 will still display the controls activated in CE9, but they will not have any functionality and can safely be removed using the in-room control editor.</p> <p>From CE9.2.1 echo cancelling is changed to mono on MX700 and MX800 in Briefing Room mode.</p>
<p>Startup Wizard</p>	<p>While the Startup Wizard is active the system will have “Do Not Disturb” mode enabled by design. The DND mode cannot be turned off while the Startup Wizard is active. To remove the Startup Wizard, finish the Startup Wizard normally by following the steps or turn off the “RunStartupWizard” by setting the value to “False”. If the Startup Wizard is active, a diagnostics message will be active in the web interface with a link to the configuration to turn it off. This should only be done by advanced users that wants to configure the system manually.</p>

<p>Presentation</p>	<p>Bug ID: CSCuh68226</p> <p>No video is displayed to share as content from a MacBook Air when using a MiniDisplay Port to VGA dongle, where a MacBook Pro has no issues displaying video as content. This is considered to be an Apple problem.</p>
<p>Custom Wallpaper Custom Branding</p>	<p>Bug ID: CSCvb67596</p> <p>A system using custom wallpaper will not display on-screen elements for example, custom branding, the clock, today's bookings or One Button to Push. This limitation is intentional as we do not know how these elements will appear on customized wallpapers. On-screen operated systems like Cisco TelePresence SX10, SX20, DX70 and DX80 are more affected by this limitation due to the lack of OBTP join mechanism compared to systems operated by a Touch 10.</p> <p>A workaround was introduced in an earlier release to make a meeting reminder appear on-screen when the meeting starts (early reminders are not supported) to allow on-screen operated systems with custom wallpaper to join the meeting using OBTP. Note: If the reminder is dismissed the meeting must be joined manually.</p>
<p>New wakeup experience WakeUpOnMotionDetection</p>	<p>Proximity mode must be enabled</p> <p>Currently, Proximity mode must be set to enabled for WakeUpOnMotionDetection to work. The endpoint does not emit ultrasound if Proximity is turned off. No Proximity services is required to be enabled, only Proximity mode.</p> <p><i>This limitation is resolved in CE9.6.1 and Proximity Mode "On" is no longer required.</i></p> <p>WakeUpOnMotionDetection is not supported for Cisco TelePresence SX10 QuickSet or Cisco Webex DX70</p> <p>Due to hardware limitations, the SX10 and DX70 do not support the WakeUpOnMotionDetection feature. The configuration is still available and can be turned on but may not work as expected. The feature may be supported in the future for these systems.</p> <p>DX80</p> <p>WakeUpOnMotionDetection is supported but turned off by default.</p>
<p>Bluetooth on DX</p>	<p>Some features, for example a smart sensor that activates the headset when worn, may not work well together with the video system. Try turning those features off when used together with the Cisco Webex DX70 and DX80</p>

HTTP Proxy	<p>Auto configuration</p> <p>In some cases, the auto configuration will not let you register to Webex Teams immediately. Please wait a few minutes until the software has been updated and it should register. If you are still experiencing issues, please try to use manual proxy configuration. A fix for this issue will come in a future release.</p>
Macro framework	<p>The Macro Framework runs the code locally on the codec and is currently isolated to the xAPI. You cannot receive remote network connections using the macro framework but from CE9.6.1 you can send outgoing HTTP POST or PUT using a macro.</p> <p>You can create up to 10 individual macro scripts on a supported video system.</p> <p>For support, please visit the Cisco TelePresence Support forums.</p> <p>For learning please visit: https://developer.cisco.com/site/roomdevices</p>
HttpClient	<p>Reading incoming response payloads or headers is not supported</p> <p>The HttpClient feature will return the status code or an error description after a request has been made but it will not be able to read the response payload of the request.</p> <p><i>Resolved in CE9.8 and above</i></p> <p>Sending HTTPS requests requires a CA certificate</p> <p>By default, the codec will attempt to verify the server certificate. If there is no CA that can verify the certificate of the remote host, the request will fail. Upload a valid CA certificate (recommended) or configure the device to allow insecure HTTPS requests (not recommended).</p>

<p>Wi-Fi</p>	<p>WPA-EAP</p> <p>There is currently no diagnostic message for expired certificates</p> <p>CA Certificates</p> <p>CA certificates must be uploaded per endpoint. There is currently no way to mass-distribute certificates to endpoints running software version < CE9.2.1. Please also note that the endpoint must be connected to a wired or WPA2-PSK wireless network in order to upload a certificate before attempting to connect to a WPA-EAP enabled network that requires a CA certificate.</p> <p>Network paired Touch 10 not supported when the video system is connected through Wi-Fi</p> <p>Even though this connectivity works, you may end up in cumbersome scenarios if the Wi-Fi connectivity is lost for any reason, for example when the Wi-Fi password is changed. In order to reconfigure the Wi-Fi connection, you need to setup a direct pairing between the video system and the Touch 10 before reconnecting the Touch 10. When the video system is using Wi-Fi connectivity Cisco recommends that you have the Touch 10 directly paired with the video system.</p>
<p>Cisco Webex Quad Camera</p>	<p>Cisco Webex Room Kit Plus camera upgrade issue</p> <p>A weakness was discovered with the Cisco Webex Room Kit Plus. When a factory reset is performed on the Cisco Webex Codec Plus it erases a link to the camera software leaving the codec unable to upgrade the Cisco Webex Quad Camera if the software is not already in sync. The workaround was to re-install CE9.1.1 but this release is now deferred. The issue is resolved in CE9.1.2 and above.</p> <p>SpeakerTrack not working when used with SX80 on CE9.12.3 CSCvt92597</p> <p>Due to a bug in CE9.12.3 SpeakerTrack functionality will stop working when using the Quad Camera together with SX80. The solution is to downgrade the software or upgrade to CE9.12.4 when available.</p>
<p>ISDN Link</p>	<p>ISDN Link requires IPv6 to be enabled on the codec and CE9.3.0 or above</p>
<p>Cisco Webex Room Series</p>	<p>H263 content channel support (CE9.4.0)</p> <ul style="list-style-type: none"> - H263 in the main video channel is not supported

<p>Software upgrade</p>	<p>Upgrading software</p> <p>Upgrading software using CUCM</p> <p>Please remember to <u>not</u> use an extension when upgrading Cisco Webex Room Series or newer devices via CUCM. When specifying a phone load or default load, make sure you do not specify “.pkg” or other extensions. For example:</p> <p>Platform Specific packages:</p> <p>s53200ce9_15_0_13-82cc7e2121d.pkg (wrong)</p> <p>s53200ce9_15_0_13-82cc7e2121d (correct)</p> <p>Super Cop (containing all software versions for all products):</p> <p>ce9_15_0_13-82cc7e2121d (correct)</p>
<p>Audio Console</p>	<p>You need to create equalizers through the xAPI as you are only able to select between equalizers in the Audio Console UI and not create them.</p> <p>When adding HDMI input connectors that have set “Mute on inactive video”, it will look like it has not been added the first time and needs to be added a second time.</p> <p>The settings will update live when configuring the Audio Console but will not be stored in a macro until it is saved. If you do not save the Audio Console setup it will get lost if you reboot the device.</p>
<p>HDCP</p>	<p>Device is not entering standby</p> <p>If you connect a Google Chromecast for example, the device will not be able to enter standby because the standby activity makes the Chromecast send “Active” signal to the codec forcing it to wake up again.</p> <p>All content is considered as HDCP when enabled</p> <p>When the input has been configured to support HDCP, it will consider anything connected to this input as HDCP content, even if it’s not. This will prevent you from sharing content from this port in a call. You can share anything locally the same way as before but note that on a dual screen device you may only see content on one screen. Check if your room device has support for one or two HDCP outputs.</p>
<p>Add participant to CMS conference</p>	<p>Only works for SIP and not H323</p> <p>Requires CMS 2.4</p>

<p>TRC6 Remote control</p>	<p>CSCvm79929</p> <p>Since CE9.3.0 it has not been possible to type in characters using the TRC6 remote control. Please use the on-screen keyboard for character input.</p>
<p>Touch re-direct</p>	<p>You may only use Touch forwarding when you are not in a call</p> <p>It is a known limitation that you cannot start annotation or stop the presentation when you are in Touch re-direct mode. This is because the touch overlay covers the whole screen. Unplug the USB-C and HDMI cable to stop the presentation.</p> <p>If the Webex Board has a touch 10 controller connected you will not be able to move the self-view image while the USB-C cable is connected.</p> <p>If you accept an incoming call while using touch re-direct the connection will be automatically turned off. To re-establish touch re-direct after the call has ended you must re-connect the cables.</p> <p>Only laptops running Windows 10 or higher is supported with the touch re-direct feature. Note that it may work in some scenarios or if you use certain touch drivers with other OS as well, but TAC will not provide support for issues on other OS than Windows 10.</p>
<p>Webex Meetings</p>	<p>Active control of Webex Meetings</p> <p>On-premises devices that are calling into Webex meetings will currently not have the same control options of the meeting that a Webex registered / linked device have. There are still some of the actions that are available through DTMF tones. Please visit https://help.webex.com/en-us/nli1uz4/DTMF-Commands-for-Video-Device-Enabled-Cisco-Webex-Meetings for a list of valid DTMF tones that can be sent to the Webex meeting to invoke certain actions.</p>
<p>Webex Edge for Devices</p>	<p>If you downgrade a device that is currently linked with Webex Edge for Device to an unsupported version, for example CE9.9.x the device will think that it is registered to the cloud and lock down certain features. The solution is to reset the device to factory defaults before downgrading the device to an unsupported version.</p> <p>Note: New customers after May 2020 requires CE9.12.3 or higher to link devices to cloud.</p> <p>Encryption key is required to link a device to Webex Edge for Devices.</p> <p>Known Issue: CSCvw51659 TMS managed systems enabled for Hybrid Calendar could see TMS overwrite bookings. This is resolved in CE9.15.0.11 and later.</p>

Extended logging	Extended logging is a troubleshooting feature and will consume a high amount of resources when used. Enabling extended logging can generate unexpected behavior in production calls and in rare cases, cause the device to crash due to resource consumption. This feature should therefore only be enabled in short periods if higher data collection is required when reproducing issues.
------------------	---

Interoperability

The interoperability section describes the equipment and software revisions that have been tested for interoperability with this release. Please note: The absence of a device or revision from this section does not imply a lack of interoperability.

H.323 gatekeepers/traversal servers

Equipment	Software version	Comments
Cisco TelePresence System Video Communication Server (VCS)	X8.x	Both Assent and H.460.18/.19 traversal technologies are supported
Cisco Expressway	X12.x	

SIP registrars/proxies

Equipment	Software version	Comments
CUCM	9.1(2), 10.5, 11.0, 11.5, 12.0, 14.0	Using the latest device packs / versions are always recommended.
Cisco TelePresence System Video Communication Server (VCS)	X8.x	
Cisco Expressway	X12.x	

Gateway interoperability

Equipment	Software version	Comments
Cisco ISDN Link	IL1.1.7, IL1.1.8, IL1.1.9	From CE9.3.0
Cisco ISDN GW 3241	2.2	

MCU interoperability

Equipment	Software version	Comments
Cisco Meeting Server (CMS)	2.x	
Cisco TelePresence Server 7010	4.3(x.x)	
Virtual TelePresence Server	4.3(x.x)	
Cisco TelePresence Server MSE 8710	4.3(x.x)	
Cisco MCU 53xx	4.5(x.x)	
Cisco MCU 42xx	4.5(x.x)	
Cisco MCU 45xx	4.4, 4.5(x.x)	
Cisco CTMS	Not supported	CTMS is not supported with endpoints running Collaboration Endpoint Software.

Streaming servers

Equipment	Software revision	Comments
Cisco TelePresence System Content Server	TCS7.x	

Management servers

Equipment	Software revision	Comments
CTS Manager	Not supported	CTS Manager is not supported with endpoints running Collaboration Endpoint Software

TelePresence Management Suite	15.13	The latest version of TMS is recommended to support management of the latest products.
-------------------------------	-------	--

Endpoint Interoperability

General information	Known affects endpoints		Comments
H.265 Interoperability	Polycom Lifesize Vidyo		<p>We have observed some interoperability issues with H.265 endpoints (SX80, MX700, MX800, MX800D, and Cisco Webex Room Series) and third-party endpoints. The symptom is no video coming from one or both directions.</p> <p>A workaround that in some cases can rectify the issue is to turn off H.265 on the above Cisco endpoints. From the web interface in "System Configuration" search for "H265" and set the Experimental Conference 1 VideoProtocol DisableH265 to "On".</p>
Cisco	Software version	Protocol	Comments
Cisco TelePresence System 500series 3x00series 1x00series TX9000 TX9200 TX1310	1.10.7 (Ten Bears)	SIP	720p30 max resolution point to point.
Cisco TelePresence System CTS500-32 TX1300 TX9000 TX9200	TX6.0.2 (Lago)	SIP	1080p30/60 support on Lago 1G codecs
Cisco TelePresence MX G1 Series	TC6.x, TC7.x	SIP/H.323	

Cisco TelePresence EX Series	TC6.x, TC7.x	SIP/H.323	
Cisco TelePresence C Series	TC6.x, TC7.x	SIP/H.323	
Cisco IP Video Phone E20	TE4.1.x	SIP/H.323	
Sony	Software version	Protocol	Comments
Sony PCS-1		H.323/SIP	Dual stream is limited to 1 FPS. The main video frame rate will never exceed 15 FPS.
Sony PCS-XG80		H.323/SIP	SIP Far End Camera Control does not work. SIP encrypted calls do not work. SIP/H.323 transfer does not work. Sony is unable to start presentation (BFCP).
Lync	Software version	Protocol	Comments
Microsoft Lync	2013	SIP over VCS trunk from VCS x8	Requires VCS X8 released September 2013.
Polycom	Software version	Protocol	Comments
Polycom VSX 7000		H.323/SIP	At a low video rate and with main video set to sharpness the VSX will not display any video. SIP/H.323 transfer does not work. H.264 is only used on lower bandwidths.
Polycom Real Presence Group 500		H.323/SIP	FECC controls do not work for incoming calls. Unattended H.323 transfer fails on incoming/outgoing calls. No video in unattended SIP transfers from CE to CE for outgoing calls.
Polycom Real Presence Group 300		H.323/SIP	FECC controls not available for outgoing / incoming calls. Unattended H.323 transfer disconnects all calls on outgoing calls.

			No video in unattended SIP transfers from CE to CE for outgoing calls. Unattended H.323 transfer succeeds but video is lost on both ends on incoming calls.
Polycom HDX 9000		H.323/SIP	
Polycom HDX 8000 HD		H.323/SIP	No video on SIP for outgoing calls to CE endpoints.
Polycom GS500		H323	Encrypted calls to GS500 will not connect when using 2048bit encryption and FIPS from Cisco devices running CE software. Set the encryption to Max1024bit or turn off encryption for the call to work.

Cameras

Equipment	Software revision	Comments
Webex PTZ 4K	CE9.14.5 and later	Premium pan-tilt-zoom camera. Works with devices that also support a standalone Precision 60 except SX80. Example Compatible devices: Cisco Webex Codec Plus, Cisco Webex Codec Pro (including systems based on these such as Webex Room 55, Webex Room 70) Presenter Track with Room, Desk and Board devices running RoomOS 10.3.x and later.
Sony SRG-120DH Sony EVI-120DH (PTZ-12)	N/A	Supported with pan, tilt and zoom functionality. No Presenter Track. Works with devices that also support a standalone Precision 60. For example: Cisco Webex Codec Plus, Room Kit Pro and Cisco TelePresence SX80
Third party cameras	N/A	Third-party cameras may work with our codecs, but this is not tested, and functionality cannot be guaranteed. TAC support may be rejected or limited.

Cisco recommended screens for best interoperability

Cisco recommends using the following LG and Samsung Digital Signage screens together with Cisco Webex Room Series and other room devices for the best visual experience and verified CEC 2.0 compatibility.

Model	LG global website link
49" UHD (49UH5C)	http://www.lg.com/global/business/information-display/digital-signage/lg-49UH5C
55" UHD (55UH5C)	http://www.lg.com/global/business/information-display/digital-signage/lg-55UH5C
65" UHD (65UH5C)	http://www.lg.com/global/business/information-display/digital-signage/lg-65UH5C
75" UHD (75UH5C)	http://www.lg.com/global/business/information-display/digital-signage/lg-75UH5C
86" UHD (86UH5C)	http://www.lg.com/global/business/information-display/digital-signage/lg-86UH5C
98" UHD (98UH5C)	http://www.lg.com/global/business/information-display/digital-signage/lg-98LS95D

Model	Samsung global website link
QMN Series (43", 49", 55", 65", 75")	https://displaysolutions.samsung.com/digital-signage/detail/1269/QM43N
QMH Series (49", 55", 65")	https://displaysolutions.samsung.com/digital-signage/detail/1144/QM49H
QBN Series (43", 49", 55", 65", 75")	https://displaysolutions.samsung.com/digital-signage/detail/1274/QB43N
QBH Series (65", 75")	https://displaysolutions.samsung.com/digital-signage/detail/1205/QB65H

*Cisco recommends use of high quality HDMI 2.0 certified cables. Lower quality cables may work but may also have an impact on the image quality. If you experience problems and do not have access to high quality cables, try using shorter HDMI cables.

xAPI Changes

We recommend endpoint configuration through the web interface and not from the xAPI command line.

The admin user has access to only a subset of relevant commands and configuration from the xAPI. The admin user can fully manage the system from the web interface where all the configurations are available. The remotesupport user has access to the full list of xAPI commands when utilized (requires TAC engagement).

Specific xAPI changes are not published in the release notes. Please refer to the Cisco API Reference Guides for the integrator products at the following location.

DX70 and DX80: <http://www.cisco.com/c/en/us/support/collaboration-endpoints/desktop-collaboration-experience-dx600-series/products-command-reference-list.html>

MX series: <http://www.cisco.com/c/en/us/support/collaboration-endpoints/telepresence-mx-series/products-command-reference-list.html>

SX series: <http://www.cisco.com/c/en/us/support/collaboration-endpoints/telepresence-quick-set-series/products-command-reference-list.html>

Cisco Webex Room Series: <http://www.cisco.com/c/en/us/support/collaboration-endpoints/spark-room-kit-series/products-command-reference-list.html>

Cisco Webex Boards: <https://www.cisco.com/c/en/us/support/collaboration-endpoints/spark-board/products-command-reference-list.html>

Cisco TelePresence systems hardware dependencies

Introduction

Due to occasional updates to hardware components there can be constraints on running older software on newly manufactured endpoints. To identify an endpoints compatibility level, you can access the web interface of the endpoint and click on Configuration > System Status > SystemUnit. Scroll down to the compatibility level on this page. The below tables can be used to identify software constraints based on the compatibility level of your endpoint.

Downgrading to an unsupported software version will fail.

The latest software release is backward compatible with previous hardware revisions.

SX10

Compatibility level	Applicable systems	Description	Minimum software version	
			CE8	CE9
0	SX10	N/A	All	All
1	SX10	N/A	All	All
2	SX10	N/A	All	All
3	SX10	N/A	All	All

SX80, MX700, MX800 and MX800 Dual

Compatibility level	Applicable systems	Description	Minimum software version	
			CE8	CE9
0	SX80	N/A	All	All
0	MX700/MX800/MX800D	N/A	All	All

SX20, MX200 G2 and MX300 G2

Compatibility level	Applicable systems	Description	Minimum software version	
			CE8	CE9
2	SX20	N/A	All	All
3	SX20	N/A	All	All
4	SX20	N/A	All	All
5	SX20	N/A	All	All
0	MX200 G2	N/A	All	All
1	MX200 G2	N/A	All	All
2	MX200 G2	N/A	All	All
0	MX300 G2	N/A	All	All
1	MX300 G2	N/A	All	All
2	MX300 G2	N/A	All	All

DX Series

Compatibility level	Applicable systems	Description	Minimum software version	
			CE8	CE9
0	DX70	N/A	8.2.0	All
0	DX80	N/A	8.2.0	All

Cisco Webex Room Series

Compatibility level	Applicable systems	Description	Minimum software version	
			CE8	CE9
0	Cisco Webex Room Kit	N/A	N/A	All
1	Cisco Webex Room Kit	N/A	N/A	9.4.1
2	Cisco Webex Room Kit	N/A	N/A	9.4.2, 9.5.1
2	Cisco Webex Room Kit Plus	N/A	N/A	9.4.2, 9.5.1
0	Cisco Webex Room Kit Plus	N/A	N/A	9.1.1
0	Cisco Webex Room 55	N/A	N/A	9.1.3
1	Cisco Webex Room 55	N/A	N/A	9.4.1
2	Cisco Webex Room 55	N/A	N/A	9.4.2, 9.5.1
2	Cisco Webex Room 55 Dual	N/A	N/A	9.4.2, 9.5.1
0	Cisco Webex Room 55 Dual	N/A	N/A	9.4.0
0	Cisco Webex Room 70/70D	N/A	N/A	9.2.0
2	Cisco Webex Room Kit Pro	N/A		9.13.1
0	Cisco Webex Room Kit Pro	N/A	N/A	9.4.0
0	Cisco Webex Room 70/70D G2	N/A	N/A	9.4.0
0	Cisco Webex Room Kit Mini	N/A	N/A	9.6.0
0	Cisco Webex Room USB	N/A	N/A	9.12.3
0	Cisco Webex Desk Pro	N/A	N/A	9.12.3

Cisco Webex Board

Compatibility level	Applicable systems	Description	Minimum software version
			CE9
0	Cisco Webex Board 55	N/A	9.8.0
0	Cisco Webex Board 70	N/A	9.8.0
0	Cisco Webex Board 55S	N/A	9.8.0
0	Cisco Webex Board 70S	N/A	9.8.0
0	Cisco Webex Board 85S	N/A	9.8.0

Cisco Desk

Compatibility level	Applicable systems	Description	Minimum software version
			CE9
2	Cisco Webex Desk Pro	N/A	9.13.1
1	Cisco Webex Desk Pro	N/A	9.13.1
0	Cisco Webex Desk Pro	N/A	9.12.3

Peripherals hardware dependencies

New hardware revisions for Cisco TelePresence Touch 10

Systems that support Touch 10 are Cisco Webex Room Series, SX10(N), SX20(N), SX80, MX200 G2, MX300 G2, MX700, MX800 and MX800D.

The hardware revision number is displayed on the Touch controller during boot in the lower right corner on the touch screen. If you see an error on the Touch 10 screen about the software not being compatible with the current software, please upgrade the room device software to the latest available.

Hardware revision	Applicable systems	Description	Minimum software version	
			CE8	CE9
102300-3 102310-0 102310-1	All	N/A	All supported codec software versions are compatible	
101282-0	All	N/A	8.3.3	9.1.1

New hardware revisions for Cisco Webex Room Navigator

Systems that support Cisco Webex Room Navigator are Cisco Webex Room Series and Cisco Webex Board 55S, 70S, 85S.

Hardware revision	Applicable systems	Description	Minimum software version	
			CE9	
101864-0	Cisco Webex Room Series Cisco Webex Board 55S/70S/85S	N/A	CE9.14.3	
101864-1	Cisco Webex Room Series Cisco Webex Board 55S/70S/85S	N/A	CE9.14.6, CE9.15.0.13	

Note: You can only connect a touch controller to a Webex Board over the network

New hardware revisions for Quad Camera

Systems that support Quad Camera are SX80, Room Kit Plus, Room Kit Pro, Codec Plus and Room 70 / Room 70 G2.

Hardware revisions of the Quad Camera can be identified using xStatus.

Example xStatus: Peripherals ConnectedDevice XXXX HardwareInfo: "73-100746-1".

Hardware info	Applicable systems	Description	Minimum software version
			CE9
73-100746-0	All	N/A	9.1.1 and later
73-100746-1	All	N/A	9.3.3, 9.4.1, 9.5.0 and later
73-100746-3	All	N/A	9.14.7, 9.15.3.18

When older software does not support the hardware this is logged as “Offered SW does not support this HW” in the device logs.

New hardware revisions for Webex PTZ 4K

Hardware info	Applicable systems	Description	Minimum software version
			CE9
74-126086-01 A0	Codec Plus Codec Pro	N/A	9.14.5 and later

New hardware revisions for Precision 60

Systems that support Precision 60 are SX80, MX700, MX800 and MX800D, Room Kit Plus, Room Kit Pro, Codec Plus and Room 70.

New hardware revisions of the Precision 60 camera are identified by production date printed on a sticker underneath the base. If there no sticker is present and you still see an error message on screen about the camera not being compatible with the current software version, please upgrade the room device to the latest software.

Production Date	Applicable systems	Description	Minimum software version
			CE9
2018/07 and earlier	All	N/A	All supported codec software versions are compatible
2018/08 and later	All	N/A	9.3.3, 9.4.1, 9.5.x 9.6.x and later

The following table lists documents and web sites referenced in this document. All product documentation can be found on our web site.

Name	Document reference
Cisco Website	http://www.cisco.com
Cisco Software Download	http://www.cisco.com/cisco/software/navigator.html?i=!ch
Cisco TelePresence User Documentation	http://www.cisco.com/go/TelePresence/docs

Latest software filenames

The released software filenames are listed in the following table.

Cisco Collaboration Endpoint	Encryption and Non-encryption* for CUCM	Encryption and Non-encryption*	Encryption and Non-encryption* bundle** for CUCM
SX10	cmterm- s52030ce9_15_13_0.k3.cop.sgn cmterm- s52030ce9_15_13_0.k4.cop.sha 512	s52030ce9_15_13_0.pkg	cmterm- ce9_15_13_0.k3.cop.sgn cmterm- ce9_15_13_0.k4.cop.sha 512
SX20	cmterm- s52010ce9_15_13_0.k3.cop.sgn cmterm- s52010ce9_15_13_0.k4.cop.sha 512 cmterm- s52011cenc9_15_13_0.k3.cop.s gn	s52010ce9_15_13_0.pkg s52011cenc9_15_13_0.pkg	cmterm- ce9_15_13_0.k3.cop.sgn *** ce9_15_13_0.k4.cop.sha 512***
SX80, MX700, MX800, MX800 Dual	cmterm- s52020ce9_15_13_0.k3.cop.sgn	s52020ce9_15_13_0.pkg	cmterm- ce9_15_13_0.k3.cop.sgn ce9_15_13_0.k4.cop.sha 512
MX200 G2, MX300 G2	cmterm- s52010ce9_15_13_0.k3.cop.sgn cmterm- s52010ce9_15_13_0.k4.cop.sha 512	s52010ce9_15_13_0.pkg	cmterm- ce9_15_13_0.k3.cop.sgn ce9_15_13_0.k4.cop.sha 512
DX80, DX70	cmterm- s52040ce9_15_13_0.k3.cop.sgn cmterm- s52040ce9_15_13_0.k4.cop.sha 512	s52040ce9_15_13_0.pkg	cmterm- ce9_15_13_0.k3.cop.sgn ce9_15_13_0.k4.cop.sha 512
Conversion load	N/A		

Cisco Collaboration Endpoint	Encryption and Non-encryption* for CUCM	Encryption and Non-encryption*	Encryption and Non-encryption* bundle** for CUCM
Room Series Board Series Room 55/70	cmterm- s53200ce9_15_13_0.k3.cop.sgn cmterm- s53200ce9_15_13_0.k3.cop.sha 512	Step upgrade from CE9.9.0/9.8.1 s53200ce9.15.6-step- upgrade.pkg	cmterm- ce9_15_13_0.k3.cop.sgn cmterm- ce9_15_13_0.k3.cop.sha 512
Room Kit Pro Room 70 G2 Panorama Desk Series	cmterm- s53300ce9_15_13_0.k3.cop.sgn cmterm- s53300ce9_15_13_0.k3.cop.sha 512	Step upgrade from CE9.9.0/9.8.1 s53300ce9.15.6-step- upgrade.pkg	cmterm- ce9_15_13_0.k3.cop.sgn ce9_15_13_0.k3.cop.sha 512

* SX20 is the only product that requires a separate software image for non-crypto, for all other products (except Cisco Webex Room Series, DX70 and DX80), this is controlled by the encryption option key which is free of charge.

** This Cisco Options Package contains software packages for all the CE platforms in one file.


*** The cop bundle does not contain no-crypto packages for SX20

Note that for UCM 14 and above the file name used will be .k4.cop.sha512

CE9.15.3.x is the last release for Room, Board and Desk series devices. These devices will need to upgrade to RoomOS10 moving forward.

Software integrity verification

To verify the integrity of the software image you have downloaded from cisco.com you can calculate a SHA512 checksum and verify that it matches with the one listed on the software download page. To find the checksum, hover the mouse pointer over the software image you have downloaded.



At the bottom you find the SHA512 checksum, if you do not see the whole checksum you can expand it by pressing the "..." at the end.

To calculate a SHA512 checksum on your local desktop please see the table below for examples.

Operative system	SHA512 checksum calculation command examples
Microsoft Windows	Open a command line window and type the following command <pre>> certutil.exe -hashfile s52020ce9_15_0_13-82cc7e2121d.pkg SHA512</pre>
Apple MAC	Open a terminal window and type the following command <pre>\$ shasum -a 512 s52020ce9_15_0_13-82cc7e2121d.pkg</pre>
Linux	Open a terminal window and type the following command <pre>\$ sha512sum s52020ce9_15_0_13-82cc7e2121d.pkg</pre> <p>Or</p> <pre>\$ shasum -a 512 s52020ce9_15_0_13-82cc7e2121d.pkg</pre>

If the SHA512 checksum matches, there is a high level of certainty that no one has tampered with the software image or the image has not been corrupted during download.

If the SHA512 checksum does not match, we advise you to not attempt upgrading any systems with the corrupted software image. Download the software again and verify the SHA512 checksum again. If there is a constant mismatch, please open a case with the Cisco Technical Assistance Center.

THE SPECIFICATIONS AND INFORMATION REGARDING THE PRODUCTS IN THIS MANUAL ARE SUBJECT TO CHANGE WITHOUT NOTICE. ALL STATEMENTS, INFORMATION, AND RECOMMENDATIONS IN THIS MANUAL ARE BELIEVED TO BE ACCURATE BUT ARE PRESENTED WITHOUT WARRANTY OF ANY KIND, EXPRESS OR IMPLIED. USERS MUST TAKE FULL RESPONSIBILITY FOR THEIR APPLICATION OF ANY PRODUCTS.

THE SOFTWARE LICENSE AND LIMITED WARRANTY FOR THE ACCOMPANYING PRODUCT ARE SET FORTH IN THE INFORMATION PACKET THAT SHIPPED WITH THE PRODUCT AND ARE INCORPORATED HEREIN BY THIS REFERENCE. IF YOU ARE UNABLE TO LOCATE THE SOFTWARE LICENSE OR LIMITED WARRANTY, CONTACT YOUR CISCO REPRESENTATIVE FOR A COPY.

The Cisco implementation of TCP header compression is an adaptation of a program developed by the University of California, Berkeley (UCB) as part of UCB's public domain version of the UNIX operating system. All rights reserved. Copyright © 1981, Regents of the University of California.

NOTWITHSTANDING ANY OTHER WARRANTY HEREIN, ALL DOCUMENT FILES AND SOFTWARE OF THESE SUPPLIERS ARE PROVIDED "AS IS" WITH ALL FAULTS. CISCO AND THE ABOVE-NAMED SUPPLIERS DISCLAIM ALL WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING, WITHOUT LIMITATION, THOSE OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND NONINFRINGEMENT OR ARISING FROM A COURSE OF DEALING, USAGE, OR TRADE PRACTICE.

IN NO EVENT SHALL CISCO OR ITS SUPPLIERS BE LIABLE FOR ANY INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES, INCLUDING, WITHOUT LIMITATION, LOST PROFITS OR LOSS OR DAMAGE TO DATA ARISING OUT OF THE USE OR INABILITY TO USE THIS MANUAL, EVEN IF CISCO OR ITS SUPPLIERS HAVE BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES.

Any Internet Protocol (IP) addresses and phone numbers used in this document are not intended to be actual addresses and phone numbers. Any examples, command display output, network topology diagrams, and other figures included in the document are shown for illustrative purposes only. Any use of actual IP addresses or phone numbers in illustrative content is unintentional and coincidental.

All printed copies and duplicate soft copies are considered un-Controlled copies and the original on-line version should be referred to for latest version.

Cisco has more than 200 offices worldwide. Addresses, phone numbers, and fax numbers are listed on the Cisco website at www.cisco.com/go/offices.

Cisco and the Cisco logo are trademarks or registered trademarks of Cisco and/or its affiliates in the U.S. and other countries. To view a list of Cisco trademarks, go to this URL: www.cisco.com/go/trademarks. Third-party trademarks mentioned are the property of their respective owners. The use of the word partner does not imply a partnership relationship between Cisco and any other company. (1110R)