



Technical Campus



COLLIN CONSTRUCTION SERVICES

COLLIN COLLEGE

MEET THE TEAM



Sarah Penso - Estimator

She is a first-year construction management student at Collin College. She first became interested in construction by working with her father who is an engineer and surveyor. She graduated in 2017 with Bachelor's degree in Civil Engineering from Brazil and she intends to continue her education and expand her knowledge in the industry to become a better professional.



Kimberly Rippentrop– Drafter

Kimberly started learning CADD in 1992 at Collin College with AutoCAD Release 9 on a digitizer. She has worked in the drafting and design industry for 25 years with companies like Nortel and Lockheed Martin and has owned her own custom home design and drafting company for the past 7 years. She's worked with multiple design firms, builders and software over the years and thoroughly enjoy today's 3D modeling capabilities.



Robert Chadwick – Estimator

Robert is a second-year student in Construction Management at Collin College and is currently working in commercial drywall with estimating and field work for Commercial Gyp Systems LLC. He got interested in construction because his father worked his way from the bottom until the top of the drywall trade then opening his own company for the last 6 years. Robert plans to grow the company based on the fundamental skills gained through the Collin College program.

MEET THE TEAM



DION WILLIAMS – Estimator

Dion is a second-year student in the construction management program at Collin College. His first experience in the industry came as an estimating inter for McCarthy this past Summer. Since then he has moved into another preconstruction role with a local homebuilder. Upon graduation Dion will look the move into the field and eventually become a Project Manager.



Matt Austin – Drafter


Matt is an aspiring architect and second-year CADD student at Collin College. He is currently working as a custom home designer at Tag & Associates LLC. After earning his Associate's degree at Collin, Matt plans to continue working in the field while pursuing a Bachelor's degree in Architecture at The University of Texas at Arlington.



WHO WE ARE



Collin County is one of the fastest growing counties in the nation with prolific construction projects in both residential and commercial properties.



Collin College's Construction Management program prepares students to work in a wide variety of management/supervisory positions, both in residential and commercial areas of construction.



WHAT WE DO




Technical/Project Approach

- The project will be managed by extremely reliable and detail-oriented personnel. Our priority is to provide a safe work site that will encourage productivity. Employees and subcontractors are encouraged to clean. Proper equipment training is utilized to ensure safe handling of all tools.

Qualifications

- Collin Construction Services has proven to be an industry leader by guaranteeing service in the following ways:
- Provide exceptional customer support from the design concept until delivery
- Provide top-of-the-line quality and craftsmanship through and through in every step of our building process
- Collin Construction Services focuses on hiring local craftsmanship, trades and purchasing local supplies in the North Carolina region. We pride our company on supporting local industry at any demographic area that we are building in.





MISSION STATEMENT



Our mission is to provide exceptional service from the design concept until delivery. We are committed to provide top-of-the-line quality and craftsmanship through every step of our building process

At Collin Construction Services we are confident that we can meet any challenges ahead and cooperate with our clients delivering their home on time, within budget and according to specifications.



SAFETY

- At Collin Construction Services we put safety and quality of life first.
- Our safety program is an ongoing commitment to make sure everyone involved in our projects goes home safely at the end of each day.
- Our Employees are our number one assets- their safety is our top concern.
- We provide constant training to our workers and our jobsites are inspected throughout the day to identify potential hazards and monitor workers to make sure they are working safely.



OVERVIEW

Collin Construction Services is pleased to submit this proposal for services to support M/I Homes in achieving its goals for improving customer satisfaction by providing friendly relationship and walk alongside our customers through the building process.

Included in this proposal, Collin Construction Services have composed a full set of working drawings, a material and labor estimate, and a complete construction schedule.

The construction drawings, estimate and schedule include a Crawl Space Option.

PROPOSAL SUMMARY

This proposal was created by Collin Construction Services for the construction of a single-family home located in the town of Holly Springs, North Carolina, in M/I Homes' Honeycutt Farm Community.

Projected sales price for the base design is **\$493,062.98**. The projected sales price for the design with the optional crawl space is **\$542,901.58**. The expected timeline for completion is projected to be **175 days**.




TEAM MEMBERS:

MATT AUSTIN
ROBERT CHADWICK
SARAH PENSO
KIMBERLY RIPPENTROP
DION WILLIAMS

SHEET LIST	
SHEET NUMBER	SHEET NAME
A-110	FIRST FLOOR PLAN
A-111	SECOND FLOOR PLAN
A-120	ROOF PLAN
A-201	FRONT & REAR ELEVATIONS
A-301	BUILDING SECTIONS
A-401	INTERIOR ELEVATIONS
A-601	SCHEDULES
A-101	SITE PLAN
A-102	FOUNDATION PLAN
A-100	COVER SHEET
A-202	SIDE ELEVATIONS


SURVEY PERFORMED BY:

RESIDENTIAL LAND SERVICES, PLLC.
 1917 EVANS ROAD
 CARY, NORTH CAROLINA 27513
 PHONE (919) 379-9316
 FIRM LICENSE # P-0873



SITE LOCATION

NOT TO SCALE



SETBACKS:
 FRONT YARD - 20'
 SIDE YARD - 5'
 REAR YARD - 25'

HEADRICK ROAD

VARIABLE WIDTH PUBLIC R/W

SITE PLAN

SCALE: 1/8" = 1'-0" ON 22X34 AND 1/16" = 1'-0" ON 11X17



2550 BENDING BRANCH WAY
 ALLEN, TEXAS 75013
 (972) 553-1290

100 Headrick Road



M/I HOMES

100 HEADRICK ROAD
 HOLLY SPRINGS, NC
 27540

HONEYCUTT FARMS COMMUNITY
 WAKE COUNTY

SITE PLAN


A-101

SCALE As indicated


12/16/2020 10:27:11 PM ANS/D

FOUNDATION NOTES

- FOUNDATIONS TO BE CONSTRUCTED IN ACCORDANCE WITH CHAPTER 4 OF THE 2018 NORTH CAROLINA RESIDENTIAL BUILDING CODE WITH ALL LOCAL AMENDMENTS.
- STRUCTURAL CONCRETE TO BE $F_c = 3000$ PSI, PREPARED AND PLACED IN ACCORDANCE WITH ACI STANDARD 318.
- FOOTINGS TO BE PLACED ON UNDISTURBED EARTH, BEARING A MINIMUM OF 12" BELOW ADJACENT FINISHED GRADE, OR AS OTHERWISE DIRECTED BY THE CODE ENFORCEMENT OFFICIAL.
- FOOTING SIZES BASED ON A PRESUMPTIVE SOIL BEARING CAPACITY OF 2000 PSF. CONTRACTOR IS SOLELY RESPONSIBLE FOR VERIFYING THE SUITABILITY OF THE SITE SOIL CONDITIONS AT THE TIME OF CONSTRUCTION.
- FOOTINGS AND PIERS SHALL BE CENTERED UNDER THEIR RESPECTIVE ELEMENTS. PROVIDE 2" MINIMUM FOOTING PROJECTION FROM THE FACE OF MASONRY.
- MAXIMUM DEPTH OF UNBALANCED FILL AGAINST MASONRY WALLS TO BE AS SPECIFIED IN SECTION R404.1 OF THE 2018 NORTH CAROLINA RESIDENTIAL BUILDING CODE.
- PILASTERS TO BE BONDED TO PERIMETER FOUNDATION WALL.
- PROVIDE FOUNDATION WATERPROOFING, AND DRAIN WITH POSITIVE SLOPE TO OUTLET AS REQUIRED BY SITE CONDITIONS.
- PROVIDED PERIMETER INSULATION FOR ALL FOUNDATIONS PER 2018 NORTH CAROLINA RESIDENTIAL BUILDING CODE.
- CORBEL FOUNDATION WALL AS REQUIRED TO ACCOMMODATE BRICK VENEERS.
- CRAWL SPACE TO BE GRADED LEVEL, AND CLEARED OF ALL DEBRIS.
- FOUNDATION ANCHORAGE SHALL BE CONSTRUCTED PER THE 2018 NORTH CAROLINA RESIDENTIAL CODE SECTION R403.1.6 MINIMUM $\frac{1}{8}$ " DIA. BOLTS SPACED AT 6'-0" ON CENTER WITH A 1" MINIMUM EMBEDMENT INTO MASONRY OR CONCRETE. ANCHOR BOLTS SHALL BE 12" FROM THE END OF EACH PLATE SECTION. MINIMUM (2) ANCHOR BOLTS PER PLATE SECTION ANCHOR BOLTS SHALL BE LOCATED IN THE CENTER THIRD OF THE PLATE.
- ABBREVIATIONS:
 DJ = DOUBLE JOIST, GT = GIRDER TRUSS, SC = STUD COLUMN, EE = EACH END, TJ = TRIPLE JOIST, CL = CENTER LINE, SJ = SINGLE JOIST, FR = FLOOR TRUSS, DR = DOUBLE RAFTER, TR = TRIPLE RAFTER, OC = ON CENTER, PL = POINT LOAD
- ALL PIERS TO BE 16"x16" MASONRY AND ALL PILASTERS TO BE 8"x16" MASONRY, TYPICAL. (UNO)
- WALL FOOTINGS TO BE CONTINUOUS CONCRETE, SIZES PER STRUCTURAL PLAN.
- A FOUNDATION EXCAVATION OBSERVATION SHOULD BE CONDUCTED BY A PROFESSIONAL GEOTECHNICAL ENGINEER, OR HIS QUALIFIED REPRESENTATIVE, IF ISOLATED AREAS OF YIELDING MATERIALS AND/OR POTENTIALLY EXPANSIVE SOILS ARE OBSERVED IN THE FOOTING EXCAVATIONS AT THE TIME OF CONSTRUCTION. SUMMIT ENGINEERING, LABORATORY AND TESTING, P.C. MUST BE PROVIDED THE OPPORTUNITY TO REVIEW THE FOOTING DESIGN PRIOR TO CONCRETE PLACEMENT.
- ALL FOOTINGS AND SLABS ARE TO BEAR ON UNDISTURBED SOIL OR 95% COMPACTED FILL, VERIFIED BY ENGINEER OR CODE OFFICIAL.



② TYPICAL SLAB ON GRADE FOOTING
 1 1/2" - 1'-0"




FOUNDATION PLAN
 SCALE: 1/4" = 1'-0" ON 22X34 AND 1/8" = 1'-0" ON IIX17

GENERAL FLOOR PLAN NOTES

GENERAL FLOOR PLAN NOTES SHALL APPLY UNLESS NOTED OTHERWISE ON PLAN.

1. WALL HEIGHTS: TYPICALLY 9'-1-1/2" FIRST FLOOR AND 8'-1-1/2" SECOND FLOOR U.N.O. ALL WALLS ARE CONSTRUCTED USING A DOUBLE TOP PLATE SPLICES AT DOUBLE TOP PLATE DO NOT NEED TO OCCUR AT VERTICAL STUDS BUT MUST BE AT LEAST 24" APART FROM JOIST IN OTHER TOP PLATE LAYER. SPECIAL WALL HEIGHTS ARE NOTED ON PLANS WHERE THEY OCCUR.
2. WALL THICKNESS IS TYPICALLY 4" AT EXTERIOR WALLS, 3-1/2" AT INTERIOR. 2X6 FRAME SHALL BE USED AT WALLS THAT BACK PU TO PLUMBING FIXTURES. WALLS GREATER THAN 10' HIGH SHALL BE FRAMED WITH 2X6 FRAMING OR GREATER AND WILL BE NOTED AS A SPECIAL CONDITION WHERE IT OCCURS ON PLAN.
3. HEADER HEIGHT SHALL BE 7'-11" AFF AT 9' PLATE HEIGHT AND 6'-11" AT 8' PLATE HEIGHT U.N.O.
4. SOFFITS, COPPERED CEILINGS, TREY CEILINGS AND OTHER SIGNIFICANT CEILING PLAN ELEMENTS ARE SHOWN ON THE FLOOR PLANS AND ARE DENOTED AS SINGLE DASHED LINES, UNLESS SPECIFICALLY CALLED OUT AS INCLUDED. KITCHENS DO NOT INCLUDE SOFFITS OVER WALL CABINETS.
5. DOOR & WINDOW FRAMES, WHERE OCCURRING NEAR CORNERS, SHALL BE A MINIMUM OF 4-1/2" FROM CORNER, EXCEPT FOR WALK-IN CLOSETS WITH DOORS NEAR A CORNER. DOORS AT CLOSETS SHALL BE CENTERED ON CLOSET.
6. WINDOWS SHALL HAVE AT LEAST (1) WINDOW IN EACH SLEEPING ROOM, THAT MEETS EGRESS. SHALL BE PROVIDED WITH TEMPERED GLASS AT HAZARDOUS GLAZING AREAS. WINDOWS USED AT UNFINISHED ATTIC SPACES AS ELEVATION DECORATIVE ELEMENTS SHALL HAVE ONLY OBSCURE GLAZING.
7. CLOSETS FOR CLOTHING OR COAT STORAGE SHALL BE EQUIPPED WITH 1 ROD / SHELF. CLOSETS FOR LINEN SHALL HAVE 5. CLOSETS FOR PANTRIES SHALL HAVE 5 SHELVES.
8. STAIRS SHALL HAVE A MINIMUM WIDTH OF 3'-7". TREADS SHALL BE 10" DEEP, RISERS SHALL BE A MAXIMUM OF 7-3/4", U.N.O.
9. HANDRAILS AND GUARDS AT STAIRS SHALL BE 34" ABOVE THE FINISHED SURFACE OF THE RAMP SURFACE OF THE STAIR. HANDRAILS AT LEANDINGS AND OVERLOOKS OF MULTILEVEL SPACES SHALL BE 42" ABOVE FINISHED FLOOR. GUARDS (PICKETS OR BALUSTERS) SHALL BE SPACES WITH NO MORE THAN 4" BETWEEN.
10. ATTIC ACCESS SHALL BE PROVIDED TO ATTIC AREAS THAT EXCEED 400 SQUARE FEET AND HAVE A VERTICAL HEIGHT OF 60" OR GREATER. MINIMUM CLEAR ATTIC ACCESS SHALL BE 20" X 30". PULL DOWN STAIRS AND ACCESS DOORS IN KNEE WALLS MEETING MINIMUM CRITERIA ARE ALSO ACCEPTABLE.
11. GARAGE DOOR TO LIVING SPACES SHALL BE 2'-8" X 6'-8" MINIMUM SIZE AND SHALL BE 20 MINUTE FIRE RATED AND WEATHER SEALED.
12. GARAGE CEILINGS, 5 / 8" TYPE "X" GYPSUM BOARD ON THE GARAGE CEILINGS WHEN HEATED SPACE IS ABOVE.



FIRST FLOOR PLAN

SCALE: 1/4" = 1'-0" ON 22X34 AND 1/8" = 1'-0" ON 11X17



**COLLIN
COLLEGE**

2550 BENDING BRANCH WAY
ALLEN, TEXAS 75013
(972) 553-1290

100 Headrick Road



M/I HOMES

100 HEADRICK ROAD
HOLLY SPRINGS, NC
27540

HONEYCUTT FARMS COMMUNITY
WAKE COUNTY

FIRST FLOOR PLAN


A-110

SCALE 1/4" = 1'-0"

GENERAL FLOOR PLAN NOTES

GENERAL FLOOR PLAN NOTES SHALL APPLY UNLESS NOTED OTHERWISE ON PLAN.

1. WALL HEIGHTS: TYPICALLY 9'-1 1/2" FIRST FLOOR AND 8'-1 1/2" SECOND FLOOR U.N.O. ALL WALLS ARE CONSTRUCTED USING A DOUBLE TOP PLATE SPLICES AT DOUBLE TOP PLATE DO NOT NEED TO OCCUR AT VERTICAL STUDS BUT MUST BE AT LEAST 24" APART FROM JOIST IN OTHER TOP PLATE LAYER. SPECIAL WALL HEIGHTS ARE NOTED ON PLANS WHERE THEY OCCUR.
2. WALL THICKNESS IS TYPICALLY 4" AT EXTERIOR WALLS, 3-1/2" AT INTERIOR. 2X6 FRAME SHALL BE USED AT WALLS THAT BACK UP TO PLUMBING FIXTURES. WALLS GREATER THAN 10' HIGH SHALL BE FRAMED WITH 2X6 FRAMING OR GREATER AND WILL BE NOTED AS A SPECIAL CONDITION WHERE IT OCCURS ON PLAN.
3. HEADER HEIGHT SHALL BE 7'-11" AFF AT 9' PLATE HEIGHT AND 6'-11" AT 8' PLATE HEIGHT U.N.O.
4. SOFFITS, COFFERED CEILINGS, TREY CEILINGS AND OTHER SIGNIFICANT CEILING PLAN ELEMENTS ARE SHOWN ON THE FLOOR PLANS AND ARE DENOTED AS SINGLE DASHED LINES, UNLESS SPECIFICALLY CALLED OUT AS INCLUDED. KITCHENS DO NOT INCLUDE SOFFITS OVER WALL CABINETS.
5. DOOR & WINDOW FRAMES, WHERE OCCURRING NEAR CORNERS, SHALL BE A MINIMUM OF 4-1/2" FROM CORNER. EXCEPT FOR WALK-IN CLOSETS WITH DOORS NEAR A CORNER. DOORS AT CLOSETS SHALL BE CENTERED ON CLOSET.
6. WINDOWS SHALL HAVE AT LEAST (1) WINDOW IN EACH SLEEPING ROOM, THAT MEETS EGRESS. SHALL BE PROVIDED WITH TEMPERED GLASS AT HAZARDOUS GLAZING AREAS. WINDOWS USED AT UNFINISHED ATTIC SPACES AS ELEVATION DECORATIVE ELEMENTS SHALL HAVE ONLY OBSCURE GLAZING.
7. CLOSETS FOR CLOTHING OR COAT STORAGE SHALL BE EQUIPPED WITH 1 ROD / SHELF. CLOSETS FOR LINEN SHALL HAVE 5. CLOSETS FOR PANTRIES SHALL HAVE 5 SHELVES.
8. STAIRS SHALL HAVE A MINIMUM WIDTH OF 3'-7". TREADS SHALL BE 10" DEEP, RISERS SHALL BE A MAXIMUM OF 7-3/4" U.N.O.
9. HANDRAILS AND GUARDS AT STAIRS SHALL BE 34" ABOVE THE FINISHED SURFACE OF THE RAMP SURFACE OF THE STAIR. HANDRAILS AT LEANDINGS AND OVERLOOKS OF MULTILEVEL SPACES SHALL BE 42" ABOVE FINISHED FLOOR. GUARDS (PICKETS OR BALUSTERS) SHALL BE SPACES WITH NO MORE THAN 4" BETWEEN.
10. ATTIC ACCESS SHALL BE PROVIDED TO ATTIC AREAS THAT EXCEED 400 SQUARE FEET AND HAVE A VERTICAL HEIGHT OF 60" OR GREATER. MINIMUM CLEAR ATTIC ACCESS SHALL BE 20"X30". PULL DOWN STAIRS AND ACCESS DOORS IN KNEE WALLS MEETING MINIMUM CRITERIA ARE ALSO ACCEPTABLE.
11. GARAGE DOOR TO LIVING SPACES SHALL BE 2'-8" X 6'-8" MINIMUM SIZE AND SHALL BE 20 MINUTE FIRE RATED AND WEATHER SEALED.
12. GARAGE CEILINGS, 5/8" TYPE "X" GYPSUM BOARD ON THE GARAGE CEILINGS WHEN HEATED SPACE IS ABOVE.



SECOND FLOOR PLAN

SCALE: 1/4" = 1'-0" ON 22X34 AND 1/8" = 1'-0" ON 11X7



2550 BENDING BRANCH WAY
ALLEN, TEXAS 75013
(972) 553-1290

100 Headrick Road



M/I HOMES

100 HEADRICK ROAD
HOLLY SPRINGS, NC
27540

HONEYCUTT FARMS COMMUNITY
WAKE COUNTY

SECOND FLOOR
PLAN

A-III

SCALE 1/4" = 1'-0"

1000 Headrick Road




100 HEADRICK ROAD
HOLLY SPRINGS, NC
27540


HONEYCUTT FARMS COMMUNITY
WAKE COUNTY

ROOF PLAN


A-120




2 ROOF OVERHANG AT SIDING
1 1/2" - 1'-0"



5 RIDGE VENT
5" - 1'-0"



4 PORCH ROOF OVERHANG
1 1/2" - 1'-0"



ROOF PLAN

SCALE: 1/4" = 1'-0" ON 22X34 AND 1/8" = 1'-0" ON 11X17

1/2" DRIP EDGE

GENERAL FLOOR PLAN NOTES

GENERAL ELEVATION NOTES SHALL APPLY UNLESS NOTED OTHERWISE ON PLAN.

1. ROOF SHALL BE FINISHED WITH COMPOSITION SHINGLES WITH SLOPES AS NOTED ON PLAN.
2. METAL ROOF FINISH IS USED AS AN ACCENT MATERIAL AND MAY BE OPTIONAL, CONSULT COMMUNITY SPECIFICATIONS.
3. RIDGE VENT SHALL BE PROVIDED AND INSTALLED ON ALL RIDGES GREATER THAN 6' IN LENGTH PER MANUFACTURER'S SPECIFICATIONS.
4. SOFFIT VENT SHALL BE CONTINUOUS SOFFIT VENT, CONSULT COMMUNITY SPECIFICATIONS FOR MATERIAL.
5. ADDITIONAL VENTS MAY BE REQUIRED TO MEET VENTILATION REQUIREMENTS, CONSULT VENTILATION CALCULATIONS AND ADDITIONAL VENTS NOTED ON PLAN.
6. HOUSE WRAP, "TYVEK" OR APPROVED EQUAL SHALL BE INSTALLED AVER ENTIRE EXTERIOR WALL PER MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS. "ZIP" SYSTEM SHEATHING MAY SUBSTITUTE FOR HOUSE WRAP.
7. FLASHING SHALL BE PROVIDED ABOVE ALL DOOR AND WINDOW OPENINGS, ABOVE FINISH WALL MATERIAL CHANGES AND AT WALL SURFACES WHERE LOWER ROOF AREAS ABUT VERTICAL WALL SURFACES.
8. PORCH RAILINGS SHALL BE PROVIDED AT ALL PORCH WALKING SURFACES GREATER THAN 30" ABOVE ADJACENT FINISHED GRADE. IT SHALL BE 36" HIGH WITH GUARDS SPACED NO MORE THAN 4 APART. CONSULT COMMUNITY SPECIFICATIONS FOR MATERIAL.
9. FINISH WALL MATERIAL SHALL BE AS NOTED ON ELEVATION DRAWINGS. CONSULT COMMUNITY SPECIFICATIONS FOR MATERIAL MAKE-UP OF SIDING, SHOWN AS GENERIC ON DRAWING.
10. BRICK VENEER, IF INCLUDED ON ELEVATION SHALL BE TIED TO WALL SURFACE WITH GALVANIZED CORRUGATED METAL TIES AT A RATE OF 24" AC HORIZONTALLY AND 16" OC VERTICALLY SO THAT NO MORE THAN 2.67SF OF BRICK IS SUPPORTED BY (1) TIE. SPACE BETWEEN FACE OF WALL AND BACK FACE OF BRICK SHALL BE LIMITED TO A MAXIMUM OF 1". FLASHING SHALL BE PROVIDED BEHIND BRICK ABOVE ALL WALL OPENINGS AND AT BASE OF BRICK WALL. FLASHING SHALL BE A MINIMUM OF 6-MIL POLY OR OTHER CORROSION RESISTANT MATERIAL AND SHALL BE INSTALLED SO THAT IT LAPS UNDER THE HOUSE WRAP MATERIAL. A MINIMUM OF 2" VEEPHOLES SHALL BE PROVIDED AT A RATE OF 48" OC AND SHALL NOT BE LESS THAN 3/16" IN DIAMETER AND SHALL BE LOCATED IMMEDIATELY ABOVE FLASHING.
11. BRICK VENEER SUPPORT LINTELS SHALL BE PROVIDED IF BRICK VENEER IS INCLUDED ON ELEVATION. SEE STRUCTURAL PLANS FOR LINTEL SIZE, BEARING AREA, AND CONNECTION TO HEADER.
12. SHEATHINGHOUSE IS COVERED 100% WITH STRUCTURAL WOOD SHEATHING AT FRONT AND REAR AND SIDE ELEVATIONS PROVIDE NAIL PATTERN OF 3" O.C. AT PERIMETER AND 6" O.C. AT FIELD.



① NORTH VIEW - FRONT ELEVATION
1/4" = 1'-0"





② SOUTH VIEW - REAR ELEVATION
1/4" = 1'-0"

GENERAL FLOOR PLAN NOTES


GENERAL ELEVATION NOTES SHALL APPLY UNLESS NOTED OTHERWISE ON PLAN

1. ROOF SHALL BE FINISHED WITH COMPOSITION SHINGLES WITH SLOPES AS NOTED ON PLAN.
2. METAL ROOF FINISH IS USED AS ON ACCENT MATERIAL AND MAY BE OPTIONAL. CONSULT COMMUNITY SPECIFICATIONS.
3. RIDGE VENT SHALL BE PROVIDED AND INSTALLED ON ALL RIDGES GREATER THAN 6" IN LENGTH PER MANUFACTURER'S SPECIFICATIONS.
4. SOFFIT VENT SHALL BE CONTINUOUS SOFFIT VENT, CONSULT COMMUNITY SPECIFICATIONS FOR MATERIAL.
5. ADDITIONAL VENTS MAY BE REQUIRED TO MEET VENTILATION REQUIREMENTS, CONSULT VENTILATION CALCULATIONS AND ADDITIONAL VENTS NOTED ON PLAN.
6. HOUSE WRAP, "TYVEK" OR APPROVED EQUAL SHALL BE INSTALLED AVER ENTIRE EXTERIOR WALL PER MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS. "ZIP" SYSTEM SHEATHING MAY SUBSTITUTE FOR HOUSE WRAP.
7. FLASHING SHALL BE PROVIDED ABOVE ALL DOOR AND WINDOW OPENINGS, ABOVE FINISH WALL MATERIAL CHANGES AND AT WALL SURFACES WHERE LOWER ROOF AREAS ADJUT VERTICAL WALL SURFACES.
8. PORCH RAILINGS SHALL BE PROVIDED AT ALL PORCH WALKING SURFACES GREATER THAN 30" ABOVE ADJACENT FINISHED GRADE. IT SHALL BE 36" HIGH WITH GUARDS SPACED NO MORE THAN 4" APART. CONSULT COMMUNITY SPECIFICATIONS FOR MATERIAL.
9. FINISH WALL MATERIAL SHALL BE AS NOTED ON ELEVATION DRAWINGS. CONSULT COMMUNITY SPECIFICATIONS FAR MATERIAL MAKE-UP OF SIDING, SHOWN AS GENERIC ON DRAWING.
10. BRICK VENEER, IF INCLUDED ON ELEVATION SHALL BE TIED TO WALL SURFACE WITH GALVANIZED CORRUGATED METAL TIES AT O RATE OF 24" AC HORIZONTALLY AND 16" OC VERTICALLY SO THAT NO MORE THAN 2.67SF OF BRICK IS SUPPORTED BY (1) TIE. SPACE BETWEEN FACE OF WALL AND BACK FACE OF BRICK SHALL BE LIMITED TO O MAXIMUM OF 1". FLASHING SHALL BE PROVIDED BEHIND BRICK ABOVE ALL WALL OPENINGS AND AT BASE OF BRICK WALL. FLASHING SHALL BE A MINIMUM OF 6-MIL POLY OR OTHER CORROSION RESISTANT MATERIAL AND SHALL BE INSTALLED SO THAT IT LOPS UNDER THE HOUSE WRAP MATERIAL A MINIMUM OF 2". WEEPHOLES SHALL BE PROVIDED AT A RATE OF 48" OC AND SHALL NOT BE LESS THAN 5/16" IN DIAMETER AND SHALL BE LOCATED IMMEDIATELY ABOVE FLASHING.
11. BRICK VENEER SUPPORT LINTELS SHALL BE PROVIDED IF BRICK VENEER IS INCLUDED ON ELEVATION. SEE STRUCTURAL PLANS FOR LINTEL SIZE, BEARING AREA, AND CONNECTION TO HEADER.
12. SHEATHING HOUSE IS COVERED 100% WITH STRUCTURAL WOOD SHEATHING AT FRONT AND REAR AND SIDE ELEVATIONS PROVIDE NAIL PATTERN OF 3" O.C. AT PERIMETER AND 6" O.C. AT FIELD.






3 TYP EXT WALL
3/8" = 1'-0"




4 TYP INT WALL
3/8" = 1'-0"




1 CROSS SECTION 1
1/4" = 1'-0"




2 CROSS SECTION 2
1/4" = 1'-0"




⑧ BASE CABINET -
DRAWER AND DOOR
1 1/2" - 1'-0"




⑥ BASE CABINET -
APPLIANCE / EQUIPMENT
1 1/2" - 1'-0"




④ UPPER CABINET -
TYPICAL
1 1/2" - 1'-0"




① BATH 2 VANITY
3/4" - 1'-0"




⑦ KITCHEN REFRIGERATOR
3/4" - 1'-0"



⑤ MASTER BATH VANITY
3/4" - 1'-0"



② KITCHEN RANGE
3/4" - 1'-0"



③ KITCHEN - ISLAND
3/4" - 1'-0"

Door Schedule									
Door Number	Door Type	Door Size	Rough Width	Rough Height	Function	Frame Type	Fire Rating	Finish	
								Comments	
1	57	36" x 80"	3' - 2"	6' - 9"	Exterior	Fiberglass		GBG Glass Insert w/ 2-Panels Below (Estate)	
2	58	12" x 80"	1' - 2"	6' - 9"	Exterior	Wood		Simple GBG Rectangles (per plan)	
3	58	12" x 80"	1' - 2"	6' - 9"	Exterior	Wood		Simple GBG Rectangles (per plan)	
4	67	32" x 80"	2' - 10"	6' - 9"	Interior	Steel		2-Panel square, Smooth	
5	60	30" x 80"	2' - 8"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
6	60	30" x 80"	2' - 8"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
7	60	30" x 80"	2' - 8"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
8	69	28" x 80"	2' - 6"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
10	63	192" x 84"	16' - 2"	7' - 1"	Exterior	Metal		32-Panel Insulated	
11	60	30" x 80"	2' - 8"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
12	69	28" x 80"	2' - 6"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
13	66	48" x 80"	4' - 2"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
14	69	28" x 80"	2' - 6"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
15	67	32" x 80"	2' - 10"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
16	69	28" x 80"	2' - 6"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
17	60	30" x 80"	2' - 8"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
18	69	28" x 80"	2' - 6"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
19	66	48" x 80"	4' - 2"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
20	61	24" x 80"	2' - 2"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
21	66	48" x 80"	4' - 2"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
22	66	48" x 80"	4' - 2"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
23	67	32" x 80"	2' - 10"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
24	69	28" x 80"	2' - 6"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
25	69	28" x 80"	2' - 6"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
26	60	30" x 80"	2' - 8"	6' - 9"	Interior	Wood		2-Panel square, Smooth	
27	76	32" x 80" Ext	2' - 10"	6' - 9"	Exterior	Metal		Full Glass	
30	71	48" x 80"	4' - 2"	6' - 9"	Interior	Wood		2-Panel square, Smooth	

Window Schedule									
Type Mark	Rough Opening		Type	Material	Jamb.	Glazing		Head Height	Comments
	Width	Height				Thickness	Type		
48	5' - 6"	1' - 0"	Fixed with Trim	VINYL	Sheetrock	1/8	LOW-E	7' - 9"	6 Lite
2030	2' - 0"	3' - 0"	Window-Fixed-Oval	VINYL	Sheetrock	1/8	LOW-E	6' - 0"	2 lite over 2 lite
2040	2' - 0"	4' - 0"	Window-Single-Hung	VINYL	Sheetrock	1/8	LOW-E	6' - 11"	4 lite over Clear
2050	2' - 0"	5' - 0"	Window-Single-Hung	VINYL	Sheetrock	1/8	LOW-E	6' - 11"	6 lite over Clear
3030	3' - 0"	3' - 0"	Window-Single-Hung	VINYL	Sheetrock	1/8	LOW-E	7' - 11"	6 lite over Clear
3050	3' - 0"	5' - 0"	Window-Single-Hung	VINYL	Sheetrock	1/8	LOW-E	6' - 11"	6 lite over Clear
3060	3' - 0"	6' - 0"	Window-Single-Hung	VINYL	Sheetrock	1/8	LOW-E	7' - 11"	6 lite over Clear
4040	4' - 0"	4' - 0"	Window-Single-Hung	VINYL	Sheetrock	1/8	LOW-E	6' - 11"	Clear
6050	6' - 0"	5' - 0"	Window-Single-Hung-Double	VINYL	Sheetrock	1/8	LOW-E	6' - 11"	6 lite over Clear
6060	6' - 0"	6' - 0"	Window-Single-Hung-Double	VINYL	Sheetrock	1/8	LOW-E	7' - 11"	6 lite over Clear

Room Finish Schedule						
Room Number	Room Name	Floor	Base	Finish		
				Wall	Ceiling	Ceiling Height
1	FLEX ROOM/OPT. BEDROOM #5	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
2	2- CAR GARAGE		NONE	UNPAINTED	UNPAINTED	9
3	DINING ROOM	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
4	STUDY	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
5	GREAT ROOM	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
6	BREAKFAST AREA	VINYL L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
7	KITCHEN	VINYL L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
8	PWDR	VINYL L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
9	MEDIA ROOM	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
10	BEDROOM #4	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
11	BEDROOM #3	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
12	BEDROOM #2	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
13	LAUNDRY	VINYL L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
14	BATH 2	VINYL L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
15	MASTER BEDROOM	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
16	WIC	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
17	LOFT/ SITTING ROOM	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
18	WIC	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
19	PANTRY	VINYL L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9
20	PORCH		NONE			9
21	PATIO/DECK		NONE			9
22	WIC	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
23	WIC	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
24	HALLWAY	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
25	BATH 2	VINYL L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
26	CLOSET	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
27	MASTER BATHROOM	TILE L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
28	WIC	CARPET L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	8
29	FOYER	ENG WOOD L1	5-1/4" "Speed Base"	SMOOTH, PAINTED-Choice	PAINTED-Bright White	9



2550 BENDING BRANCH WAY
ALLEN, TEXAS 75013
(972) 553-1290

1000 Headrick Road



M/I HOMES

100 HEADRICK ROAD
HOLLY SPRINGS, NC
27540

HONEYCUTT FARMS COMMUNITY
WAKE COUNTY

SCHEDULES

A-601

SCALE

12/16/2020 10:27:15 PM ANS/D

Projected Profit and Loss Statement

With Crawl Space Option

Projected Sales Price	\$492,151.99	\$534,063.53
Projected Cost of Sales	\$410,126.66	\$445,052.95
Projected Gross Profit	\$82,025.33	\$89,010.59
Projected Real Estate Comission	\$10,253.17	\$11,126.32
Projected Overhead	\$12,303.80	\$13,351.59
Projected Extra labor & Material	\$6,151.90	\$6,675.79
	\$28,708.87	\$31,153.71
Projected Profit Margin %	10.83	10.83
Projected Net Profit	\$53,316.47	\$57,856.88

Estimate									Crawl Space Option				
CATEGORY/ACTIVITY	ITEM	UNIT	QUANTITY	UNIT PRICE	MATERIAL COST	LABOR COST	TURNKEY COST	TOTAL COST	QUANTITY	MATERIAL COST	LABOR COST	TURNKEY COST	TOTAL COST
ESTIMATE SUMMARY													
General Expenses													
Foundation													\$ 22,888.10
Framing													\$ 8,913.84
Roofing													
Exterior finishes													\$ 7,116.00
Doors and Windows													
Insulation													\$ 701.40
Drywall													\$ 185.44
Flooring													
Paint													
Doors and Windows													
Interior trim and shelving													
Cabinets													
Appliances													
Landscaping													
Sales tax 7.25%													\$ 1,727.38
Allowances													
Plumbing													
HVAC													
Electrical													
Building cost													\$41,532.16
GENERAL EXPENSES													
Lot price													\$ 130,000.00
Building Permit													\$ 10,283.97
Occupancy permit													\$ 50.00
Corporate Charges													\$ 4,090.00
Construction financing cost													\$ 1,600.00
Corporate Charges													\$ 4,090.00
Water tap													\$ 900.00
Sewer tap													\$ 900.00
Portable toilet													\$ 501.93
Dumpster 20 yards													\$ 640.00
Energy Star Test & Certification													\$ 1,250.00
Temp Drive													\$ 500.00
Final cleaning													\$ 1,000.00
FOUNDATION													\$ 30,357.75
FORM BOARDS													
2X12													
Stakes									1092	\$ 3,439.80	\$ 910.00		
EXCAVATION									182	\$ 573.30			\$ 13,500.00
REINFORCING BARS													
6"x6" W1.4 W1.4 WWM 8'x20' 2148Sqt													
Anchor Bolts - 50-Pack									-14	\$ (784.00)	\$ (1,875.00)		
CONCRETE SLAB													\$ 16,520.00
VAPOR BARRIER													\$ 250.00
CRAWL SPACE													
Footing													\$ 6,758.00
Foam Board Insulation										\$ 366.00			
TOTAL										\$ 3,595.10	\$ (965.00)	\$ 20,258.00	
STRUCTURAL FRAMING													\$ 8,913.84
ROUGH LUMBER													
2x4 Studs 9'									-58	\$ (270.60)			
2x6 Studs 9'													\$ 178.40
2x4 Studs 8'													\$ 1,528.32
2x6 Plates													\$ 22.00

2x4 Plates	2523 Ln Ft	Ln Ft	1766	\$ 1.00	\$ 1,766.00														
Equipment	Crane	UN.	1							\$ 500.00									
Prefab Roof Trusses	12" O.C. Prefabricated Roof Trusses	UN.	100	\$ 60.00	\$ 6,000.00														
8" Box Column	8" Box Column x 8 Columns	UN.	8	\$ 254.38	\$ 2,035.04														
Fascia Board	1x8 Fascia Board for 252 Ln Ft	Ln Ft	252	\$ 0.99	\$ 248.98														
Common Nails	3 1/2" 50lbs Nail	UN.	5	\$ 61.50	\$ 307.50														
3/4" Decking	T&G Plywood Decking for 2nd floor 2000sqFt	UN.	66	\$ 27.43															
ALT 2x4 Studs x 13'	71 Ln Ft	UN.		\$ 7.38								58	\$ 428.04	\$ 150.00	\$ 200.00				
ALT 3/4" Decking	T&G Plywood Decking for 1st floor 1512sqFt	UN.		\$ 27.43								50	\$ 1,371.50	\$ 1,300.00					
STAIRS																			
Stringers 2X12-16		UN.	3	\$29.00	\$87.00														
2x4-16 #2&BTR		UN.	3	\$7.15	\$21.45														
1X8 Riser		Ln Ft	60	\$0.85	\$51.00														
1 1/8 x 11 1/4		UN.	5	\$15.50	\$77.50														
TAEXX BUILT-IN PEST CONTROL																			
		UN.	1							\$ 600.00									
EXTERIOR SHEATHING																			
7/16" OSB	4x8 Zip OSB Wall Sheathing 3456sq Ft	UN.	119	\$ 20.25						\$ 2,409.75									
Tyvek Housewrap	9x150 Rolls cover 3456sq Ft	UN.	8	\$ 140.25	\$ 1,122.00														
Tyvek Housewrap Tape	164ft rolls	UN.	6	\$ 13.08	\$ 78.48														
SAFETY RAILS																			
ALT Rails for Front Porch	Prefab Railing	UN.	1	\$ 110.25	\$ 110.25	\$ 150.00						5	\$ 551.25	\$ 250.00					
Rails for Interior Stairs	Prefab Railing	UN.	1	\$ 350.00	\$ 350.00	\$ 150.00													
I-JOIST																			
I-JOIST 50'	50' I-Joist 16 O.C.	UN.	34	\$ 92.35						\$ 3,139.90									
CRAWL SPACE																			
I-JOIST																			
ALT I-JOIST 30'	30' I-Joist 16" O.C.	UN.		\$ 52.25								21	\$ 1,097.25	\$ 2,500.00					
ALT I-JOIST 36'	36' I-Joist 16" O.C.	UN.		\$ 55.00								6	\$ 330.00						
ALT End Plate	2x12x12	UN.		\$ 19.49								10	\$ 194.90						
ALT 2x4		Ln Ft		\$ 0.58								374	\$ 216.92						
TOTAL					\$ 15,210.62	\$ 29,780.00	\$ 6,649.65						\$ 3,812.59	\$ 4,751.25	\$ 350.00				
ROOFING																			
\$ 7,369.21																			
Sheathing	4x8 OSB Roof Sheathing	UN.	104	\$ 16.00	\$ 1,664.00	\$ 700.00													
Roofing Felt	432Sq Ft Rolls for 2750 Sq Ft Roof	UN.	7	\$ 39.58	\$ 277.06														
Shingles	30 Year Shingles 32.85sq Ft (26pc) per Package 275	UN.	84	\$ 31.48	\$ 2,644.32	\$ 1,400.00													
Hip and Ridge Shingles	Hip & Ridge Bundle	UN.	3	\$ 24.49	\$ 73.47														
Starter Strip Shingles	Start Strip for Shingles 33Ln Ft Each for 210Ln Ft	UN.	7	\$ 21.30	\$ 149.10														
Ridge Vent	52' Ridge Vent 20' Each Roll Plus Other Gables	UN.	5	\$ 45.49	\$ 227.45														
H-clips	50 Per Bag	UN.	2	\$ 6.54	\$ 13.08														
Roofing Nails w/ Cap	~8800 Per 50Lb Box With 4 Per Shingle Plus Starter	UN.	1	\$ 59.48	\$ 59.48														
Common Nails for OSB Sheathing	~5000 Per 50Lb Box With 36 Nails Per Sheet	UN.	1	\$ 71.25	\$ 71.25														
Pipe Boot		UN.	4	\$ 7.50	\$ 30.00														
Nails	Box	UN.	2	30	\$ 60.00														
TOTAL					\$ 5,269.21	\$ 2,100.00	\$ -												
EXTERIOR FINISH																			
\$ 16,647.17																			
PAINTING																			
Painting Batten & Board and Fascia	Painter Provides Paint	Sq Ft	426	\$ 3.25						\$ 1,384.50									
Painting Columns	Painter Provides Paint	Sq Ft	168	\$ 3.25						\$ 546.00									
Painting Trim Board	Painter Provides Paint	Sq Ft	98	\$ 3.25						\$ 318.50									
SIDING																			
Batten	1x3 Trim Joint Board	Ln Ft	240	\$ 5.25	\$ 1,260.00	\$ 3,825.00													
Board	1x12 Board	Ln Ft	236	\$ 5.25	\$ 1,239.00														
15" Shutters	15" Shutters x 3 Pairs	Ea	3	\$ 243.25	\$ 729.75														
10" Shutters	10" Shutters x 1 Pair	Ea	1	\$ 238.18	\$ 238.18														
Fiber Cement Lap Siding	1'x12' Lap Siding for 5492 Ln Ft	Ea	504	\$ 8.05	\$ 4,057.20														
Trim Behind Fascia	1x4" Trim Board 35 Ln Ft	Ln Ft	38	\$ 0.98	\$ 37.24														
1x10 Headers	1x10 Header 26 Ln Ft	Ln Ft	28	\$ 2.10	\$ 58.80														
Trim at Corners and Sill	1x6 Trim Board for Corners and Sill	Ln Ft	110	\$ 0.75	\$ 82.50														
STONE EXTERIOR																			
Stone Veneer	Stone & Mortar	Sq Ft	205	\$ 6.50	\$ 1,332.50	\$ 1,538.00													
CRAWL SPACE																			
Stone Veneer	Stone & Mortar	Sq Ft		\$ 6.50								584	\$ 3,796.00	\$ 1,320.00					
Exterior Stairs																		\$ 2,000.00	
Crawl space entry door													\$ 128.00						
TOTAL					\$ 9,035.17	\$ 5,363.00	\$ 2,249.00						\$ 3,796.00	\$ 1,320.00	\$ 2,000.00				

POWDER ROOM BATH ACCESSORIES	Polished Chrome, Square (Includes 1 Towel Ring and 1 Paper Holder)	UN.	2	\$ 25.00			\$ 50.00						
TOTAL													
APPLIANCES								\$ 2,440.00					
RANGE	Electric Freestanding Range: JB625RK Stainless Steel GE	UN.	1	\$ 1,142.00	\$ 1,142.00	\$ 100.00							
MICROWAVE	JVM3162RJ Stainless Steel (Vented to the Outside) GE	UN.	1	\$ 289.00	\$ 289.00	\$ 100.00							
DISHWASHER	GSD3360K Stainless Steel (Energy Star Rated) GE	UN.	1	\$ 709.00	\$ 709.00	\$ 100.00							
TOTAL					\$ 2,140.00	\$ 300.00							
LANDSCAPING								\$ 9,000.00					
PLUMBING	Includes Fixtures and Pipes							\$ 16,348.50					
HVAC								\$ 8,279.00					
ELECTRICAL	Includes Light Fixtures							\$ 10,021.00					
TOTAL SALES TAX 7.25%					\$ 144,076.31			\$ 10,445.53	\$ 23,825.98			\$ 1,727.38	

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20					Nov '20							
							13	20	27	4	11	18	25	1	8	15	22		
0	100 Headrick Road, Holly Springs, NC PT2	142 days	Mon 2/1/21	Tue 8/17/21															
1	General Conditions	20 days	Mon 2/1/21	Fri 2/26/21															
2	Finalize plans and develop esti	5 days	Mon 2/1/21	Fri 2/5/21		General contractor													
3	Sign contract and notice to pro	1 day	Mon 2/8/21	Mon 2/8/21	2	General contractor													
4	Apply for Permits	10 days	Mon 2/15/21	Fri 2/26/21															
5	Secure Permits	1 day	Fri 2/26/21	Fri 2/26/21		General contractor													
6	Site Work	4 days	Mon 3/1/21	Thu 3/4/21															
7	Order long lead items	1 day	Mon 3/1/21	Mon 3/1/21		General contractor													
8	Initial Erosion Control	1 day	Mon 3/1/21	Mon 3/1/21		Erosion Control Contractor													
9	Install Temporary Power Pole	1 day	Tue 3/2/21	Tue 3/2/21	8	Electric company													
12	60 Erosion Control inspection	1 day	Tue 3/2/21	Tue 3/2/21	8	Inspector													
11	Connect Temp Power	1 day	Wed 3/3/21	Wed 3/3/21	9	Electric company													
10	30 Temp Board Inspection	1 day	Thu 3/4/21	Thu 3/4/21	11	Inspector													
13	Foundation	12 days	Fri 3/5/21	Mon 3/22/21	6														
14	Deliver Form Boards, Re-bar/M	1 day	Fri 3/5/21	Fri 3/5/21	12	Concrete contractor													
15	Excavate for foundations	1 day	Mon 3/8/21	Mon 3/8/21	14	Site excavation contractor													
16	Form Boards	1 day	Tue 3/9/21	Tue 3/9/21	15	Concrete contractor													
19	Install Underground Plumbing	1 day	Tue 3/9/21	Tue 3/9/21	15	Electric contractor,Plumbing contractor													
20	Plumbing Rough-in	1 day	Tue 3/9/21	Tue 3/9/21	15	Plumbing contractor													
17	Survey Form Boards	1 day	Wed 3/10/21	Wed 3/10/21	16	Surveyor													
21	Install Underground Electrical	1 day	Wed 3/10/21	Wed 3/10/21	19	Electric company													
28	51 Plumbing Rough-In Inspecti	1 day	Wed 3/10/21	Wed 3/10/21	20	Inspector													
18	01 Foundation Survey Inspecti	1 day	Thu 3/11/21	Thu 3/11/21	17	Inspector													
22	31 Electrical Ground Work Inspe	1 day	Thu 3/11/21	Thu 3/11/21	21	Inspector													
23	50 Plumbing Underground Inspection	1 day	Thu 3/11/21	Thu 3/11/21	21	Inspector[25%]													
24	Install Slab Makeup	1 day	Fri 3/12/21	Fri 3/12/21	23	Concrete contractor													
25	13 Slab Inspection	1 day	Mon 3/15/21	Mon 3/15/21	24	Inspector													
26	Box Plumbing	1 day	Tue 3/16/21	Tue 3/16/21	25	Plumbing contractor													
27	Pour Concrete for Slab	3 days	Wed 3/17/21	Fri 3/19/21	26	Concrete contractor													
29	Backfill	1 day	Mon 3/22/21	Mon 3/22/21	27	Site excavation contractor													
30	Framing	12 days	Tue 3/23/21	Wed 4/7/21	13														
31	Deliver 1st Floor Lumber Packa	1 day	Tue 3/23/21	Tue 3/23/21	29	Supply Contractor													

Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20					Nov '20						
							13	20	27	4	11	18	25	1	8	15	22	
32	Frame 1st floor walls	1 day	Wed 3/24/21	Wed 3/24/21	31	Framing contractor												
33	Deliver 2nd Floor Lumber Pack	1 day	Tue 3/30/21	Tue 3/30/21		Supply Contractor												
34	Install 2nd floor joists and Decl	1 day	Wed 3/31/21	Wed 3/31/21	33	Framing contractor												
35	Frame 2nd floor decking	1 day	Thu 4/1/21	Thu 4/1/21	34	Framing contractor												
36	Frame 2nd floor walls	2 days	Fri 4/2/21	Mon 4/5/21	35	Framing contractor												
37	Deliver Roof Lumber Package	1 day	Mon 4/5/21	Mon 4/5/21		Supply Contractor												
38	Complete roof framing	2 days	Tue 4/6/21	Wed 4/7/21	37	Framing contractor												
39	Dry In	9 days	Mon 4/12/21	Thu 4/22/21	30													
40	Deliver Sheathing	1 day	Mon 4/12/21	Mon 4/12/21	38	Supply Contractor												
41	Install Exterior Sheathing	2 days	Tue 4/13/21	Wed 4/14/21	40	Framing contractor												
42	Deliver Roofing Package	1 day	Thu 4/15/21	Thu 4/15/21	41	Supply Contractor												
43	Wrap House	1 day	Fri 4/16/21	Fri 4/16/21	42	Exterior Contractor												
44	Install roof decking	1 day	Mon 4/19/21	Mon 4/19/21	43	Framing contractor												
45	Install felt, flashing and shingle	1 day	Tue 4/20/21	Tue 4/20/21	44	Roofing contractor												
46	Hang 1st floor exterior doors	1 day	Wed 4/21/21	Wed 4/21/21	45	Framing contractor												
47	Install Windows	1 day	Thu 4/22/21	Thu 4/22/21	46	Framing contractor												
48	MEP Top-Out	4 days	Fri 4/23/21	Wed 4/28/21														
49	Plumbing Top-Out	1 day	Fri 4/23/21	Fri 4/23/21	47	Plumbing contractor												
50	Mechanical Rough-In	1 day	Mon 4/26/21	Mon 4/26/21	49	Heating and AC contractor												
51	Electrical Rough-In	1 day	Tue 4/27/21	Tue 4/27/21	50	Electric company												
52	17 Framing Inspection	1 day	Wed 4/28/21	Wed 4/28/21	51	Inspector												
53	Exterior Finishes	4 days	Mon 5/17/21	Thu 5/20/21	39													
54	Install Stone Veneer	2 days	Mon 5/17/21	Tue 5/18/21	47	Masonry contractor												
55	Complete exterior siding	2 days	Wed 5/19/21	Thu 5/20/21	54	Exterior Contractor												
56	Complete Inside of House	41 days	Mon 5/17/21	Mon 7/12/21	39													
57	Insulation	7 days	Mon 5/17/21	Tue 5/25/21														
58	Place wall insulation - 1st fl	1 day	Mon 5/17/21	Mon 5/17/21	47	Insulation contractor												
59	Place wall insulation - 2nd fl	1 day	Tue 5/18/21	Tue 5/18/21	58	Insulation contractor												
60	Place ceiling insulation-Attic	2 days	Fri 5/21/21	Mon 5/24/21	66	Insulation contractor												
61	18 Conduct insulation insper	1 day	Tue 5/25/21	Tue 5/25/21	60	Inspector												
62	Interior Finishes	41 days	Mon 5/17/21	Mon 7/12/21														
63	Drywall	7 days	Mon 5/17/21	Tue 5/25/21		Drywall contractor												
64	Deliver Drywall	1 day	Mon 5/17/21	Mon 5/17/21		Supply Contractor												
65	Install drywall - 1st floor	2 days	Tue 5/18/21	Wed 5/19/21	58	Drywall contractor												

Project: 100 Headrick Road, Ho
Date: Wed 12/16/20

Task		Inactive Task		Manual Summary Rollup		External Milestone	
Split		Inactive Milestone		Manual Summary		Deadline	
Milestone		Inactive Summary		Start-only		Progress	
Summary		Manual Task		Finish-only		Manual Progress	
Project Summary		Duration-only		External Tasks			

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20							Nov '20					
							13	20	27	4	11	18	25	1	8	15	22		
66	Install drywall 2nd floor	2 days	Wed 5/19/21	Thu 5/20/21	59	Drywall contractor													
67	Tape and float 1st floor di	3 days	Thu 5/20/21	Mon 5/24/21	65	Drywall contractor													
68	Tape and float 2nd floor c	3 days	Fri 5/21/21	Tue 5/25/21	66	Drywall contractor													
69	Millwork	8 days	Wed 5/26/21	Fri 6/4/21	68														
70	Install 1st floor Millwork	3 days	Wed 5/26/21	Fri 5/28/21	68	Finish carpentry contractor													
71	Install 2nd Floor Millwork	3 days	Mon 5/31/21	Wed 6/2/21	70	Finish carpentry contractor													
72	Install chair rails, crown m	2 days	Thu 6/3/21	Fri 6/4/21	71	Finish carpentry contractor													
73	Paint	8 days	Mon 6/7/21	Wed 6/16/21	72														
74	Paint all of 1st floor	2 days	Mon 6/7/21	Tue 6/8/21	72	Painting contractor													
75	Paint all of 2nd floor	2 days	Wed 6/9/21	Thu 6/10/21	74	Painting contractor													
76	Paint exterior siding& trin	4 days	Fri 6/11/21	Wed 6/16/21	75	Painting contractor													
77	Finish Plumbing	8 days	Thu 6/17/21	Mon 6/28/21	76														
78	Install Tile to Prepare for	3 days	Thu 6/17/21	Mon 6/21/21	76	Flooring contractor													
79	Complete 1st floor - kitch	1 day	Tue 6/22/21	Tue 6/22/21	78	Plumbing contractor													
80	Complete 2nd floor plum	2 days	Wed 6/23/21	Thu 6/24/21	79	Plumbing contractor													
81	Trim out gas meter	1 day	Fri 6/25/21	Fri 6/25/21	80	Plumbing contractor													
82	54 Plumbing Final Inspect	1 day	Mon 6/28/21	Mon 6/28/21	81	Inspector													
83	Finish HVAC	3 days	Mon 6/28/21	Wed 6/30/21															
84	Complete 1st floor - zone	1 day	Mon 6/28/21	Mon 6/28/21	81	Heating and AC contractor													
85	Complete 2nd floor - zone	1 day	Tue 6/29/21	Tue 6/29/21	84	Heating and AC contractor													
86	44 HVAC Final inspection	1 day	Wed 6/30/21	Wed 6/30/21	85	Inspector													
87	Finish Electrical	5 days	Thu 7/1/21	Wed 7/7/21															
88	Complete 1st floor circuit	1 day	Thu 7/1/21	Thu 7/1/21	86	Electric contractor													
89	Complete 2nd floor circui	1 day	Fri 7/2/21	Fri 7/2/21	88	Electric contractor													
91	Complete communication	2 days	Mon 7/5/21	Tue 7/6/21	89	Electric contractor													
90	34 Electrical Final Inspect	1 day	Wed 7/7/21	Wed 7/7/21	91	Inspector													
92	Carpet and Appliances	8 days	Thu 7/1/21	Mon 7/12/21															
93	Install Flooring - Vinyl	3 days	Thu 7/1/21	Mon 7/5/21	86	Flooring contractor													
94	Install Flooring - 1st floor	2 days	Tue 7/6/21	Wed 7/7/21	93	Flooring contractor													
95	Install Flooring - 2nd floor	2 days	Thu 7/8/21	Fri 7/9/21	94	Flooring contractor													
96	Install appliances	1 day	Mon 7/12/21	Mon 7/12/21	95	Appliance contractor													
97	Landscaping and Grounds Work	6 days	Thu 6/17/21	Thu 6/24/21	73														
98	Pour concrete driveway and si	2 days	Thu 6/17/21	Fri 6/18/21	76	Concrete contractor													
99	Sod and complete plantings - fi	2 days	Mon 6/21/21	Tue 6/22/21	98	Landscape contractor													


Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20					Nov '20					
							13	20	27	4	11	18	25	1	8	15	22
100	Sod and complete plantings - b	1 day	Wed 6/23/21	Wed 6/23/21	99	Landscape contractor											
101	65 Street Trees Inspection	1 day	Thu 6/24/21	Thu 6/24/21	100	Inspector											
102	66 Final Erosion Control Inspec	1 day	Thu 6/24/21	Thu 6/24/21	100	Inspector											
103	Final Acceptance	26 days	Tue 7/13/21	Tue 8/17/21	97												
104	21 Final inspection for certifica	1 day	Tue 7/13/21	Tue 7/13/21	96	Inspector											
105	Cleanup for occupancy	1 day	Wed 7/14/21	Wed 7/14/21	104	Maid service											
106	Perform final walk-through ins	1 day	Thu 7/15/21	Thu 7/15/21	105	Owner											
107	Complete punch list items	14 days	Fri 7/16/21	Wed 8/4/21	106	General contractor											
108	Final Walkthrough With buyer	1 day	Thu 8/5/21	Thu 8/5/21	107	General contractor											




Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			

Dec '20 22 29 6 13 20 27 | Jan '21 3 10 17 24 | Feb '21 31 7 14 21 | Mar '21 28 7 14 21 | Apr '21 28 4 11 18 25 | May '21 2 9 16 23 30 | Jun '21 6 13 20 27 | Jul '21 4 11 18 25 | Aug '21 1 8 15 22 29 | Sep '21 5




Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			




Project: 100 Headrick Road, Ho
Date: Wed 12/16/20

Task		Inactive Task		Manual Summary Rollup		External Milestone	
Split		Inactive Milestone		Manual Summary		Deadline	
Milestone		Inactive Summary		Start-only		Progress	
Summary		Manual Task		Finish-only		Manual Progress	
Project Summary		Duration-only		External Tasks			



Project: 100 Headrick Road, Ho
Date: Wed 12/16/20

Task		Inactive Task		Manual Summary Rollup		External Milestone	
Split		Inactive Milestone		Manual Summary		Deadline	
Milestone		Inactive Summary		Start-only		Progress	
Summary		Manual Task		Finish-only		Manual Progress	
Project Summary		Duration-only		External Tasks			






















Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20					Nov '20							
							13	20	27	4	11	18	25	1	8	15			
0	100 Headrick Road, Holly Springs, NC PT2	135 days	Mon 2/1/21	Fri 8/6/21															
1	General Conditions	20 days	Mon 2/1/21	Fri 2/26/21															
2	Finalize plans and develop estimate	5 days	Mon 2/1/21	Fri 2/5/21		General contractor													
3	Sign contract and notice to proceed	1 day	Mon 2/8/21	Mon 2/8/21	2	General contractor													
4	Apply for Permits	10 days	Mon 2/15/21	Fri 2/26/21															
5	Secure Permits	1 day	Fri 2/26/21	Fri 2/26/21		General contractor													
6	Site Work	4 days	Mon 3/1/21	Thu 3/4/21															
7	Order long lead items	1 day	Mon 3/1/21	Mon 3/1/21		General contractor													
8	Initial Erosion Control	1 day	Mon 3/1/21	Mon 3/1/21		Erosion Control Contractor													
9	Install Temporary Power Pole	1 day	Tue 3/2/21	Tue 3/2/21	8	Electric company													
12	60 Erosion Control inspection	1 day	Tue 3/2/21	Tue 3/2/21	8	Inspector													
11	Connect Temp Power	1 day	Wed 3/3/21	Wed 3/3/21	9	Electric company													
10	30 Temp Board Inspection	1 day	Thu 3/4/21	Thu 3/4/21	11	Inspector													
13	Foundation	11 days	Fri 3/5/21	Fri 3/19/21	6														
14	Deliver Form Boards, Re-bar/M	1 day	Fri 3/5/21	Fri 3/5/21	12	Supply Contractor													
15	Excavate for foundations	1 day	Mon 3/8/21	Mon 3/8/21	14	Site excavation contractor													
16	Form Boards	1 day	Tue 3/9/21	Tue 3/9/21	15	Concrete contractor													
19	Install Underground Plumbing	1 day	Tue 3/9/21	Tue 3/9/21	15	Electric contractor,Plumbing contractor													
20	Plumbing Rough-in	1 day	Tue 3/9/21	Tue 3/9/21	15	Plumbing contractor													
17	Survey Form Boards	1 day	Wed 3/10/21	Wed 3/10/21	16	Surveyor													
21	Install Underground Electrical	1 day	Wed 3/10/21	Wed 3/10/21	19	Electric company													
27	51 Plumbing Rough-In Inspecti	1 day	Wed 3/10/21	Wed 3/10/21	20	Inspector													
18	01 Foundation Survey Inspecti	1 day	Thu 3/11/21	Thu 3/11/21	17	Inspector													
22	31 Electrical Ground Work Insp	1 day	Thu 3/11/21	Thu 3/11/21	21	Inspector													
23	50 Plumbing Underground Insp	1 day	Thu 3/11/21	Thu 3/11/21	21	Inspector													
24	Install Slab Makeup	1 day	Fri 3/12/21	Fri 3/12/21	23	Concrete contractor													
25	13 Slab Inspection	1 day	Mon 3/15/21	Mon 3/15/21	24	Inspector													
26	Pour Concrete	3 days	Tue 3/16/21	Thu 3/18/21	25	Concrete contractor													
28	Backfill	1 day	Fri 3/19/21	Fri 3/19/21	26	Site excavation contractor													
29	Framing	13 days	Mon 3/22/21	Wed 4/7/21	13														
30	Deliver 1st Floor Lumber Packa	1 day	Mon 3/22/21	Mon 3/22/21	28	Supply Contractor													
31	Frame 1st Floor System	2 days	Tue 3/23/21	Wed 3/24/21	30	Framing contractor													

Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20					Nov '20				
							13	20	27	4	11	18	25	1	8	15
32	Frame 1st floor walls	1 day	Thu 3/25/21	Thu 3/25/21	31	Framing contractor										
33	Deliver 2nd Floor Lumber Pack	1 day	Tue 3/30/21	Tue 3/30/21		Supply Contractor										
34	Install 2nd floor joists and Decl	1 day	Wed 3/31/21	Wed 3/31/21	33	Framing contractor										
35	Frame 2nd floor decking	1 day	Thu 4/1/21	Thu 4/1/21	34	Framing contractor										
36	Frame 2nd floor walls	2 days	Fri 4/2/21	Mon 4/5/21	35	Framing contractor										
37	Deliver Roof Lumber Package	1 day	Mon 4/5/21	Mon 4/5/21												
38	Complete roof framing	2 days	Tue 4/6/21	Wed 4/7/21	37	Framing contractor										
39	Dry In	9 days	Thu 4/15/21	Tue 4/27/21	29											
40	Deliver Sheathing	1 day	Thu 4/15/21	Thu 4/15/21	38	Supply Contractor										
41	Install Exterior Sheathing	2 days	Fri 4/16/21	Mon 4/19/21	40	Framing contractor										
42	Deliver Roofing Package	1 day	Tue 4/20/21	Tue 4/20/21	41	Supply Contractor										
43	Wrap House	1 day	Wed 4/21/21	Wed 4/21/21	42	Exterior Contractor										
44	Install roof decking	1 day	Thu 4/22/21	Thu 4/22/21	43	Framing contractor										
45	Install felt, flashing and shingle	1 day	Fri 4/23/21	Fri 4/23/21	44	Roofing contractor										
46	Hang 1st floor exterior doors	1 day	Mon 4/26/21	Mon 4/26/21	45	Framing contractor										
47	Install Windows	1 day	Tue 4/27/21	Tue 4/27/21	46	Framing contractor										
48	MEP Top-Out	4 days	Wed 4/28/21	Mon 5/3/21												
49	Plumbing Top-Out	1 day	Wed 4/28/21	Wed 4/28/21	47	Plumbing contractor										
50	Mechanical Rough-In	1 day	Thu 4/29/21	Thu 4/29/21	49	Heating and AC contractor										
51	Electrical Rough-In	1 day	Fri 4/30/21	Fri 4/30/21	50	Electric company										
52	17 Framing Inspection	1 day	Mon 5/3/21	Mon 5/3/21	51	Inspector										
53	Exterior Finishes	5 days	Mon 5/17/21	Fri 5/21/21	39											
54	Install Stone Veneer	3 days	Mon 5/17/21	Wed 5/19/21	47	Masonry contractor										
56	Install Front Porch Railing	1 day	Mon 5/17/21	Mon 5/17/21		Exterior Contractor										
55	Complete exterior siding	2 days	Thu 5/20/21	Fri 5/21/21	54	Exterior Contractor										
57	Complete Inside of House	42 days	Mon 5/17/21	Tue 7/13/21	39											
58	Insulation	8 days	Mon 5/17/21	Wed 5/26/21												
59	Place Insulation - 1st floor	2 days	Mon 5/17/21	Tue 5/18/21	47	Insulation contractor										
60	Place insulation - 2nd floor	1 day	Wed 5/19/21	Wed 5/19/21	59	Insulation contractor										
61	Place ceiling insulation-Attic	2 days	Mon 5/24/21	Tue 5/25/21	67	Insulation contractor										
62	18 Conduct insulation insper	1 day	Wed 5/26/21	Wed 5/26/21	61	Inspector										
63	Interior Finishes	42 days	Mon 5/17/21	Tue 7/13/21												
64	Drywall	8 days	Mon 5/17/21	Wed 5/26/21		Drywall contractor										
65	Deliver Drywall	1 day	Mon 5/17/21	Mon 5/17/21		Supply Contractor										

Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20					Nov '20					
							13	20	27	4	11	18	25	1	8	15	
66	Install drywall - 1st floor	2 days	Wed 5/19/21	Thu 5/20/21	59	Drywall contractor											
67	Install drywall 2nd floor	2 days	Thu 5/20/21	Fri 5/21/21	60	Drywall contractor											
68	Tape and float 1st floor d	3 days	Fri 5/21/21	Tue 5/25/21	66	Drywall contractor											
69	Tape and float 2nd floor c	3 days	Mon 5/24/21	Wed 5/26/21	67	Drywall contractor											
70	Millwork	8 days	Thu 5/27/21	Mon 6/7/21													
71	Install 1st floor Millwork	3 days	Thu 5/27/21	Mon 5/31/21	69	Finish carpentry contractor											
72	Install 2nd Floor Millwork	3 days	Tue 6/1/21	Thu 6/3/21	71	Finish carpentry contractor											
73	Install chair rails, crown m	2 days	Fri 6/4/21	Mon 6/7/21	72	Finish carpentry contractor											
74	Paint	8 days	Tue 6/8/21	Thu 6/17/21													
75	Paint all of 1st floor	2 days	Tue 6/8/21	Wed 6/9/21	73	Painting contractor											
76	Paint all of 2nd floor	2 days	Thu 6/10/21	Fri 6/11/21	75	Painting contractor											
77	Paint exterior siding& trin	4 days	Mon 6/14/21	Thu 6/17/21	76	Painting contractor											
78	Finish Plumbing	8 days	Fri 6/18/21	Tue 6/29/21													
79	Install Tile to Prepare for	3 days	Fri 6/18/21	Tue 6/22/21	77	Flooring contractor											
80	Complete 1st floor - kitch	1 day	Wed 6/23/21	Wed 6/23/21	79	Plumbing contractor											
81	Complete 2nd floor plum	2 days	Thu 6/24/21	Fri 6/25/21	80	Plumbing contractor											
82	Trim out gas meter	1 day	Mon 6/28/21	Mon 6/28/21	81	Plumbing contractor											
83	54 Plumbing Final Inspect	1 day	Tue 6/29/21	Tue 6/29/21	82	Inspector											
84	Finish HVAC	3 days	Tue 6/29/21	Thu 7/1/21													
85	Complete 1st floor - zone 1	1 day	Tue 6/29/21	Tue 6/29/21	82	Heating and AC contractor											
86	Complete 2nd floor - zone	1 day	Wed 6/30/21	Wed 6/30/21	85	Heating and AC contractor											
87	44 HVAC Final inspection	1 day	Thu 7/1/21	Thu 7/1/21	86	Inspector											
88	Finish Electrical	5 days	Fri 7/2/21	Thu 7/8/21													
89	Complete 1st floor circuit	1 day	Fri 7/2/21	Fri 7/2/21	87	Electric contractor											
90	Complete 2nd floor circui	1 day	Mon 7/5/21	Mon 7/5/21	89	Electric contractor											
92	Complete communication	2 days	Tue 7/6/21	Wed 7/7/21	90	Electric contractor											
91	34 Electrical Final Inspect	1 day	Thu 7/8/21	Thu 7/8/21	92	Inspector											
93	Carpet and Appliances	8 days	Fri 7/2/21	Tue 7/13/21													
94	Install Flooring - Vinyl	3 days	Fri 7/2/21	Tue 7/6/21	87	Flooring contractor											
95	Install Flooring - 1st floor	2 days	Wed 7/7/21	Thu 7/8/21	94	Flooring contractor											
96	Install Flooring - 2nd floor	2 days	Fri 7/9/21	Mon 7/12/21	95	Flooring contractor											
97	Install appliances	1 day	Tue 7/13/21	Tue 7/13/21	96	Appliance contractor											
98	Landscaping and Grounds Work	7 days	Thu 6/17/21	Fri 6/25/21	74												
99	Pour concrete driveway and si	2 days	Fri 6/18/21	Mon 6/21/21	77	Concrete contractor											


Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			

ID	Task Name	Duration	Start	Finish	Predecessors	Resource Names	Oct '20					Nov '20				
							13	20	27	4	11	18	25	1	8	15
100	Sod and complete plantings - f	2 days	Tue 6/22/21	Wed 6/23/21	99	Landscape contractor										
101	Sod and complete plantings - b	1 day	Thu 6/24/21	Thu 6/24/21	100	Landscape contractor										
102	65 Street Trees Inspection	1 day	Fri 6/25/21	Fri 6/25/21	101	Inspector										
103	66 Final Erosion Control Inspec	1 day	Fri 6/25/21	Fri 6/25/21	101	Inspector										
104	Final Acceptance	27 days	Thu 7/1/21	Fri 8/6/21												
105	21 Final inspection for certifica	1 day	Wed 7/14/21	Wed 7/14/21	97	Inspector										
106	Cleanup for occupancy	1 day	Thu 7/15/21	Thu 7/15/21	105	Maid service										
107	Perform final walk-through ins	1 day	Fri 7/16/21	Fri 7/16/21	106	Owner										
108	Complete punch list items	14 days	Mon 7/19/21	Thu 8/5/21	107	General contractor										
109	Final Walkthrough With buyer	1 day	Fri 8/6/21	Fri 8/6/21	108	General contractor										




Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			


Dec '20 22 29 6 13 20 27 Jan '21 3 10 17 24 Feb '21 31 7 14 21 Mar '21 28 7 14 21 Apr '21 28 4 11 18 25 May '21 2 9 16 23 Jun '21 30 6 13 20 Jul '21 27 4 11 18 25 Aug '21 1 8 15 22 29 Sep




Project: 100 Headrick Road, Ho
Date: Wed 12/16/20

Task		Inactive Task		Manual Summary Rollup		External Milestone	
Split		Inactive Milestone		Manual Summary		Deadline	
Milestone		Inactive Summary		Start-only		Progress	
Summary		Manual Task		Finish-only		Manual Progress	
Project Summary		Duration-only		External Tasks			







Project: 100 Headrick Road, Ho Date: Wed 12/16/20	Task		Inactive Task		Manual Summary Rollup		External Milestone	
	Split		Inactive Milestone		Manual Summary		Deadline	
	Milestone		Inactive Summary		Start-only		Progress	
	Summary		Manual Task		Finish-only		Manual Progress	
	Project Summary		Duration-only		External Tasks			