




Commissioning of the High Current ERL Injector at Cornell

Florian Loehl
for the Cornell ERL team





ERL – Injector Prototype



Design parameter:

Nominal bunch charge

77 pC

Bunch repetition rate

1.3 GHz

Beam power

up to 550 kW

Nominal gun voltage

500 kV

SC linac beam energy gain

5 to 15 MeV

Beam current

100 mA at 5 MeV

33 mA at 15 MeV

Bunch length

0.6 mm (rms)


Transverse emittance

< 1 mm-mrad





Initial thermal emittance measurements



Measured normalized beam emittance
at \sim fC bunch charge (5 MeV):

0.2 to 0.4 mm mrad
(in both planes)

Good agreement with predictions from
thermal limit at cathode and utilized laser
spot size.

→ Next step: optimizing injector for 77 pC operation



- Implemented fast (\sim 5 s), “single button” measurement
- Will be used for parametric optimization of the injector






Comparison of beam measurements with simulations

Beam properties at the cathode



Fixed slits phase space measurements

- Corrector coils for beam scanning
- 10 to 20 micron precision slits
- 1 kW beam power handling




Phase space measured after the beam was transported through the accelerator.

Good agreement with theory gives confidence that the very small simulated emittances can be achieved.

From Phys. Rev. ST-AB 11, 100703 (2008)




Implemented global beam position feedback which uses all BPMs, corrector, and dipole magnets.







Implemented global beam position feedback which uses all BPMs, corrector, and dipole magnets.






Transverse Deflecting Cavity

- Number of cavities 1
- Max transverse kick voltage 200 kV
- Max RF power 3.8 kW
- Average power 200 W
- Pulse duration 60 μ s
- Max rep. rate 1 kHz





Initial high current run




- Achieved maximum current is about 9 mA
 - Main limitations:
 - Gun high voltage instabilities
 - Laser amplitude / position instabilities
- Work on solving the stability issues is in progress








Strange beam response of 250 kV beam

Steering the beam differently through the cryomodules
changed the beam shape (no RF field in cavities)





Strange beam response







Localizing stray fields in the cryomodule with DC coupler-kicks

Generation of electrical DC fields in the coupler regions of the SRF cavities

dipole-like field



quadrupole-like field





Localizing stray fields in the cryomodule with DC coupler-kicks

dipole-like coupler kick





deflection of the beam after the cryomodule
due to the coupler field





Localizing stray fields in the cryomodule with DC coupler-kicks

quadrupole-like coupler kick




deflection of the beam after the cryomodule
due to the coupler field









Localizing stray fields in the cryomodule with DC coupler-kicks

Determined the origin of the stray fields:






In-situ demagnetization





Warm up and in-situ
demagnetization removed
stray fields





Stray fields


- Stray fields reappeared after a beam loss in the cryomodule
 - Coupler conditioning changed the stray fields
- Charging up of HOM absorbers!







HOM absorbers



Total # loads	3 @ 78mm + 3 @ 106mm
Power per load	26 W (200 W max)
HOM frequency range	1.4 – 100 GHz
Operating temperature	80 K
Coolant	He Gas
RF absorbing tiles	TT2, Co2Z, Ceralloy



Antennas to study HOM spectrum



Charging up of HOM absorbers



Low conductivity of HOM absorber tiles: Can hold charge for many days / weeks!

Worst offender: **Ceramic 137Zr10**, followed by ferrite Co2Z and TT2


Small beam loss charged up absorber tiles -> kV **electric** fields at beam position!



Removing inner tiles


Consequence of low resistivities of absorber materials:

- Completely removed ceramic $^{137}\text{Zr}10$
 - Tried gold coating of TTE absorbers but coating may fall off
- Removed all tiles from the inside of the HOM absorber



Found one loose tile during cryomodule disassembly

- Thermal stress tests confirmed this problem
- Solved by cutting stress relief slots in the tiles






Power limitations with modified HOM absorbers

Blue: inside and outside ferrites

Red: outside ferrites only






Power limitations with modified HOM absorbers

Power loss in the metal walls


Blue: inside and outside ferrites

Red: outside ferrites only





Cavity Quality Factors



Had difficulties with low cavity quality factors

- Q factors degraded over time
→ Q disease?

During the rebuild, all cavities were high pressure rinsed
→ Q restored to 1.6×10^{10} at 1.8 K
→ no Q disease
→ cavities were possibly contaminated with particles?





Current status of the injector cryomodule

- Cryomodule is rebuilt and back in the injector
 - Cooled down to 4 K
 - 2 K cool-down planned for next Monday
- Ready to see beam in the next weeks!





Charging up of the HOM absorbers caused difficulties during the first commissioning

- Rebuild cryomodule during the last 6 months and removed problematic absorbers

Still, many critical systems could be successfully commissioned and prepared.

- Measured thermal beam emittance as expected
- Could increase beam current to 9 mA for short times (limitations understood and being worked on)

First beam operation after cryomodule rebuilt expected end of March

- Emittance optimization at 77 pC
- Work on high current beam operation

