

# **Dimensional Control Survey Proposal**

Ver. Date : 2017.06.15

# Our Business

## World's #1 Dimensional Accuracy Control Technology

### Accurate


- +/- 1mm (1/24") Accuracy
- 0 failures in First Time Fit

### Fast

- 50% faster than other leading technologies

### Know How

- 10 years of consulting in Dimensional Control and Dimensional Control ONLY!



### Onshore Plant

Modular Construction  
Single Weld Hook Up  
After Installation Check  
Erection Simulation

### Offshore Plant & Shipbuilding

Prefabrication Check  
As built vs Design comparison  
As built vs As built clash detection



### Buildings & Steel Structures

Revamp  
Retrofit  
Renovation

# Why is Dimensional Control so important?

Small accuracy errors accumulated during pre-fabrication lead to huge problems during installation

Re-work on module installation stage increases danger of industrial accidents, and cause decline of work efficiency




Cutting

Sub  
- Assembly

Assembly

Transport

Installation




**Increases  
cost,  
duration,  
and safety  
hazard**

**Objective of Dimensional Control : First Time Fit**

# Dimensional Accuracy Control in Modular Construction

Most measurements are taken without stopping work process

## Construction Phase



Pre-Fabrication


## What we offer

### Dimension Check

- Design vs build control to minimize errors in pre-fab

## How Fast we do it

Measured while being built  
1~3 Checks per module  
2~3 hours per check




Assembled Work

### \* Clash Detection

- Pipe Spool clash check using as built vs as built clash check simulation before transportation

Measured while being built  
1 day : Pipe Rack (~80 spools)  
1~3days : 4~500 Ton  
1 week : 2,000 Ton+




After Transport

### Deformation Check

- Check for deformation after transport

Measured before installation  
1~2 Hours



After Installation

### Installed Module Check





- Check proper installation of the module to prepare for next installation

Measured while positioning module  
1~2 Hours

# Dimensional Accuracy Control in Modular Construction

**Pre-Fabrication : Minimize errors during assembly quickly**

Average Error Occurrence : 16~37%




Solved by

**1 ~ 3 Measurements  
per module**


**2~3 hours per  
measurement**

**Errors are caught  
and corrected  
without interruption**


**How we do it**



Measured while being built



Simulation




Instant Comparison Report

# Dimensional Accuracy Control in Modular Construction

**Detect & Fix errors before transporting the module**

Around 70% mis-alignments occur during installation leading to increased safety hazard & cost



Misalignment



Onsite modification




**1 measurement**

**1 day per measurement**

**Errors are caught and corrected without interruption**

## How we do it



# Dimensional Accuracy Control in Modular Construction

## Deformation check after transport

20% of modules are deformed during transportation



Damages incurred from Lifting and Transporting




**1 Measurement**

**1~2 hours per measurement**

**Stand by time : 2hrs**

## How we do it






# Dimensional Accuracy Control in Modular Construction

## Installation Check

Without Dimensional Accuracy Control  
angle error, positioning error occurs  
99% of time



Wrong Angle, Tilting to one side




**1 Measurement**

**1~2 hours per  
measurement**

**Stand by time: 2 hrs**

## How we do it

Measure and check Angle, Vertical Position, and Level  
while setting the module






# Samin's Core Competency : Accuracy, Speed, Knowhow

10+ years of technological advancement in Dimensional Control

More than 50% Faster






**Single Weld Hook UP  
Realistic View**

# SWHU in Modular Construction


**First Time Fit on site is achieved through Single Weld Hook Up (SWHU)**

- SWHU : Conjoining pipes without using Pup piece and only welding in a single area

**Without Dimensional Control**




**With Dimensional Control**



# Reality in today's SWHU


Theoretically, SWHU should reduce cost and resources by 50% or more

**Reality : Construction companies spend millions of dollars extra to implement SWHU do to lack of experience and right tools**  
**(No single company achieved 100% SWHU as of today)**




# Reality in today's SWHU

What companies are doing :  
Mix of Stick Built, 'Pup Piece', and SWHU (20~50%)



Creating 'Reserve'  
to make room for  
mis-alignment



# SWHU in Samin Dimensional Control - Benefit

## Case without Samin Dimensional Control


Company A spent \$4million on design change and \$4million+ more extra installing the modules

PKG	STEEL STRUCTURE		PIPING		TOTAL
	Pre-assemble	Modularized	Pre-assemble	Modularized	
PKG A	900 Ton 27 EA	5,800 Ton 61 EA	1,500 Ton	5,800 Ton	14,000 Ton
PKG B	4,000 Ton 34 EA	3,700 Ton 89 EA	2,300Ton	1,900 Ton	11,900 Ton
PKG C	400 Ton 4 EA	2,000 Ton 22 EA	-	1,600 Ton	4,000 Ton
TOTAL	5,300 Ton	11,500 Ton	3,800 Ton	9,300 Ton	29,900 Ton


## With Samin Dimensional Control

Design change is minimized, and can apply SWHU on most installations (80%+) **at fraction of the cost**


Structure Dimension Control



Module Dimension Control



Pipe Dimension Control



Simulation between modules






## **References & Case Studies**








# Project Reference

Project		Year	Work Scope	RM
S-Oil RUC Project		2016~ 2017	<ul style="list-style-type: none"> <li>3rd Party Dimensional Inspector of Project Owner</li> <li>HS FCC Vessel Dimensional Inspection</li> <li>HS FCC Vessel Installation Simulation &amp; Inspection</li> </ul>	<ul style="list-style-type: none"> <li>Scanner : Leica C10, P30</li> <li>Total Station : Leica MS 50</li> <li>Pre Process : Cyclone</li> <li>Inspection &amp; Simulation S/W : EcoPASS, EcoInspection(Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>
LNG Plant Project		2015	<ul style="list-style-type: none"> <li>LNG Plant Module and Vessel Dimensional Error Analysis</li> <li>Dimension Check for 600ton, 2000ton, Column</li> <li>Module and Vessel Installation Simulation</li> </ul>	<ul style="list-style-type: none"> <li>Scanner: Leica P20</li> <li>Data Process : Cyclone</li> <li>Analysis &amp; Simulation S/W : EcoPASS, EcoInspection(Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>
CBDC Plant Project		2013	<ul style="list-style-type: none"> <li>Large Column (External/Internal) Dimensional Inspection</li> <li>Flatness of Skid Base, Nozzle Orientation, Straightness, Roundness &amp; Internal Tray Dimensional Accuracy Comparing 3D Design and 3D Laser Scanning Data</li> </ul>	<ul style="list-style-type: none"> <li>Scanner : Leica P20</li> <li>Data Process : Cyclone</li> <li>Inspection S/W : EcoInspection (Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>
Gorgon LNG Plant Project		2012~ 2013	<ul style="list-style-type: none"> <li>Providing 3D Dimensional Control Solutions and Laser Scanner</li> <li>Technical Training for Shop and Site Survey using Laser Scanner and Total Station</li> <li>Technical Training for Dimensional Error Analysis using Software Solution</li> </ul>	<ul style="list-style-type: none"> <li>Scanner: Z+F IMAGER 5010C</li> <li>Total Station : SOKKIA NET</li> <li>Inspection S/W : EcoInspection, EcoBLOCK, EcoOTS(Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>
Semi-Sub Project		2011~ 2012	<ul style="list-style-type: none"> <li>Technical Training for Preparing Dimensional Control Procedure &amp; Field Application of 3D Dimensional Control Solution</li> <li>Providing 3D Dimensional Control Solution</li> </ul>	<ul style="list-style-type: none"> <li>Total Station : SOKKIA NET</li> <li>Inspection S/W : EcoBLOCK (Specialized Dimensional Control S/W dev. by SAMIN)</li> </ul>

# Project Reference


Project		Year	Work Scope	RM
Prelude FLNG Project		2014~ 2015	<ul style="list-style-type: none"> <li>Clash Check : Topside Module integration to hull</li> <li>Project Range : 12 Modules + 1 Flare Tower</li> <li>Report to Owner &amp; Construction Company : Clash, Dimensional Error, Tight Gap</li> </ul>	<ul style="list-style-type: none"> <li>Scanner : Leica C10</li> <li>Data Process : Cyclone</li> <li>Clash Check S/W : EcoPASS (Specialized Dimensional Control S/W dev. by SAMIN)</li> </ul>
Q-204 FPSO Project		2013	<ul style="list-style-type: none"> <li>Lower Turret Installation Simulation</li> <li>Gap and Clash Check When Lower Turret is located to the certain critical elevation. (Hull : 3 Elevations/ Lower Turret : 3 Elevations)</li> <li>Report to Owner &amp; Construction Company</li> </ul>	<ul style="list-style-type: none"> <li>Scanner: Z+F IMAGER 5010C</li> <li>Data Process : Cyclone</li> <li>Simulation S/W : EcoPASS (Specialized Dimensional Control S/W dev. by SAMIN)</li> </ul>
Spar Hull Project		2016	<ul style="list-style-type: none"> <li>Spar Hull Dimensional Error Analysis and Erection Simulation</li> <li>50m Diameter sized Cylinder Structures Dimension Check and Structure Alignment Check</li> </ul>	<ul style="list-style-type: none"> <li>Scanner : Leica P40</li> <li>Data Process : Cyclone</li> <li>Inspection S/W : EcoPass (Specialized Dimensional Control S/W dev. by SAMIN)</li> </ul>
Jackup Project		2013~ 2014	<ul style="list-style-type: none"> <li>Technical Training for Preparing Dimensional Control Procedure &amp; Field Application of 3D Dimensional Control Solution</li> <li>Providing 3D Dimensional Control Solution</li> </ul>	<ul style="list-style-type: none"> <li>Total Station : SOKKIA NET</li> <li>Inspection S/W : EcoBLOCK (Specialized Dimensional Control S/W dev. by SAMIN)</li> </ul>
Shanghai Tower		2013~ 2014	<ul style="list-style-type: none"> <li>Utilizing 3D Dimensional control software for Shanghai landmark dimensional quality control</li> </ul>	<ul style="list-style-type: none"> <li>Total Station : SOKKIA NET</li> <li>Inspection S/W : EcoBLOCK (Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>

# Project Reference

Project	Year	Work Scope	RM
SAMSUNG Display Factory Modeling 	2016	<ul style="list-style-type: none"> <li>As-Built 3D Modeling Project</li> <li>Factory Scale : 310×110×5m 7stories LED factory</li> <li>15 Years old factory ; Less factory drawing information.</li> <li>Compare the existing drawing and present state</li> <li>Verify the area need to be replaced and added.</li> </ul>	<ul style="list-style-type: none"> <li>Scanner : Leica C10, P30</li> <li>Pre Process &amp; Modeling : Cyclone</li> </ul>
Heavy Structure Inspection (Huisman-Yard) 	2016~2017	<ul style="list-style-type: none"> <li>Dimensional Inspection for mega sized crane equipment. (HEEREMA 10,000T Crane, Boskalis 300 OT offshore platform truster etc.)</li> </ul>	<ul style="list-style-type: none"> <li>Total Station</li> <li>Inspection S/W : EcoMES, EcoBlock (Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>
Building Inspection 	2014	<ul style="list-style-type: none"> <li>Dimensional Inspection for irregular shaped building comparing Design and 3D Scanning Data</li> <li>Dimension check for columns and roof</li> <li>Providing Inspection Report.</li> </ul>	<ul style="list-style-type: none"> <li>Scanner : Leica C10</li> <li>Data Process : Cyclone</li> <li>Inspection S/W : EcoPASS (Specialized Dimensional Control S/W dev. by SAMIN)</li> </ul>
Macau Hotel Tower 	2014~2015	<ul style="list-style-type: none"> <li>Providing 3D Dimensional control inspection service for building module dimensional error analysis</li> </ul>	<ul style="list-style-type: none"> <li>Total Station : SOKKIA NET</li> <li>Inspection S/W : EcoBLOCK (Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>
HuTong Bridge 	2015~2016	<ul style="list-style-type: none"> <li>Utilizing 3D Dimensional control software for China railway bridge dimensional quality control</li> </ul>	<ul style="list-style-type: none"> <li>Total Station : SOKKIA NET</li> <li>Inspection S/W : EcoBLOCK (Specialized Dimensional Control s/w dev. by SAMIN)</li> </ul>

# Offshore Plant - FLNG


- Project Summary : The World Largest Ship – FLNG Topside Module Clash Check Simulation
- Project Purpose :
  - Spools, pipes, a lot of outfitting on module are temporarily placed, also there are a lot of scaffolding and cable support, so it is not easy to forecast the expected location of clash after the erection.
  - Because of safety reason it is not allow anybody to enter and do any modification work in PE place.
  - All modification works should be done in fabrication location after the modules is brought back if any clash happens.





# Offshore Plant - FLNG

## 1. Original Topside Module Clash Detection Process

### ① Clash Check



Clash check using 3D design model




Design

Find difference



On-site



Check the clashes for different parts using tape

### ② Erection & Remove Clash parts

Cost



Erection



Remove clash parts




Clash ??





# Offshore Plant - FLNG

2. Samin produced accurate Clash Detection simulation and report within **5 days per module**  
(Competitor's estimate was 3 weeks per module)




- Gathered accurate measurement using 3D scan
- Used Samin solution to prepare accurate simulation data
- Shared the result of simulation with production team.
- Determined where to remove and modify structure parts
- **No interruption during fabrication**



# Offshore Plant - FLNG

## 3. Conclusion

<Report>



- Achieved 0 clash in all 13 modules
- Module erection time was reduced from 12 hours to average 3hrs (The shortest 40mins)
- Saved millions of dollars (ROI of 2,000%)



# Competitor Comparison

Some companies are proud of...

- Spending 8 days two person team for measuring 800 scan positions
- Spending 21 days 1 person scan positioning registration
- To produce only the Registered point cloud and TruView

For comparing 'design of gas plant' with 'to be integrated existing structure'



## SURVEYING EQUIPMENT

Scanner Riegl VZ-400, Leica  
TCRA 1101 plus Total Station




## TOTAL TIME SPENT

8 days two person team over  
800 scanpositions  
21 days 1 person scan positions  
registration



## FINAL PRODUCT

Registered point cloud and  
TruViews



If they came to Samin, they would've had "Clash Simulation" result  
within **11** days!

One more thing...

## **Samin Price Competitiveness**

Costs **40%** less per day/person  
than F company

Costs **10%** less per day/person  
than A Company


**More than 50%** Faster output  
than competitors

# Appendix




- Company History**
- How Dimensional Control is conducted in Korea**
- Process Flow**

# History



# How Dimensional Control is conducted in Korea


- Conduct dimensional accuracy inspection of all block/module at the end of each stage.
- Defects found are not released to next phase.
- Korean heavy industries companies sporadically conduct dimensional accuracy inspection.
- Dimensional accuracy control policy enabled Korean heavy industries companies to build high quality of mega sized blocks and modules.




# 3D Dimensional Control Management Method

## 1. Prepare Dimensional Control plan for each module fabrication stage


- Select proper management methodology, device, and software for each stage and module type.




<Small size assembly – Manual Check>




<Mid to Large Size Assembly – 3D measurement>  
(Length, Vertical degree, Level, Deformation check)



<Erection/Installation- 3D measurement>  
(Datum point based erection/installation simulation S/W)



<Round and complicated structure>  
(3D laser scanning Dimensional Control S/W)




<Set datum points and direction of final module installation>



# 3D Dimensional Control Management Method

## 2. Acquisition of dimensional data of fabricated modules

- Determine the equipment type and method based on structure type and management point



Piping Module  
-3D Laser Scanning  
(Acquire central focal point)





Focal Point



Large Column  
-3D Laser Scanning



Pipe Rack  
-3D Laser Scanning  
(for Pipe Rack Alignment Check)



Module  
-3D precision measurement  
using Total Station

Measurement Point





3D measurement software 소프트웨어  
(Instant access to measured data using  
Mobile and PDA)


# 3D Dimensional Control Management Method

## 3. Measurement Analysis


- Verify As-Built measurement against design and tolerance




Support Ring Angle & Flatness




3D As-Built Measurement- Nozzle Orientation  
(3D Laser Scanning Data)



Module 3D measurement & Reporting  
(3D Design vs. 3D Measurement)



Column 3D Measurement  
(3D Design vs. 3D Laser Scanning)








Tubler As-Built Measurement Verification  
(3D Measurement)

# 3D Dimensional Control Management Method

## 4. Module Erection/Installation Simulation

- Clash detection simulation using gathered data
- Plan best path and location for module installation/erection
- Modify any clash points before installation/erection
- Apply weight offset value during operation as needed




First  
Time  
Fit




# 3D Dimensional Control Management Method

## 5. Dimensional Control during Module Installation/Erection

- Simulation based module installation/erection check
- Verify the position and setting of module during installation/erection



<Pipe rack Erection Check>




<Vessel Installation Check>


# 3D Dimensional Control Management Method

## 6. Module As Built Data Analysis and Management

- Check metal expansion/shrinkage after welding using phase based measurement data
- Analyze measured data against tolerance level
- Periodic deformation check during operation and transport
- Utilize data gathered during maintenance, revamp, and retrofit




<Statistical analysis of phase based measurement >



<As-Built data utilization >

# Utilize SAMIN Software Solution to Process Flow



# Utilize SAMIN Software Solution to Process Flow

**Design vs. Production**




**Laser Scanner**



**EcoInspection**

**Production vs. Production**




**EcoPASS**




**Total Station**

**EcoMES**



**EcoBLOCK**



**EcoOTS**



# Q&A

Thank you.

삼인정보시스템(주)  
SAMIN INFORMATION SYSTEM CO.,LTD.

Website : [www.saminis.com](http://www.saminis.com)

YouTube : [www.youtube.com/saminisen](http://www.youtube.com/saminisen)

Email : [jskim@saminis.com](mailto:jskim@saminis.com)