Ford Motor Company Advanced Product Quality Planning (APQP) Status Reporting Guideline

Any questions regarding this document, or the content therein, should be directed to:

VO Quality Office

(313) 248-6538

This document is located on the Ford Intranet at:

http://www.dearborn2.ford.com/apqpcntr

This Guideline is published by Ford Motor Company, Quality Office Copyright © 2001 Ford Motor Company.

All rights reserved

Foreword

Ford Motor Company launched an Advanced Product Quality Planning Status Reporting Guideline (APQP) Fast Start Initiative in December 1994. A crossfunctional APQP team formed to review the existing FAO Procedures and target best practices. The 1994 version of this document was created at that time, to be in line with the AIAG Advanced Product Quality Planning and Control Plan Manual.

Since that time, the external suppliers to Ford Motor Company, and internal suppliers within Ford have used the FAO APQP Status Reporting Guideline to monitor their own systems with regard to APQP.

With the experience that has been acquired since 1994, it has become necessary to update this manual to reflect current practices, and successes. In addition, the Ford Product Development System (FPDS) has become the documented system for the Product Development processes within Ford (replacing World Class Timing).

A cross-functional team was formed in 1999/2000 to review the 1994 FAO APQP manual and practices, and this guideline has been updated to reflect generic timing with respect to the FPDS system. It also contains references (at the time of publishing) to the FPDS Process Sheets. All of this is to clarify further the appropriateness of the APQP process, and its direct tie to the existing systems/process Ford currently has in place.

Furthermore, it is intended that the updated APQP process and FPDS timing information will assist the external supply base in understanding the differences between their own timing requirements, and those which need to be met by the entire Vehicle Program in the delivery of a new vehicle.

This Guideline documents the Ford APQP evaluation and status reporting process and is intended to be used for 2004 MY Programs and beyond. This Guideline does not replace the AIAG Advanced Product Quality Planning and Control Plan Reference Manual as the basis for quality planning.


Table of Contents

| FOREWORD | 2 |
|-------------------------------------------------------------------------------------|----------|
| | _ |
| APQP FUNDAMENTALS | |
| APQP Process Flow Map | |
| Fundamentals of the APQP Process | <i>I</i> |
| APQP REPORTING PROCESS | 10 |
| APQP Status Reporting Process Flow Chart | |
| APQP Status Report | |
| APQP Status Report Form | |
| Filling Out the Status Report Form | |
| Quality of Event Checklists | |
| Risk Assessment | 15 |
| APQP TIMING | 17 |
| Ford / Supplier Systems "V" Model | |
| APQP Generic Program Timing Gantt Chart | |
| 71 Qi Conono i rogiam riiming Cana Chara | |
| APQP ELEMENTS | |
| Sourcing Decision | |
| Customer Input Requirements | |
| Craftsmanship | |
| Design Failure Mode and Effects Analysis (DFMEA) | |
| Design / Manufacturing Reviews | |
| Design Verification Plan & Report (DVP&R) | |
| Sub-Contractor APQP Status | |
| Facilities / Tools / Gauges | |
| Prototype Build Control Plan | |
| Prototype Builds | |
| Drawings & Specifications | |
| Team Feasibility Commitment | |
| Manufacturing Process Flow | |
| Process Failure Mode and Effects Analysis (PFMEA) | |
| Measurement System Evaluation | |
| Pre-Launch Control Plan | |
| Operator Process Instructions | |
| Packaging Specifications | |
| Production Trial Run | |
| Production Control PlanPreliminary Process Capability | |
| | |
| Production Validation TestingPart Submission Warrant (PSW) | |
| Part Submission Warrant (PSW) | |
| APPENDIX SECTION | 52 |
| ADDENDIV A. ADOD DOLES & DESPONSIBILITIES | <i>-</i> |
| APPENDIX A: APQP ROLES & RESPONSIBILITIES Powertrain Roles and Responsibilities Ma | |
| r uwertiain rules and responsibilities ivia | UIX54 |

| Pow | vertrain Roles and Responsibilities Matrix | 55 |
|------------------|--------------------------------------------|----|
| Powertra | ain Program Review Process') | 56 |
| (PTPRP STA Ro | ')les & Responsibilities | 56 |
| OTATIO | too a responsibilities | |
| EXTERNAL SUP | PPLIERS | 67 |
| | | |
| APPENDIX B: | RELATED FORMS | 69 |
| | | |
| APPENDIX C: | GLOSSARY OF TERMS | 72 |
| ADDENDLY D. | REFERENCES AND WEBSITES | 70 |
| APPENDIX D: | REFERENCES AND WEBSITES | /9 |
| REFERENCES 8 | k WEB SITES | 80 |
| | ~ ··== | |

APQP Fundamentals

APQP Process Flow Map



Advanced Product Quality Planning Release Level: 3.0 Ford APQP Guideline (copyright ©, 2001)

Fundamentals of the APQP Process

Advanced Product Quality Planning (APQP)

Advanced Product Quality Planning (APQP) is a structured method for defining and executing the actions necessary to ensure a product satisfies the customer. APQP is program and supplier-led and is required of all system, subsystem and component manufacturing locations. This includes both internal and external suppliers to Ford.

The Goal of APQP

The goal of APQP is to facilitate communication between all persons and activities involved in a program and ensure that all required steps are completed on time, with a **high quality-of-event**, at acceptable cost and quality levels.

The Purpose of APQP

The purpose of this status reporting guideline is to establish:

- Common APQP expectations for the internal and external suppliers to Ford Motor Company
- Common APQP process metrics
- A common program status reporting format
- Roles and responsibilities for APQP elements
- A better understanding of how the APQP elements relate to the Ford Product Development System (FPDS), specific FPDS milestones, and their timing

The Approach of APQP

This status reporting guideline describes 23 key APQP disciplines. Ford Motor Company expectations are defined for these key disciplines in definitions, and detailed checklists. The status for these disciplines is summarized using metrics described in the Reporting section.

This status reporting guideline is written from a supplier standpoint. A supplier is an internal or external supplier of materials, components, subsystems, systems, designs or processes that will be delivered to a customer. A customer is the recipient of the supplier's product or process. Besides customers, every supplier will have subcontractors. A subcontractor is the provider of material or parts to a supplier.

The Applicability of APQP

APQP status reporting is a requirement of all internal and external suppliers to Ford (including Ford Product Development). APQP must be done for new programs/parts and major part changes as appropriate. In addition, Product Development Teams are to monitor the status of internal and external engineering and process development disciplines and assess the "Quality-of-Event" as well as the timing and completion of each of the 23 elements.

Teams

The first step in the Advanced Product Quality Planning Process is to assign responsibility to a cross-functional team. Effective product quality planning requires the involvement from all areas within a corporation. The team includes representatives from engineering, manufacturing, material control, purchasing, quality, sales, field service, subcontractors, and customers as appropriate.

Elements

This Status Reporting Guideline describes 23 key APQP disciplines, identified as Ford APQP elements. Please note that there is a slight difference in the 23 elements in this updated version. These elements, when summarized and reported, communicate the status of different levels of a program.

Of the 23 Ford APQP elements, 19 are requirements of the AIAG Advanced Product Quality Planning and Control Plan manual. The four additional elements meet unique Ford requirements for APQP status reporting and communication between supplier and customer.

The 19 industry standard elements are:

| Design I | FMEA |
|----------------------------|------|
|----------------------------|------|

- Design Verification Plan & Report
- Prototype Build Control Plan
- Manufacturing Process Flow Chart
- Process FMEA
- Pre-Launch Control Plan
- Operation Process Instructions
- Production Control Plan
- Design & Mfg. Review(s)
- Facilities / Tools / Gauges

- Prototype Builds
- Drawings and Specifications
- Team Feasibility
 Commitment
- Measurement Systems Evaluation
- Packaging Specifications
- Production Trial Run
- Preliminary Process Capability Study
- Production Validation Testing
- Production Part Approval (PSW)

The four Ford unique elements are:

- Sourcing Decision
- Customer Input Requirements
- Subcontractor APQP Status
- Craftsmanship (note: new this release)

Elements (cont.)

Another difference from the original status reporting guideline, is the combination of the two elements for "Production Part Approval (PSW)" and "PSW part delivery at MRD" into one element called:

Part Submission Warrant (PSW)

APQP Flow

The chart on the page 6 of this section is an overall summary of the APQP process. It is intended to show that APQP is <u>NOT</u> just a feed forward process, but it also includes feeding information back, updating documents in an iterative fashion, and using information and lessons learned from a program for future programs.

The APQP Process includes five main functions:

- 1. Planning of the APQP elements
- 2. Execution of the APQP elements
- 3. Monitoring the "Quality-of-Event" of the execution of the elements, as well as the timing, by the team in-between FPDS milestones
- 4. Issues Resolution
- 5. Status Reporting (minimum at FPDS milestones)

Roles

The roles matrix in Appendix A defines the lead and support roles for Vehicle Operations and Product Development. Under the VO/PD matrix, the APQP Status Reporting is as follows: Vehicle Operations Program Launch Manager reports the status on VO Internal Suppliers, and Product Development Team Leaders will report on the D & R Engineers' status. Powertrain will report both Internal & External P/T Suppliers (see Powertrain R & R matrix for further detail). STA will report status on External Suppliers

This Roles and Responsibilities matrix can be used to derive other tables specific to each organization's requirements for element responsibility and status reporting.


Responsibilities

Responsibilities for the activities are identified in the checklist, and references to FPDS process sheets are in the element descriptions. A Quality-of-Event checklist is provided for each element to assist in understanding the Expectations for each element. Rating history, FPDS timing requirements, and Expectations due at certain points in the program are described.

APQP Reporting Process

APQP Status Reporting Process Flow Chart

APQP Status Reporting Flow Chart



Advanced Product Quality Planning Release Level: 3.0 Ford APQP Guideline (copyright ©, 2001)

APQP Status Report

The Ford APQP Status Report summarizes the program status using the 23 Ford APQP elements. It summarizes the information and provides an assessment at the component/subsystem level, the system/organization level(s), and finally the program level. The individual issues at each level are to be documented and tracked, as well as raised to management for assistance in solving/closing if they cannot be handled at the working level.

Please note the different levels of reporting, and the summarizing process as shown on page 11.

- Submit the Status Report to the customer at all major program reviews (e.g. FPDS Milestones).
- Customers or suppliers shall conduct more frequent status reviews as needed.
- The customer shall provide a list of all scheduled program status review dates to the supplier.
- Submit supporting documentation upon customer request.

The subsystem team completes the status report for its product, with component supplier status summarized on the Subcontractor APQP status line. The subsystem teams submit the report to their customer, the system team.

The system/organization team will then complete the status report for their product, with their subsystem supplier status summarized onto the Subcontractor APQP status line. The system teams submit the data to their customer, the vehicle team.

Ratings and Assessment

G/Y/R Status

Green-Yellow-Red status communicates the progress toward the successful completion of an APQP Element by the program need date. Program need date is the last possible date an element can be completed and not adversely affect <u>quality</u> or <u>timing</u> of the program. The "GYR Status" column of the report shows the assessment for each element.

Definitions/Risk factors for Green, Yellow, and Red are listed in the table below.

| | DEFINITIONS | | | | | | | | |
|----------|------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|--|--|--|
| | Risk/Status Assessment | | | | | | | | |
| Risk | Risk Color Definition | | | | | | | | |
| High | Red | Target dates and/or deliverables are at risk. A recovery work plan is not available and/or implemented, or the work plan does not achieve program targets. | | | | | | | |
| Moderate | Yellow | Target dates and/or deliverables are at risk, but a resourced recovery work plan has been developed to achieve program targets, and has been approved by the appropriate Management Team. | | | | | | | |
| None | Green | Target dates and deliverables are on track and meeting objectives. | | | | | | | |

APQP Status Report Form

| Ford Met | or Company, |
|----------|-------------|
|----------|-------------|

Advanced Product Quality Planning Status Report

| | Supplier/Org: | ① | | | Pro | ogram: | | (5) | | Part | Name: | | (9) | |
|------------------|---------------------|--------------------------------------|-----------|-----------------------------------------|---------|--------------------------|--------------|---------------------------|-----------|-----------|------------|--------------|----------------|-----------|
| Location: | | | | - | Mode | el Year | | <u>6</u> | | Part N | lumber | 10 | | |
| Supplier Code: 3 | | | FP | DS Mile | estone. | (5) (6) (7) (8) | | | Notice | l evel | <u> </u> | | | |
| | ontact Name/Tel: | | | • • • • • • • • • • • • • • • • • • • • | Revie | w Date: | | <u> </u> | | Use | r Plant | 10 | | |
| - | | | | • | 110110 | Date. | | | | | i i idiit. | | - | |
| | | FPDS MILESTONE | ∠SI> | <sc></sc> | ∠PH> | - ΡΔ> | (ST) | <pr></pr> | (CP) | <cc></cc> | <lr></lr> | <1.S> | (.11) | <fs></fs> |
| APC | QP ELEMENT | | | mm/dd/yy | | | | | | | mm/dd/yy | | | mm/dd/y |
| | Sourcing Decision |) | 13 | | | | ,,, | | ,,, | | | | | |
| | Customer Input R | | | | | | | | | | | | | |
| | Craftsmanship | equiremente | 1 | | | | | | | | | | | |
| | Design FMEA | | | | | | | | | | | | | |
| | Design/Manufactu | ırina Review(s) | i e | | | | | | | | | | | |
| | Design Verification | | 1 | | | | | | | | | | | |
| | Subcontractor AP | | | | | | | | | | | | | |
| | Facilities, Tools & | | | | | | | | | | | | | |
| | Prototype Build C | | | | | | | | | | | | | |
| | Prototype Build(s) | | | | | | | | | | | | | |
| 11. | Drawings & Speci | fications | | | | | | | | | | | | |
| 12. | Team Feasibility (| Commitment | | | | | | | | | | | | |
| 13. | Manufacturing Pro | ocess Flowchart | | | | | | | | | | | | |
| 14. | Process FMEA | | | | | | | | | | | | | |
| 15. | Measurement Sys | stems Evaluation | | | | | | | | | | | | |
| 16. | Pre-Launch Contr | ol Plan | | | | | | | | | | | | |
| 17. | Operator Process | Instructions | | | | | | | | | | | | |
| 18. | Packaging Specifi | ications | <u> </u> | | | | | | | | | | | |
| 19. | Production Trial R | tun | ļ | | | | | | | | | | | |
| 20. | Production Contro | ol Plan | 1 | | | | | | | | | | | |
| 21. | Preliminary Proce | ss Capability Study | <u> </u> | | | | | | | | | | | |
| | Production Valida | | <u> </u> | | | | | | | | | | | |
| | Part Submission \ | | <u> </u> | | | | | | | | | | | |
| OVE | | TUS RATING (GYR) | (1.2 | | | | | (13 | | | | _ | | |
| | (12) | Januara San Da | (15) | Class and | | C | A | (16) | ! | Diam | (1 Tim | | | 8 |
| # | Activity Activity | Issue(s) for Re (summarize the co | | | | | | ction / Re ning, alloc | | | Open | ing Close | Respon Ford | Supplie |
| | rouvity | (ourmnanzo trio ot | SHOOM Q 1 | counting in | ioitj | (c.g. | TO VIOC LIII | mig, and | ato rocot | | Орон | 0.000 | 1 010 | Саррис |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |

Filling Out the Status Report Form

The following section describes how to fill in each of the fields on the Status Report. Refer to the status report example on the previous page for the number in each field.

1. Org/Supplier

Enter your organization or your company name. If you are delivering the product to another department within the manufacturing facility, a department number or group name may be entered here.

2. Location

Enter the location of the facility manufacturing the system/subsystem or component if applicable.

3. Supplier Code

Enter the UCCS code for the manufacturing facility if applicable.

4. Contact Name/Telephone Number

Identify Program Manager and phone number.

5. Program

Enter the name of the program.

6. Model Year

Enter the Model Year of the program.

7. FPDS Milestone/Team Event

Enter the current FPDS Milestone / Team Event that you will be reporting on.

8. Review Date

Enter the date of the review of this report.

9. Part Name

Enter the name of the part being reviewed (if applicable).

10. Part Number

Enter the part number of the part being reviewed (if applicable).

11. Notice Level

Enter the notice level of the part being reviewed (if applicable).

12. User Plant

Enter the plant(s) where this vehicle will be built.

Filling Out the Status Report Form (cont.)

13. G/Y/R Status

Enter status for the 23 Elements

14. Element / Activity

Enter your home Element Number for which the issue is being reported and the Activity reporting on the issue.

15. Issue(s) for Red/Yellow Elements

Summarize the concern and resulting risk here.

16. Corrective Action / Resolution Plan

Enter a summary of the corrective action for the issue being addressed and the resolution plan to correct the issue (an 8D that is tracking the issue may be referenced here).

17. Timing

Enter the Open date for the issue, and when it is resolved, enter the closing date.

18. Responsibility

Enter the name of the Ford Motor Company and/or the Supplier person responsible for follow-up on this issue.

Quality of Event Checklists

In Appendix B, is an example of a complete Quality-of-Event Checklist along with the website location of the Excel file that contains the 23 Element Checklists. These checklists cover the basic requirements for successful completion of the elements, but may not be inclusive. These checklists are to be used as a guideline in assessing your status. The Element expectations on these checklists have been grouped for Milestone reporting following the FPDS process. The shaded areas should be completed by the appropriate milestone. For next milestone report requirements, update the previous milestone shaded area as needed. The APQP Status Report Form is linked to the checklists and the Information Worksheet for ease of reporting.

Risk Assessment

Every APQP team should conduct a risk assessment as soon as possible after forming the team. The purpose of the risk assessment is to determine what elements in the APQP process a supplier, organization, or program team must complete.

Risk Assessment (cont.)

Elements to be evaluated in the Risk Assessment include:

1) Quality History

- High warranty or Things Gone Wrong (TGWs) on current model or surrogate product
- Frequent Quality Rejects (QRs) and/or campaigns at the receiving plant (Assy & Stmp. Plants, Supplier Plants, etc.)
- Similar component or system was the cause of a recall action

2) Supplier Profile

- New supplier or new manufacturing location
- Product or manufacturing technology is new to the supplier manufacturing location
- Supplier's historic launch performance is poor
- Supplier resources are stretched due to significant amount of new business
- Supplier location is not Q-1 or is under Q-1 probation

3) Engineering Profile

- New design
- Manufacturing techniques are new to the industry
- Similar products are subject to numerous design changes that threaten program timing
- High product or process complexity
- Product is strategically important due to high visibility or functional performance

4). Performance versus Targets


- Design goals (weight, materials, functional performance, etc.) will be difficult to achieve
- Reliability goals will be difficult to achieve
- Quality goals (warranty, TGWs, scrap rates, rework rates, etc.) will be difficult to achieve
- Program timing is compressed
- Cost targets are aggressive

5). Adjustments


If any of the concerns listed above are present, the customer may require all APQP elements to be completed and reported. If the program is considered to be low risk, the supplier may skip certain APQP elements. For example, if the product is carryover with minor changes, existing control plans may be used, and packaging evaluations may not be required. The customer must agree in writing to all deviations from the APQP process. If the customer and the supplier agree that an element/expectation is not required, the supplier should write "NA" for not applicable in the corresponding Milestone column on the Quality-of-Event Checklists.

APQP Timing

Ford / Supplier Systems "V" Model



APQP Generic Program Timing Gantt Chart



APQP Generic Program Timing Gantt Chart

| | | | | | | | | | FER (Approx. 17 Months | | PSW Requirement 1PP Build | | | Assembl Job1 | |
|---------|--------------------------------|----------------------------------|----------|----------|----------|----------|----------|----------|------------------------------|----------|---------------------------------|------------|-----|-----------------|----------|
| | Monti | ns Before Job #1 (MBJ1) | | | | | | | | | | | | 1 | |
| | | All new vehicle: S6 | 52 | 42 | 36 | 33.5 | 30 | 25.5 | 19 | 14.5 | 8 | 4.5 | 3.5 | 0 | -6 |
| | | nodified lower struc: S5 | 50 | 41 | 36 | 33.5 | 30 | 25.5 | 19 | 14.5 | 8 | 4.5 | 3.5 | 0 | -6 |
| | | c/o lower structure: S4 | 43 | 37 | 34 | 32 | 28.5 | 25 | 18.5 | 14 | 8 | 4.5 | 3.5 | 0 | -6 |
| | Mc | derate Freshening: S3 | 38 | 32 | 30 | 30 | 25 | 25 | 18 | 14 | 8 | 4.5 | 3.5 | 0 | -6 |
| | | Minor Freshening: S2 Trim: S1 | 28 21 | 24 18 | 22 16 | 22 16 | 20 14 | 20 14 | 13 11 | 10 8 | 6 5 | 3.5 3.5 | 2.5 | 0 | -6 -6 |
| Element | | FPDS Milestones | КО | SI | SC | PH | PA | ST | PR | CP | CC | LR | LS | J1 | FS |
| Number | APQP Elements | T DO MINOCONICO | | Ţ. | 1 | | | Ť. | 110 | <u> </u> | | | | Ť | |
| | | Ford | | | | Pr | ocess | Definit | ion | | Oper. | Alloc/Trai | ng | | |
| 17 | Operator Process Instructions | Tier 1 Supplier (In/Ex) | | | | | | | | | | | | | |
| | • | | | | | | | | | | | | | | |
| | | Ford | | | | | | | | | | | | | |
| 18 | Packaging Specifications | Tier 1 Supplier (In/Ex) | | | | | | | | | | | | | |
| | | Tier 2 Supplier | | | _# | | | | | | | | | | |
| | | Ford | | | | | | | | | | | | | |
| 19 | Production Trial Run | Tier 1 Supplier (In/Ex) | | | | | | | | | | - | | | |
| | | Tier 2 Supplier | | | | _ | | | _# | | ₩₩ | | | | |
| | | Ford | | | | | | | | | | | | | |
| 20 | Production Control Plan | Tier 1 Supplier (In/Ex) | | | | | | | | | | | | | |
| | | Tier 2 Supplier Ford | _ | | | | | | - | | | | | | |
| 21 | Preliminary Process Capability | Tier 1 Supplier (In/Ex) | | | | | | | | | | | | | |
| | 1 reminiary 1 rocess oupublity | Tier 2 Supplier | | | | | | | | | | | | | |
| | | Ford | | | | | | | | | | | | | |
| 22 | Production Validation Testing | Tier 1 Supplier (In/Ex) | | | | | | | | | | | | | |
| | | Tier 2 Supplier | | | | | | | | | | | | | |
| | | Ford | | | | Interna | al Supp | oliers | > | | | | | | |
| 23 | Part Submission Warrant (PSW) | Tier 1 Supplier | | | | Extern | al Sup | pliers - | > | | | | | | |
| | | Tier 2 Supplier | | | | Sub-S | upplier | | > | | | | | | |

INTERNAL FORD =

EXTERNAL SUPPLIERS OWN PROCESS & PARTICIPATION WITH CUSTOMER'S TEAM =

MAINTENANCE / FEEDBACK (as appropriate) = PARTICIPATE WITH YOUR CUSTOMER'S TEAM =

FER = Final Engineering Release (Supplier)

APQP Elements

Sourcing Decision

Overview

Sourcing Decision is a formal customer commitment to work with the supplier on the program. The goal of the Sourcing element in APQP is to assure that all Internal and External Part Suppliers, Tooling Suppliers, and Facility Suppliers are on board with the program early (e.g. by SC) to allow for them to understand all of the Vehicle Program timing and requirements. The Suppliers are to make sure that all of their Sub-suppliers are also on board to fulfill the Vehicle Program requirements, as soon as possible.

The Sourcing Decision is to be made using appropriate Quality History, and Customer Input data to assure that the supplier is capable of meeting all requirements.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones (KO) to <SC>.

Associated FPDS Process Sheets include (but are not limited to):

| 1.3.2.16.3 | Develop Phase I & II Early Sourcing Workplan |
|------------|-----------------------------------------------------------------|
| 1.3.2.16.4 | Update Sourcing Assumptions for Major Vehicle Systems (Internal |
| | & External Supply) to <si> Level</si> |
| 1.3.2.16.8 | Develop Phase III Early Sourcing Workplan |

Linkage

Key APQP Elements that are input to "Sourcing Decision " include (but are not limited to):

Customer Input Craftsmanship

Key APQP Elements that "Sourcing Decision" will provide output information to include (but are not limited to):

Customer Input

Customer Input Requirements

Overview

Customer Input Requirements are the design criteria and the program requirements necessary to initiate the Advanced Product Quality Planning process. They include Design Goals, Reliability and Quality Goals, Program Timing, Affordable Cost Targets, Capacity Planning Volumes, Key Contact Personnel, and input requested from & supplied by the Manufacturing Facilities involved. This is done to assure that any current Manufacturing/Process issues are addressed appropriately by the new design and process, early in the Product Development cycle.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <PA>.

Associated FPDS Process Sheets include (but are not limited to):

- 1.3.1.5.1.4 Create Preliminary Manufacturing & Assembly Strategy
- 1.5.1.3.1.2 Analyze Quality History in Support of Vehicle Target Ranges
- 1.5.1.5.3.1.2 Analyze Quality History in Support of System Targets
- 1.5.1.6.3.1.1 Analyze Quality History in Support of Sub-System Level 1 Targets
- 1.5.1.7.3.1.1 Analyze Quality History in Support of Sub-System Level 2 Targets
- 1.5.1.8.3.1.1 Analyze Quality History in Support of End-Item/Component Targets

<u>Linkage</u>

Key APQP Elements that are input to "Customer Input" include (but are not limited to):

Sourcing Decision Craftsmanship

Key APQP Elements that "Customer Input" will provide output information to include (but are not limited to):

Drawings & Specifications (Including P-Diagram information, Failure Mode & Effects of Failure Modes, Design Specifications (VDS/SDS/CDS)). Facilities / Tools / Gauges
Manufacturing Process Flow

Overview

Craftsmanship is an assessment of what the customer sees, touches, uses, hears, and smells. It impacts design and manufacturing, and improves the overall perception of value.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program

Timing

Planning is aligned with FPDS Milestones (KO) to (J1).

Associated FPDS Process Sheets include (but are not limited to):

| 1.3.1.2.2 | Update Craftsmanship Strategy |
|------------|----------------------------------------------------|
| 1.3.2.7 | Craftsmanship Implementation Plan |
| 2.4.3 + | Appearance (and its sub-processes) |
| 2.4.3.8.3 | Develop and Assess Fixed Craftsmanship Models |
| 2.4.3.11.6 | Develop and Assess Adjustable Craftsmanship Models |

<u>Linkage</u>

Key APQP Elements that are input to "Craftsmanship" include (but are not limited to):

Sourcing Decision Customer Input Design Reviews

Key APQP Elements that "Craftsmanship" will provide output information to include (but are not limited to):

Sourcing

Customer Input

Drawings & Specifications (Including P-Diagram information, Failure Mode &

Effects of Failure Modes, Design Specifications (VDS/SDS/CDS)).

Prototype Builds

PSW (Color/Appearance)

Design Failure Mode and Effects Analysis (DFMEA)

Overview

A Design or Concept FMEA is a systematic approach; used by a design responsible team, to assure that potential design failure modes and their associated causes have been considered and addressed. DFMEA's are to be done concurrently with the design process to allow for the determined Recommended Actions to positively affect the design.

Output from the Design FMEA (e.g. potential Special Characteristics) should also be used when creating and analyzing the Process FMEA, and the Control Plans.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <PA>, with updates to <CC>.

Associated FPDS Process Sheets include:

| 2.1.11.1 | Perform DFMEA Document Management |
|----------|----------------------------------------------------------------------|
| 2.1.11.2 | Create Design Failure Mode and Effects Analysis (DFMEA) Document |
| 2.1.11.3 | Update Design Failure Mode and Effects Analysis (Prior to <pr>)</pr> |
| 2.1.11.4 | Update Design Failure Mode and Effects Analysis (Prior to <cc>)</cc> |

<u>Linkage</u>

Key APQP Elements that are input to "Design Failure Mode and Effects Analysis (DFMEA)" include (but are not limited to):

Drawings & Specifications (Including P-Diagram information, Failure Mode & Effects of Failure Modes, Design Specifications (VDS/SDS/CDS))

Updates determined from the Design Verification Plan (DVP)

Updates determined from the Process Failure Mode and Effects Analysis (PFMEA)

Updates determined from the Prototype Build

Updates determined from the Production Trial Run

Design Failure Mode and Effects Analysis (DFMEA) – (Cont.)

Key APQP Elements that "Design Failure Mode and Effects Analysis (DFMEA)" will provide output information to include (but are not limited to):

Drawings & Specifications
Design Verification Plan (DVP)
Facilities / Tools / Gauges
Manufacturing Process Flow
Operator Process Instructions (Process definitions)
Process Failure Mode and Effects Analysis
Prototype Build Control Plan

Design / Manufacturing Reviews

Overview

For Suppliers, Design Reviews are regularly scheduled meetings led by the supplier's design activity and must include other affected areas. Manufacturing Reviews are regularly scheduled meetings used to monitor the status of the manufacturing process development.

Within Ford, Design Reviews are held by the Program Teams. Manufacturing Reviews are reviews of the Manufacturing Design, Tooling, Equipment & Facilities.

Both types of reviews are a series of data driven verification activities, and not just a Status Reporting exercise. These reviews are an effective method to prevent problems and misunderstandings; they also provide a mechanism to monitor progress, resolve issues, and report to management.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <LR> (suppliers), and to (J1) (Ford).

Associated FPDS Process Sheets include:

N/A

Linkage

Key APQP Elements that are input to "Design/Manufacturing Reviews " include (but are not limited to):

All APQP Elements

Key APQP Elements that "Design/Manufacturing Reviews " will provide output information to include (but are not limited to):

All APQP Elements

Design Verification Plan & Report (DVP&R)

Overview

The Design Verification Plan is a document that lists the engineering evaluations and tests required to establish that the design is fit for use in its intended environment.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <PA> with updates and reporting to <CC>.

<u>Associated FPDS Process Sheets include (but are not limited to):</u>

| 1.5.1.4.5.4 | Develop Vehicle Design Verification Plan |
|-------------|-----------------------------------------------------------------|
| 1.5.1.5.5.4 | Develop System Design Verification Plan |
| 1.5.1.6.5.4 | Develop Sub-System Level 1 Design Verification Plan |
| 1.5.1.7.5.4 | Develop Sub-System Level 2 Design Verification Plan |
| 1.5.1.8.4.4 | Develop End-Item/Component Design Verification Plan |
| 2.1.2.2 | Update Design Verification Plan (DVP) and Schedule for Existing |
| | Design |
| 2.1.3.2 | Update Design Verification Plan (DVP) and Schedule for Modified |
| | Design |
| 2.1.4.2 | Update Design Verification Plan (DVP) and Schedule for New |
| | Design |
| | · · · · · |

Linkage

Key APQP Elements that are input to "Design Verification Plan (DVP&R)" include (but are not limited to):

Drawings & Specifications (Including P-Diagram information, Failure Mode & Effects of Failure Modes, Design Specifications (VDS/SDS/CDS)).

Design Failure Mode and Effects Analysis (DFMEA)

Prototype Builds

Key APQP Elements that "Design Verification Plan (DVP&R) " will provide output information to include (but are not limited to):

Design Failure Mode and Effects Analysis (DFMEA)

Sub-Contractor APQP Status

Overview

The Subcontractor APQP Status identifies and reports on the condition of an External Supplier or Subcontractor's APQP process. It is required that Internal suppliers (within Ford) & External suppliers cascade APQP requirements to their sub-suppliers or sub-contractors, and conduct APQP reviews as appropriate. The results of those reviews are summarized in Element 7 (Subcontractor APQP Status) of the APQP Status Report.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <LS>.

Associated FPDS Process Sheets include:

N/A

Linkage

Key APQP Elements that are input to "Sub-Contractor APQP Status" include (but are not limited to):

All appropriate APQP Elements for the next lower level external supplier

Key APQP Elements that "Sub-Contractor APQP Status" will provide output information to include (but are not limited to):

Design/Manufacturing Reviews

Facilities / Tools / Gauges

Overview

Facilities, tools, and gauges are those additional, new, refurbished, and relocated resources required to produce the product at the customer specified quantity and quality levels. Expectations for this element include but are not limited to planning, statistical and acceptance criteria, lean manufacturing considerations, qualification of equipment, corrective actions, delivery and setup.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <LS>.

Associated FPDS Process Sheets include:

| 1.3.2.12.1 | Develop Preliminary Manufacturing Plan for <si></si> |
|------------|------------------------------------------------------|
| 1.3.2.12.2 | Update <si> Manufacturing Plan for <sc></sc></si> |
| 1.3.2.12.3 | Update <sc> Manufacturing Plan for <pa></pa></sc> |
| 1.3.2.12.4 | Finalize Manufacturing Plan |

Associated FPDS Sections:

| 1.5.2 | Develop Manufacturing & Tooling Concepts/ Specifications |
|-------|--------------------------------------------------------------------|
| 2.2 | Design Manufacturing Process, Building, Facilities, Tooling & |
| | Equipment and Material Handling |
| 3.8 | Build/ Ship/ Install Manufacturing Facilities, Tooling & Equipment |
| | and Material Handling |

Linkage

Key APQP Elements that are input to "Facilities / Tools / Gauges" include (but are not limited to):

Team Feasibility Commitment
Drawings & Specifications
Design Failure Mode and Effects Analysis
Measurement System Evaluation
Manufacturing Process Flow
Process Failure Mode and Effects Analysis

Facilities / Tools / Gauges - (cont.)

Key APQP Elements that "Facilities / Tools / Gauges" will provide output information to include (but are not limited to):

Team Feasibility Commitment
Measurement System Evaluation
Manufacturing Process Flow
Operator Process Instructions (Process definitions)
Process Failure Mode and Effects Analysis

Prototype Build Control Plan

Overview

The Prototype Build Control Plan is a description of the dimensional measurements, material, and functional tests that will occur during the confirmation prototype build (e.g. (CP)).

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SC> to (CP).

<u>Associated FPDS Process Sheets include (but are not limited to):</u>

1.3.2.20.1 Develop Quality Plans for Prototype Builds

Linkage

Key APQP Elements that are input to "Prototype Build Control Plan" include (but are not limited to):

Manufacturing Process Flow

Operator Process Instructions (Process definition)

Process Failure Mode and Effects Analysis (PFMEA)

Measurement System Evaluation

Design Failure Mode and Effects Analysis (DFMEA)

Key APQP Elements that "Prototype Build Control Plan will provide output information to include (but are not limited to):

Prototype Builds

Pre-Launch Control Plan

Prototype Builds

Overview

The Prototype Builds element entails the manufacture or assembly of components, subsystems, systems, or assembled vehicles (e.g. Confirmation Prototype) that will be supplied to the customer and built prior to the 1PP production trial run.

This element not only includes the actual build process itself, but the preparation for the build.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <PA> to (CP).

Associated FPDS Process Sheets include:

- 3.7.2.1.1.3 Verify Process Sheets During the Confirmation Prototype Build Phase
- 3.7.2.1.2.2.4 Train Operators during the Confirmation Prototype Build Phase
- 3.7.2.1.2.2.7 Build First Confirmation Prototype Unit
- 3.7.2.1.2.2.8 Build Balance of Confirmation Prototype Units

Associated FPDS Sections:

3.7.2.1.2 Perform Confirmation Prototype Build

<u>Linkage</u>

Key APQP Elements that are input to "Prototype Builds" include (but are not limited to):

Prototype Build Control Plan

Operator Process Instructions (Process definitions)

Key APQP Elements that "Prototype Builds" will provide output information to include (but are not limited to):

Facilities / Tools / Gauges

Manufacturing Process Flow

Operator Process Instructions (Process definitions)

Process Failure Mode and Effects Analysis (PFMEA)

Design Failure Mode and Effects Analysis (DFMEA)

Design Verification Plan (DVP)

Pre-Launch Control Plan

Measurement System Evaluation

Drawings & Specifications

Overview

The Drawings & Specifications element is an evaluation of the development of Targets and Specifications as they are defined to be input to the design process (e.g. VDS/SDS/CDS), and to the Drawings (including all engineering drawings, CAD data, material specifications and engineering specifications.)

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning and execution of the Systems Engineering process is aligned with FPDS Milestones <SI> to <PA>. Planning and execution of the Drawings process is aligned with FPDS Milestones <PA> to <PR>.

Associated FPDS Process Sheets include:

| 1.5.1.4.6 | Update/Publish VDS Containing the Compatible Vehicle Targets |
|------------|-----------------------------------------------------------------------------------------------------------------------------|
| 1.5.1.5.6 | Publish SDS Containing the Compatible System Targets |
| 1.5.1.6.6 | Publish SS1DS Containing the Compatible Sub-system Level 1 Targets |
| 1.5.1.7.6 | Publish SS2DS Containing the Compatible Sub-system Level 2 Targets |
| 1.5.1.8.5 | Update/Publish CDS(s) Containing the Compatible End-Item/Component Targets |
| 1.5.2.1.10 | Integrate Manufacturing Equipment, Tools and Process Concepts, Capabilities and Constraints into System Targets |
| 1.5.2.1.11 | Integrate Manufacturing Equipment, Tools and Process Concepts, Capabilities and Constraints into Sub-system Level 1 Targets |
| 1.5.2.1.12 | Integrate Manufacturing Equipment, Tools and Process Concepts, Capabilities and Constraints into Sub-system Level 2 Targets |
| 1.5.2.1.13 | Integrate Manufacturing Equipment, Tools and Process Concepts, Capabilities and Constraints into End-Item/Component Targets |
| 1.5.2.4.3 | Develop Manufacturing Equipment, Tooling and Process Specifications for VO |

Drawings & Specifications – (cont.)

Linkage

Key APQP Elements that are input to "Drawings & Specifications" include (but are not limited to):

Customer Input

Team Feasibility Commitment

Design Failure Mode and Effects Analysis (DFMEA)

Design Verification Plan (DVP)

Key APQP Elements that "Drawings and Specifications" will provide output information to include (but are not limited to):

Design Failure Mode and Effects Analysis (DFMEA)

Facilities / Tools / Gauges

Manufacturing Process Flow

Operator Process Instructions (Process definitions)

Process Failure Mode and Effects Analysis (PFMEA)

Pre-Launch Control Plan

Measurement System Evaluation

Team Feasibility Commitment

Overview

Team Feasibility determines whether the proposed design can be manufactured within the guidelines and specifications. A cross-functional design/manufacturing review team is charged with assessing design feasibility. Once workability is established, the Program Organization undertakes the responsibility of following the design/manufacturing review process and reassessing feasibility for any design or part change that may occur during product development.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <CC>.

<u>Associated FPDS Process Sheets include:</u>

- 1.5.2.2.1.1 Perform Manufacturing Feasibility Studies to Support Vehicle Level Target Setting
- 1.5.2.2.1.2 Perform Manufacturing Feasibility Studies to Support System Level Target Setting
- 1.5.2.2.1.3 Perform Manufacturing Feasibility Studies to Support Sub-System Level 1 Target Setting
- 1.5.2.2.1.4 Perform Manufacturing Feasibility Studies to Support Sub-System Level 2 Target Setting
- 1.5.2.2.1.5 Perform Manufacturing Feasibility Studies to Support End-Item/
 Component Level Target Setting
- 1.5.2.2.2.1.1 Perform Manufacturing Tooling/Machining Supplier Feasibility Studies to Support Vehicle/System Level Target Setting
- 1.5.2.2.2.1.2 Perform Manufacturing Tooling/Machining Supplier Feasibility Studies to Support Sub-System Level 1 Target Setting
- 1.5.2.2.2.1.3 Perform Manufacturing Tooling/Machining Supplier Feasibility Studies to Support Sub-System Level 2 Target Setting
- 1.5.2.2.2.1.4 Perform Manufacturing Tooling/Machining Supplier Feasibility Studies to Support End-Item/Component Level Target Setting
- 1.5.2.1.11 Integrate Manufacturing Equipment, Tools and Process Concepts, Capabilities and Constraints into Sub-system Level 1 Targets

Team Feasibility Commitment – (cont.)

| 1.5.2.1.12 | Integrate Manufacturing Equipment, Tools and Process Concepts, |
|------------|----------------------------------------------------------------|
| | Capabilities and Constraints into Sub-system Level 2 Targets |
| 1.5.2.1.13 | Integrate Manufacturing Equipment, Tools and Process Concepts, |
| | Capabilities and Constraints into End-Item/Component Targets |

Linkage

Key APQP Elements that are input to "Team Feasibility Commitment" include (but are not limited to):

Customer Input

Facilities / Tools / Gauges

Design Failure Mode and Effects Analysis

Measurement System Evaluation

Manufacturing Process Flow

Operator Process Instructions (Process definition)

Process Failure Mode and Effects Analysis

Key APQP Elements that "Team Feasibility Commitment" will provide output information to include (but are not limited to):

Facilities / Tools / Gauges Manufacturing Process Flow Measurement System Evaluation Drawings & Specifications

Manufacturing Process Flow

Overview

The Manufacturing Process Flow is a graphic representation of the current or proposed sequence of manufacturing process. The Manufacturing flow chart can be either in the traditional flow chart format, or depicted in Cycle Line Layouts, Tooling Line Layouts, Plant Layouts, or other appropriate types of layouts, providing all necessary information is included or attached.

The purpose of this element is to ensure that the process definition, PFMEA, and Control Plans can be created and analyzed in the appropriate sequence. It is also a visual confirmation that everyone involved from the suppliers, design and manufacturing engineering, and the manufacturing facility understand the proposed sequence of manufacturing.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SC> to (CP).

Associated FPDS Process Sheets include (but are not limited to):

| 1.3.1.5.1.5 | Create Part Flow for Manufacturing and Assembly |
|--------------|-------------------------------------------------------------------|
| 1.3.1.4.4.9 | Perform Graphic Illustration Process to Support <si></si> |
| 1.3.1.4.4.10 | Perform Graphic Illustration Process to Support <sc></sc> |
| 1.3.1.4.4.25 | Perform Graphic Illustration Process to Support <pa> Costing</pa> |
| 1.5.2.3 | Define Process Flow |
| 1.5.2.4.1 | Update Process Flow for Specifications |
| 1.5.2.5 | Document Manufacturing and Assembly Process/Layout to Support |
| | <pa> Costing</pa> |

Linkage

Key APQP Elements that are input to "Manufacturing Process Flow" include (but are not limited to):

Facilities / Tools / Gauges
Design Failure Mode and Effects Analysis (DFMEA)
Prototype Builds

Manufacturing Process Flow - (cont.)

Key APQP Elements that "Manufacturing Process Flow " will provide output information to include (but are not limited to):

Operator Process Instructions (Process definition)
Process Failure Mode and Effects Analysis (PFMEA)
Prototype Build Control Plan
Pre-Launch Control Plan

<u>Process Failure Mode and Effects Analysis</u> (PFMEA)

Overview

A Process FMEA is a systematic approach used by a manufacturing responsible team to assure that potential process related failure modes and their associated causes have been addressed and resolved.

The Manufacturing Process Flow diagrams are used as visual inputs to the PFMEA to ensure that the process is analyzed in the appropriate sequence, and that all failure modes are addressed. In addition, the potential Special Characteristics from the DFMEA process are a key input to the PFMEA. The PFMEA is used to help determine if those potential Characteristics will need to be monitored in production, or if there is a way to control them through the process.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone timing dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SC> to (CP), with updates to <LR>.

Associated FPDS Process Sheets include (but are not limited to):

| 1.5.2.3.1 | Perform Manufacturing Process Failure Mode and Effects Analysis |
|-----------|-------------------------------------------------------------------|
| | (NEW Product and Processes) |
| 1.5.2.3.2 | Manufacturing Process Failure Mode and Effects Analysis (Existing |
| | Product and Processes) |

Update Manufacturing Process Failure Mode and Effects Analysis

Linkage

1.5.2.3.5

Key APQP Elements that are input to "Process Failure Mode and Effects Analysis (PFMEA)" include (but are not limited to):

Design Failure Mode and Effects Analysis (DFMEA)

Facilities / Tools / Gauges

Manufacturing Process Flow

Operator Process Instructions (Process definition)

Prototype Builds

Production Trial Run

Process Failure Mode and Effects Analysis (PFMEA) – (cont.)

Key APQP Elements that "Process Failure Mode and Effects Analysis (PFMEA)" will provide output information to include (but are not limited to):

Design Failure Mode and Effects Analysis (DFMEA) Team Feasibility Commitment Prototype Build Control Plan Pre-Launch Control Plan Operator Process Instructions (Process definition)

Measurement System Evaluation

Overview

The Measurement System Evaluation assesses the variation of the measurement system and determines whether the measurement system is acceptable for monitoring the process.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SC> to <CC>.

Associated FPDS Process Sheets include:

| 1.3.2.21.1 | Develop Preliminary Dimensional Control Plan for <si></si> |
|---------------|------------------------------------------------------------|
| 1.3.2.21.3 | Update <si> Dimensional Control Plan for <sc></sc></si> |
| 1.3.2.21.4 | Update <sc> Dimensional Control Plan for <pa></pa></sc> |
| 1.3.2.21.5 | Finalize Dimensional Control Plan |
| 2.2.4.5.1 | Modify Existing Quality Control Tools & Equipment Design |
| 2.2.4.5.2 | Design New Quality Control Tools & Equipment |
| 3.8.1.8.1 | Modify Existing Quality Control Tools & Equipment |
| 3.8.1.8.2 | Build New Quality Control Tools & Equipment |
| 3.8.2.6 | Ship Quality Control Tools & Equipment to Final Production |
| | Location |
| 3.7.1.2.4.5.2 | Verify Gauge Repeatability and Reliability |
| 3.7.1.2.4.5.3 | Gauge Certification |
| 3.7.1.1 | Re-certify Re-usable Tools, Equipment and Processes using |
| | Carry-over End-Item |
| | |

Linkage

Key APQP Elements that are input to "Measurement System Evaluation" include (but are not limited to):

Team Feasibility Commitment Drawings & Specifications Facilities / Tools / Gauges

Measurement System Evaluation – (cont.)

Key APQP Elements that "Measurement System Evaluation" will provide output information to include (but are not limited to):

Team Feasibility Commitment
Facilities / Tools / Gauges
Prototype Build Control Plan
Pre-Launch Control Plan
Production Control Plan
Preliminary Process Capability
Part Submission Warrant (PSW)

Pre-Launch Control Plan

Overview

The Pre-Launch Control Plan is a written description of the dimensional measurements and material and functional tests (in-process checks) that will occur after the Prototype Builds and before the Production Builds. The Pre-Launch Control Plan should include any additional necessary product/process controls until the production process is validated. Its purpose is to contain potential non-conformances after prototype, but prior to full production (e.g. 1PP and FEU Builds).

Examples of these types of checks include:

- Increased Inspection
- Increased Audits
- Increased Statistical Charting

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <PR> to <CC> with updates to <LR>.

Associated FPDS Process Sheets include (but are not limited to):

1.3.2.20.2 Develop Quality Control Plans for Pre-Launch Builds

Linkage

Key APQP Elements that are input to "Pre-Launch Control Plan" include (but are not limited to):

Process Failure Mode and Effects Analysis (PFMEA)

Prototype Build Control Plan

Prototype Builds

Measurement System Evaluation

Operator Process Instructions

Manufacturing Process Flow

Key APQP Elements that "Pre-Launch Control Plan" will provide information to include (but are not limited to):

Operator Process Instructions (Process verification, allocations, and training)

Production Trial Run

Production Control Plan

Operator Process Instructions

Overview

The Operator Process Instructions element is divided into two major components: The first being Process Description; and the second being Operator Instructions (e.g. operator allocations, verification of process definition, and operator training). Operator Process Instructions describe the details of controls and actions that operating personnel must perform to produce quality products.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning of the Process Description is aligned with FPDS Milestones <SC> to (CP). Planning of the Operator Allocations and Training process is aligned with FPDS Milestones (CP) to <LS>, with updates to (J1) and beyond.

Associated FPDS Process Sheets include (but are not limited to):

| 1.5.2.3.3 | Modify or Develop New Process Sheets |
|---------------|---------------------------------------------------------------------|
| 1.5.2.3.4 | Update Process Sheets |
| 3.7.2.1.1.3 | Verify Process Sheets during the Confirmation Prototype Build Phase |
| 3.7.2.1.2.2.4 | Train Operators during the Confirmation Prototype Build Phase |
| 3.7.2.2.3 | Verify Process Sheets during the Hard Tooled Functional Build Phase |
| 3.7.2.2.4 | Train Operators during the Hard Tooled Functional Build Phase |
| 3.7.2.3.5 | Train Operators During TTO/1PP Build Phase |
| 3.7.2.4.4 | Train Operators During Integrated/Continuous Build Phase |

Linkage

Key APQP Elements that are input to "Operator Process Instructions" include (but are not limited to):

Design Failure Mode and Effects Analysis (DFMEA)

Facilities / Tools / Gauges

Manufacturing Process Flow

Prototype Builds

Pre-Launch Control Plan

Production Trial Run

Process Failure Mode and Effects Analysis (PFMEA)

Key APQP Elements that "Operator Process Instructions" will provide output information to include (but are not limited to):

Production Trial Run

Process Failure Mode and Effects Analysis (PFMEA)

Production Control Plan

Packaging Specifications

Overview

The supplier of a product must ensure that individual packaging for shipment (including interior partitions) is designed and developed. Customer packaging standards or generic packaging requirements should be used when appropriate.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones <SI> to <PA>. Engineering and testing of the Packaging is aligned with FPDS Milestones <PA> to <LS>.

Associated FPDS Process Sheets include (but are not limited to):

TBD

Linkage

Key APQP Elements that are input to "Packaging Specifications " include (but are not limited to):

Sourcina

Customer Input

Team Feasibility Commitment

Key APQP Elements that "Packaging Specifications" will provide output information to include (but are not limited to):

Prototype Builds Production Trial Run

Production Trial Run

Overview

The Production Trial Run is a validation of the effectiveness of the manufacturing and assembly process, using production tooling, equipment, environment (including production operators), facilities and cycle times. Output of the Production Trial Run is used for Production Part Approval for the manufacturer, and "Open-To-Go" review for Assembly.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

(Please note that there are two different checklists for this element: Internal / External Suppliers, and the Assembly Process).

Timing

Planning for Internal / External Suppliers is aligned with FPDS Milestones <CP> to (J1). Planning for the Assembly Process is aligned with FPDS Milestones <CC> to (J1).

Associated FPDS Process Sheets include:

| 3.7.2.3 | Validate Production Assembly via Production Prove-Out Build (1PP) |
|-----------|--------------------------------------------------------------------|
| 3.7.2.3.6 | Tool Try-out/Production Prove-out Build (TTO/1PP) |
| 3.7.2.4 | Validate Production Assembly Process via Sales Build (Includes FEU |
| | Builds) |
| 3.7.2.4.7 | Build Continuous Sales Units |

Linkage

Key APQP Elements that are input to "Production Trial Run " include (but are not limited to):

Pre-Launch Control Plans
Operator Process Instructions

Operator Process Instructions

Key APQP Elements that "Production Trial Run" will provide output information to include (but are not limited to): Production Control Plan

Preliminary Process Capability
Process Failure Mode and Effects Analysis (PFMEA)
Design Failure Mode and Effects Analysis (DFMEA)
Production Validation Testing

Production Control Plan

Overview

The Production Control Plan is a written description of the systems for controlling parts and processes during full production. This document is based on the Pre-Launch Control Plan.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone timing dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

(Please note that there are two different checklists for this element: Internal / External Suppliers, and the Assembly Process).

Timing

Planning for Internal / External Suppliers is aligned with FPDS Milestones (CP) to <LR>. Planning for the Assembly Process is aligned with FPDS Milestones <LR> to (J1)+.

Associated FPDS Process Sheets include:

1.3.2.20.3 Develop Quality Control Plans for On-Going Production

Linkage

Key APQP Elements that are input to "Production Control Plan" include (but are not limited to):

Pre-Launch Control Plans

Operator Process Instructions

Production Trial Run

Preliminary Process Capability

Measurement System Evaluation

Production Validation Testing

Key APQP Elements that "Production Control Plan" will provide output information to include (but are not limited to):

Operator Process Instructions Customer Input

Preliminary Process Capability

Overview

The Preliminary Process Capability study is a statistical assessment of the ability of the process to produce product within specification. Refer to the AIAG Production Part Approval Process (PPAP) manual for more details concerning the Preliminary Process Capability study.

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Timing

Planning is aligned with FPDS Milestones (CP) to (J1).

Associated FPDS Process Sheets include:

3.7.1.3 Perform Preliminary Process Capability Study (Ppk)

Linkage

Key APQP Elements that are input to "Preliminary Process Capability " include (but are not limited to):

Production Trial Run Measurement System Evaluation

Key APQP Elements that "Preliminary Process Capability" will provide output information to include (but are not limited to):

Production Control Plan Production Validation Testing Part Submission Warrant (PSW)

Production Validation Testing

Overview

Production Validation Testing refers to engineering testing which validates that products made from production tools and processes meet engineering standards/specifications. All Internal and External Suppliers to Ford are to complete Production Validation Testing as a requirement of the Part Submission Warrant (PSW).

APQP Expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

(Please note that there are two different checklists for this element: Internal / External Suppliers, and the Assembly Process).

Timing

Planning for Internal / External Suppliers is aligned with FPDS Milestones (CP) to <LR>. Planning for the Assembly Process is aligned with FPDS Milestones <CC> to <LS>.

<u>Associated FPDS Process Sheets include:</u>

| 3.7.2.3 | Validate Production Assembly Process via Production Prove-out |
|-----------|------------------------------------------------------------------|
| | Build (1PP) |
| 3.7.1.4.2 | Produce PSW Parts/Assemblies |
| 3.7.1.1 | Re-certify Re-usable Tools, Equipment and Processes using Carry- |
| | over End-Item |
| 3.7.2.3.3 | Suppliers & Ford Confirm can Handle Line Speed |

Linkage

Key APQP Elements that are input to "Production Validation Testing" include (but are not limited to):

Preliminary Process Capability Production Trial Run

Key APQP Elements that "Production Validation Testing" will provide output information to include (but are not limited to):

Part Submission Warrant (PSW)
Production Control Plans

Part Submission Warrant (PSW)

Overview

Production Part Approval Process is the documented verification that the Internal or External supplier meets all engineering design requirements and the process has the capability to meet these requirements during an actual production run. The Part Submission Warrant (PSW) is the final sign-off that the Production Part Approval Process (PPAP) has been followed.

This element not only requires that PPAP/PSW is followed, but the supplier can provide appropriate level parts to the customer's assembly process by the required In-Plant-Date (IPD).

Timing

Planning for Internal / External Suppliers is aligned with FPDS Milestones <PR> to <LR>, with requirements out to (J1)+.

APQP expectations for this element are described in the associated Quality-of-Event Checklist. The Checklist is used to plan for the element, and the Vehicle Program's FPDS milestone dates shall be understood and applied to the generically shown timing. This is done to make the Checklist specific for the supplier and the program.

Associated FPDS Process Sheets include:

- 3.7.1 Validate Components / End-Items for Part Submission Warrant (PSW)
- 3.7.1.4.2 Produce PSW Parts / Assemblies

Linkage

Key APQP Elements that are input to "PPAP/PSW" include (but are not limited to):

ALL 23 APQP Elements

Appendix Section

Appendix A: APQP Roles & Responsibilities

| | <u>vo</u> . | - PD APQP I | LEADI S | UPPORT | RESPONS | BILITIES - | RELATION | SHIP TABL | <u> </u> | |
|------|--------------------------------------|---------------------------------------------------------------------------------|---------------------------------------------------------------|--------------------------------------|--------------------|---------------------------------------------------------|------------------------------------------|-------------------------------------------------|----------------------------------------------------------|-------------------------------------|
| | Element | Other (NON VO) | VO APQP | Assembly Plant | Stamping Plant | Stamping-Structures, Paint & Assembly Engineering | New Model Program Engineering (°6) | Material Handling & Packaging Engineering | Advanced Manufacturing Pre- Program Engineering | Manufacturing Business Office |
| 1 | Sourcing Decision | Purchasing(*3) | Input/Particip. | Input/Particip. | Input/Particip. | Input/Concur | Input/Particip. | Input/Particip. | Participate | L _{v0(*2)} |
| 2 | Customer Input Requirements | L _{ead} CBG | Input/Particip. | Input/Particip. | Input/Particip. | Input/Concur | Input/Particip. | Input/Particip. | Input/Particip. | Participate |
| 3 | Craftsmanship | L _{ead} CBG & Input/Part. Craft. Ctr | Input/Particip. | Input/Particip. | Input/Particip. | Input/Particip. | Input/Particip. | No Role | Input/Particip. | No Role |
| 4 | Design FMEA | L _{ead} CBG | Input/Particip. | Input/Review | Input/Review | Input/Concur | No Role | No Role | Input/Particip. | No Role |
| 5 | Design / Manufacturing Review(s) | Shared Lead - CBG | Input/Particip. | Input/Particip. | Input/Particip. | Shared Lead | Input/Concur | Input/Concur | Participate | No Role |
| 6 | Design Verification Plan & Report | L _{ead} CBG | Input/Review | Participate | Participate | Input/Concur | Input/Concur | No Role | No Role | No Role |
| 7 | Subcontractor APQP Status | L _{ead} Purch (*3) | Review | Input/Particip. | Input/Particip. | Input/Particip. | No Role | No Role | No Role | No Role |
| 8 | Facilities, Tools, and Gages | No Role | Review | Input/Concur | Input/Concur | Lead | Input/Concur | Input/Particip. | Input/Particip. | Input/Particip. |
| 9 | Prototype Build Control Plan | Shared Lead CBG | Shared Lead | Input/Particip. | Input/Particip. | Input/Concur | Concur | No Role | No Role | No Role |
| 10 | Prototype Builds | L _{ead} CBG | Participate | Participate | Participate | Input/Concur | "AP" Conces"CP" Lead | Participate | No Role | Input/Particip. |
| 11 | Drawings and Specifications | L _{ead} CBG | Review | Review/Concur | Review/Concur | Input/Review | Review | Input/Review | No Role | No Role |
| 12 | Team Feasibility Commitment | Shared Lead CBG | Participate | Input/Concur | Input/Concur | Shared Lead | Input/Concur | Input/Particip. | Input/Concur | Input/Concur |
| 13 | Manufacturing Process Flow Chart | No Role | Review | Input/Concur | Input/Concur | Lead | Participate | Input/Particip. | No Role | No Role |
| 14 | Process FMEA | Input/Particip. CBG | Input/Concur | Input/Particip. | Input/Concur | Lead | Review | Input/Particip. | No Role | No Role |
| 15 | Measurement Systems Evaluation | No Role | Review | Input/Particip. | Input/Particip. | Lead | No Role | No Role | No Role | No Role |
| 16 | Pre-Launch Control Plan | Input/Particip. CBG | Input/Concur | Lead | Lead | Input/Concur | Input/Particip. | No Role | No Role | No Role |
| 17 | Operator Process Instructions | No Role | Review | Input/Particip. | Input/Particip. | Lead(%) | Review | No Role | No Role | No Role |
| 18 | Packaging Specifications | Input/Concur Purch. | Review | Input/Concur | Input/Concur | Input/Particip. | No Role | Lead | No Role | No Role |
| 19 | Production Trial Run | Input/Particip. CBG | Participate | Lead | Lead | Input/Particip. | Input/Concur | Input/Particip. | No Role | No Role |
| 20 | Production Control Plan | No Role | Input/Concur | Lead | Lead | Input/Particip. | Input/Particip. | No Role | No Role | No Role |
| 21 | Preliminary Process Capability Study | No Role | Review | Review | Shared Lead | Shared Lead | Input/Concur | No Role | No Role | No Role |
| 22 | Production Validation Testing | L _{ead} CBG | Review | Input/Particip. | Input/Particip. | No Role | Input/Concur | No Role | No Role | No Role |
| 23 | Part Submission Warrant (PSW) | Purchasing(*3) | Input/Particip. | L _{vo(*t)} | L _{voeto} | Input/Particip. | Input/Concur | No Role | No Role | No Role |
| | KEY | | | | | | PLEASE NOTE: | | | |
| Luni | Lead for VO deliverables | *1 for Make Parts | | | | | | picts an example of | a Ford Vehicle Ope | rations / Product |
| | G = Consumer Business Group | *2 for Vehicle Asso *3 Purchasing for the for Cp builds *5 Engineering Re | Buy Parts sponsible for F r Operator Ger nch Process | rocess Sheets; erated Instruction | | | Development Tear | m Relationship Tabl | e. It can be used as ganizations' require | s an example to |

Advanced Product Quality Planning Release Level: 3.0

Ford APQP Guideline (copyright ©, 2001)

Powertrain Roles and Responsibilities Matrix for Quality Planning

| | | Responsibility to Drive Element to Completion | | | | | |
|----|--------------------------------------|-----------------------------------------------|---------|---------|---------|---------|----------|
| | | Program Office | PD | ME | Plant | STA | Supplier |
| 1 | Sourcing Decision | Lead | Support | Support | - | - | - |
| 2 | Customer Input Requirement | - | Lead | Support | Support | - | - |
| 3 | Craftsmanship | - | Lead | Support | Support | - | - |
| 4 | Design FMEA | - | Lead | Support | - | - | - |
| 5 | Design Review(s) | - | Lead | Support | - | - | - |
| 6 | Design Verification Plan | - | Lead | Support | - | - | - |
| 7 | Subcontractor APQP Status | - | Support | Support | Support | Support | Lead |
| 8 | Facilities, Tools and Gauges | - | Support | Lead | Support | - | - |
| 9 | Prototype Build Control Plan | - | Support | Lead | Support | Support | - |
| 10 | Prototype Build | - | Support | Lead | Support | Support | Support |
| 11 | Drawings and Specifications | - | Lead | Support | - | - | - |
| 12 | Team Feasibility Commitment | - | Support | Lead | Support | - | - |
| 13 | Process Flow Chart | - | Support | Lead | Support | - | - |
| 14 | Process FMEA | - | Support | Lead | Support | Support | Support |
| 15 | Measurement Systems Evaluation | - | Support | Lead | Support | - | - |
| 16 | Pre-Launch Control Plan | - | Support | Lead | Support | - | - |
| 17 | Operator Process Instructions * | - | Support | Lead | Support | - | - |
| 18 | Packaging Specifications | - | Support | Lead | Support | - | - |
| 19 | Production Trial Run | - | Support | Lead | Support | Support | Support |
| 20 | Production Control Plan * | - | Support | Lead | Support | Support | - |
| 21 | Preliminary Process Capability Study | - | Support | Lead | Support | - | - |
| 22 | Production Validation Testing | - | Support | Lead | Support | Support | Support |
| 23 | Part Submission Warrant (PSW) | - | Support | Support | Lead | Support | Support |

^{* =} recommended responsibility. Final agreement made by ME & Plant at beginning of program

Powertrain Program Review Process (PTPRP)

The Power Train Program Review Process (PTPRP) standard is used to manage and review Powertrain program status and supports FPDS. This standard defines:

- Power Train Program Review Process in support of the PQOS
- A series of Powertrain checkpoints and their relationship to FPDS
- The program review process used to monitor the status of the deliverables and the overall health of the program
- The means of communicating the status of the deliverables at each checkpoint from Component Program Module Team (CPMT) through a total Powertrain System Checkpoint Review
- Uniform reporting formats to communicate program status within the team structure

Note: The PTPRP standard is not intended to define the Powertrain Product Development Process.

The correlation of FPDS to PTPRP is as follows:

| • | Kick Off; | KO = Chpt. 11 |
|---|--------------------------|---------------|
| • | Engineering Declaration; | SI = Ckpt. 9 |
| • | Strategic Confirmation; | SC = Ckpt. 8 |
| • | Program Approval; | PA = Ckpt. 7 |
| • | Design Complete; | PT = Ckpt. 6 |
| • | Final Release; | PR = Ckpt. 5 |
| • | Confirmation Prototypes; | CP = Ckpt. 4 |
| • | Change Cut-off; | CC = Ckpt. 3 |
| • | Launch Readiness; | LR = Ckpt. 2 |
| • | Job 1; | J1 = Ckpt. 1 |
| • | Final Status | FS = Ckpt1 |

STA Roles & Responsibilities

External Supplier (typically the role of a Project Manager):

Responsible to:

- Plan, cascade, and evaluate completion of the APQP elements with a focus on Quality of Event and sub-tier performance.
- Collect and consolidate APQP Assessments for supplier internal program status reviews, QOS reporting, and proactive concern resolution.
- Communicate, deliver APQP assessments, action items and resolution plans, in a timely manner, to STA and PMT/CPMT on "High-Impact commodities" and any other red or yellow assessments or upon request.
- Provide adequate support for all build events and facilitate quick resolution of issues that may arise.

STA Program Engineer

Responsible to:

- Lead selection of high impact suppliers with input from program team.
- Notify high impact suppliers and provide guidance on APQP Status reporting requirements.
- Collect, verify and consolidate "High-Impact" and red/yellow assessments on external suppliers for the vehicle program.
- Prepare, distribute, and communicate periodic APQP status and risk assessment reports.
- Support Site Engineers, as needed, in signing-off PFMEA and Control Plans for Segment III and IV suppliers
 with Inverted Delta parts.
- Support Site Engineers, as needed, in the disposition of PPAP packages for Segment III & IV suppliers with PPAP levels 2 through 5.
- Coordinate all Launch Readiness Reviews and support Site Engineer, as needed, for Segment III & IV
 Suppliers.
- Support program build events and facilitate resolution of supplier quality issues.

STA Site Engineer

Responsible to:

- Support High Impact Supplier selection process.
- Assist supplier in developing robust product quality and process control methods.
- Review supplier APQP status per program schedule.
- Update Program Engineer on APQP status for all High Impact Supplier and those with Red or Yellow status.
- Assist Suppliers in establishing element action plans and resolution.
- Sign-off on PFMEAs and Control Plans for Inverted Delta parts.
- Perform Launch Readiness Reviews for all Suppliers as required.
- Disposition PPAP packages for all supplier sites.

1. Sourcing Decision

| Organization | Activity |
|-------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Powertrain Operations (PTO) STA | Provides input and participates in the development of the suppliers list |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. Report status, identify issues, open APQP action items and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |
| Supplier Technical Assistance (STA) | Support program sourcing decision by providing input on historical supplier quality performance and lessons learned from previous and current launches when requested. |

2. Customer Input Requirements

| Organization | Activity |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Provides input and participates in the vehicle design criteria and program requirements and supports the development of the Wants List |
| Supplier Technical Assistance (STA) | Program STA Engineer will provide APQP status reporting frequency, review schedule, and other program specific requirements. |
| | Collect all information needed from customer as outlined in the APQP quality of event checksheets. |
| External Suppliers | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |

3. Craftsmanship

| Organization | Activity |
|-------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Provides input and participates in the execution of the Craftsmanship targets |
| Supplier Technical Assistance (STA) | Support all craftsmanship targets development activities for High Impact Suppliers as needed. |
| External Suppliers | Understand and execute all craftsmanship targets for your parts and support all pertinent activities outlined in the APQP quality of event checksheets, report status, identify issues and open APQP action items and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) on a timely basis. |

4. Design FMEA

| Organization | Activity |
|-------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Provides input and supports the program team and P/T engineers to develop DFMEAs |
| Supplier Technical Assistance (STA) | Support DFMEA activities for High Impact Suppliers as needed. |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. |
| | Conduct regular reviews of DFMEA updates with customer engineering and reliability team as design changes occurs until final engineering sign-off. |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT/CPMT on a timely basis. |

5. Design and Manufacturing Review(s)

| Organization | Activity |
|-------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Provides input and concurs on the Design and Manufacturing Reviews |
| Supplier Technical Assistance (STA) | Support reviews as needed and facilitate resolution of High Impact Supplier issues. |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. |
| | Report key issues, open APQP action items and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |

6. Design Verification Plan & Report

| Organization | Activity |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Works with program team and P/T engineers to review and confirm the DVP results and specification settings for the engine and powertrain significant/critical characteristics |
| Supplier Technical Assistance (STA) | Support development of DVP for High Impact Suppliers as needed. |
| External Suppliers | Deliver all expectations at program-designated timelines outlined in the quality of event checksheets and APQP implementation guidebook. |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |

7. Sub-Contractor APQP Status

| Organization | Activity |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Internal and External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. |
| | Report status, identify issues and open APQP action items and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |
| Supplier Technical Assistance (STA) | Review supplier sub-contractor plans of High Impact Suppliers for program risks and monitor resolution of issues if there are any. |

8. Facilities, Tools & Gauges

| Organization | Activity |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Complete deliverables as outlined in the APQP quality of event checksheets. |
| External Suppliers | Report status, identify issues and open APQP action items and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |
| Supplier Technical Assistance (STA) | Review High Impact Supplier tooling development for program risks, elevate issues to program team, and monitor resolution of issues if there are any. |
| VO and All Other Internal Suppliers | Prior to the Production Trial Run, all other VO internal suppliers provide input and participate in supporting: • The selection of the facilities |
| | The delivery and installation of tools and gauges |

9. Prototype Build Control Plan

| Organization | Activity |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Provides input and participates in identifying any additional significant/critical characteristics for the PBCP |
| Supplier Technical Assistance (STA) | Review, facilitate, and monitor resolution of issues for High Impact Suppliers as needed. STA sign-off required for all inverted delta parts. |
| External Suppliers | Deliver all expectations at program-designated timelines outlined in the quality of event checksheets and APQP implementation guidebook. Present final document for engineering and STA approval |
| | and sign-off for all inverted delta parts. Report status, identify issues and open APQP action items and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |

10. Prototype Build

| Organization | Activity |
|-------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Commits to identify lessons learned for new products, processes, facilities, and tools throughout the Prototype Build Phase |
| Supplier Technical Assistance (STA) | Support prototype build events and facilitate resolution of supplier quality issues. |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. Support all prototype build activities and provide immediate response and prompt resolution when build issues arise. Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |

11. Drawings & Specifications

| Organization | Activity |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Provides input and supports the program team and P/T engineers to develop drawings and specifications |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. |
| | Report status, identify issues and open APQP action items and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |
| Supplier Technical Assistance (STA) | Verify that drawings and specifications include enough detail to ensure customer satisfaction, fit and function. Assist in identifying SC/CC's for High Impact Suppliers as needed. |

12. Team Feasibility Commitment

| Organization | Activity |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Takes an active role in reviewing its support functions' feasibility at each Design and Manufacturing Reviews up to <cc>, and works to resolve all feasibility issues relating to specifications set for significant, critical, and special characteristics.</cc> |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. Take an active role in presenting data and reviewing feasibility at each Design and Manufacturing Reviews up to <cc>, and work to resolve all feasibility issues relating to specifications set for significant, critical, and special characteristics. Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis.</cc> |
| Supplier Technical Assistance (STA) | Support reviews as needed, monitor risk and facilitate resolution of High Impact Supplier issues. |

13. Manufacturing Process Flow

| Organization | Activity |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Supplier Technical Assistance (STA) | Conduct on-site reviews for High Impact Suppliers as needed. |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. Report status, identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |
| VO and All Other Internal Suppliers | Provide input and participate in preparing Manufacturing Process Flow Charts, if necessary |

14 Process FMEA

| Organization | Activity |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PTO STA | Leads in determining the PFMEAs to be prepared, and ensuring their coordination and preparation with all affected cross-functional activities |
| Supplier Technical Assistance (STA) | Conduct on-site review for High Impact Suppliers as needed. STA sign-off required for all inverted delta parts. |
| | Complete deliverables as outlined in the APQP quality of event checksheets. |
| External Suppliers | Present final document for engineering and STA approval and sign-off for all inverted delta parts. |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. |

15. Measurement System Evaluation

| Organization | Activity | | | | | |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|--|
| PTO STA | Supports the development of the Wants List and will support Measurement Systems Evaluation status, when required | | | | | |
| Supplier Technical Assistance (STA) | Conduct on-site review for High Impact Suppliers as needed. | | | | | |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. | | | | | |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | | |

16. Pre-Launch Control Plan

| Organization | Activity | | | | |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|
| Supplier Technical Assistance (STA) | Conduct on-site review for High Impact Suppliers as needed. STA sign-off required for all inverted delta parts. | | | | |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. | | | | |
| | Present final document for engineering and STA approval and sign-off for all inverted delta parts. | | | | |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | |

17. Operator Process Instructions

| Organization | Activity | | | | |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. | | | | |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | |
| Supplier Technical Assistance (STA) | Conduct on-site review for High Impact Suppliers as needed. | | | | |

18. Packaging Specifications

| Organization | Activity | | | | | |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|--|
| Supplier Technical Assistance (STA) | Conduct on-site review for High Impact Suppliers as needed. | | | | | |
| | Complete deliverables as outlined in the APQP quality of event checksheets. | | | | | |
| External Suppliers | Ensure that all packaging trials and approvals are obtained prior to PPAP submission. | | | | | |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | | |

19. Production Trial Run

| Organization | Activity | | | | | |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|--|
| Supplier Technical Assistance (STA) | Conduct on-site run@rate reviews at supplier manufacturing location as needed. Support assembly plant trial runs and facilitate resolution of supplier quality issues. | | | | | |
| Internal and External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. Support customer assembly plant production trial runs with adequate personnel and provide prompt response and assistance to resolve any build issues that arise. | | | | | |

20. Production Control Plan

| Organization | Activity | | | | |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|
| Supplier Technical Assistance (STA) | Conduct on-site review as needed. STA sign-off required for all inverted delta parts. | | | | |
| | Complete deliverables as outlined in the APQP quality of event checksheets. | | | | |
| External Suppliers | Present final document to engineering and STA approval and sign-off for all inverted delta parts. | | | | |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | |

21. Preliminary Process Capability

| Organization | Activity | | | | |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|
| Supplier Technical Assistance (STA) | Review and verify capability for full PSW approval. | | | | |
| | Complete deliverables as outlined in the APQP quality of event checksheets. | | | | |
| External Suppliers | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | |

22. Production Validation Testing

| Organization | Activity | | | | |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|
| Supplier Technical Assistance (STA) | Review and verify successful completion of tests for full PSW approval. | | | | |
| External Suppliers | Complete deliverables as outlined in the APQP quality of event checksheets. Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | |

23. Part Submission Warrant (PSW)

| Organization | Activity | | | | |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|
| Supplier Technical Assistance (STA) | PSW sign-off approval authority for all PPAP submission levels 2 through 5. | | | | |
| Internal Suppliers | Provide the facilities to deliver PSW parts at IPD and support the program as necessary | | | | |
| | Coordinate PSW approval activities with STA to support program PSW and Assembly plant IPD timing requirements. | | | | |
| External Suppliers | Follow AIAG Production Parts Approval Process (PPAP) submission requirements along with Ford specific guidelines in preparing PPAP packages. | | | | |
| | Report status; identify issues and open APQP action items; and their resolution plan in the APQP status reports submitted to Supplier Technical Assistance (STA) and PMT / CPMT on a timely basis. | | | | |

Appendix B: Related Forms

Please refer to the FPS Website for information regarding OEE:

http://www.fps.ford.com/html/inf/fps/index.html

Please refer to the APQP Website for APQP Status Report/Checklists/APQP Risk Assessment forms:

http://www.dearborn2.ford.com/apqpcntr



FPDS Timing

APQP Element Rating Checklist

1. Sourcing Decision

Due Dates

Sourcing Decision is a formal customer commitment to work with all Internal & External Part Suppliers, Tooling Suppliers, and Facility Suppliers on the program. Suppliers, and their sub-suppliers, should be engaged as early as possible (e.g. by SC) to understand program timing and requirements. Sourcing Decision should be made with appropriate Quality History & Customer Input Data.

| | ***** | 1 mang | Date | Dates | | | | | | | | | | | | | |
|---------|-------|--------|-------------------|--------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------|-----------|---------------|----------|---------------|----------|-----------|-----------|-----------|---------------|---------------|
| Item | Start | Target | Program Timing | Supplier Timing | Expectations < | SI> | <sc></sc> | <ph></ph> | < PA > | (ST) | < PR > | (CP) | <cc></cc> | <lr></lr> | <ls></ls> | (J1) | < FS > |
| 1. | ко | | 13-Jul-99 | 13-Jul-99 | There are NO major Sourcing Decision issues/inhibitors, that will create an uncontainable risk now or in the foreseeable future. | G | R | Υ | G | | | | | | | | |
| 2. | ко | sī | 26-Jul-99 | N/A | Ensure that the Supplier's Quality History is factored into the Sourcing Decision for all Phases of the Sourcing Decision including Global Logistics concerns. (e.g. Supplier Improvement Metrics (SIM) database). | G | | | 1 | | | | \ | | | | |
| 3. | ко | sı | 26-Jul-99 | N/A | Ensure that Ford Global Logistics is aware of all selected suppliers at the St Milestone. | G | | | | | | | | | | | |
| 4. | ко | sc | 28.Oct.99 | 21.0ct.99 | Complete and communicate the Sourcing Decisions to the Part, Tooking & Facility Suppliers/Sub-Suppliers by the SC Milestons. | | Ŗ | G | | | | | | > | | | |
| 5. | ко | sc | 28-Oct-99 | 28-Oct-99 | Ensure that all appropriate Part, Tooling and Facilities Suppliers Sub-Suppliers are on-board and involved with the Program Team early enough to understand at requirements including Craftsmanship targets. | | R |) Y | G | | | | | | | | |
| 6. | ко | sc | 28-Oct-99 | N/A | Ensure that Assembly and Storping Plants are were of all selected Suppliers. (see APCF Element Custome Input). | | Y | G | | | | | | | | | |
| 7. | sı | PA | 29-Jun-99 | 29-Jun-99 | The Early Sourcing Target Agreement (BSTs) and Reliability Statement of Work, Engineering Statement of Work, etc., have been signed by Furchesing, Product Development and the Simplier. | | | | \ Y | | | | | | | | |
| Other | | | | | | | \nearrow | | | | | | | | | | |
| Overall | ко | PA | 29-Jun-99 | 29-Jun-99 | Team's Overall Rating of this Element (G/Y/R) | G | R | Y | Y | | | | | | | | |
| | | | $\overline{}$ | $\overline{}$ | | M02/99 | 11101199 | 12/03/99 | 07113800 | E7/26/90 | 04/18/01 | 88920991 | 03/04/02 | 06119402 | 87/24/82 | 11804802 | TED |

Instructions: Consider status of Expectations and then enter Overall Ratter for that reflectance. Enter open issues/comments/risks & resolution plans below. Rate this element based on the Expectations that should be complete at a milestone. Future Expectations should be considered when developing a Plan for completion of this Element

If a particular "Expectations" item is not applicable, enter "N/A" in the Degram (Need Date) Timing field. Additional lines have been left blank, and may be used by Teams to add additional Expectations. Actions/Tasks to satisfy an Expectation may not to be IN PROCRESS before they become due. Teams may enter "% complete", or similar rating, for their own use in tracking progress/status if desired.

| Item | Ford | Supplier | Open | Close | Issues / Comments Hisks | Corrective Actions / Resolution Plan |
|------|----------|----------|-----------|------------|---------------------------------------------|-------------------------------------------------|
| 4 | T. Jones | F. Smith | | - ' | CCAR List - Item # 08 | See CCAR list - Item 8 |
| 5 | A. Nume | H. Putt | - | - | AIMS Lacue Number - 21835489 | See AIMS Issue Number - 21835489 |
| 6 | T. Jones | - | - | - | Reference an Equivalent Program Issues Deck | See Equivalent Program Issues Deck |
| 7 | K. Mann | H.Putt | 15-Jun-99 | 12-Avag-99 | Write Issue / Comments / Risks here | Write Corrective Actions / Resolution Plan here |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Advanced Product Quality Planning Release Level: 3.0

Ford APQP Guideline (copyright ©, 2001)

Page 70 of 83

March 2001 Uncontrolled Copy

APQP Program Risk Assessment

| | Milestone | |
|---------------------------|------------------------------------|--------------------------------|
| | | |
| System/Sub-System/Part | | |
| Affected APQP Elements | | Overall Program Risk: R Y |
| List all functional activ | rities affected by the concern(s). | |
| Bullet Point risks and | corresponding potential impact | to the program. |
| | | + |
| | | |
| | | |
| | | |
| | | |
| Recommend appropri | ate action (e.g., engrg. change, | allocate additional resources, |
| etc.). | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Key: Red: High Risk - Target dates and/or deliverables are at risk. A recovery work plan is not available and/or implemented, or the work plan does not achieve program targets.

Yellow: Moderate Risk - Target dates and/or deliverables are at risk, but a resourced recovery plan has been developed to achieve program targets, and has been approved by the appropriate Management Team.

Appendix C: Glossary of Terms

Glossary of Terms

1PP Build

The First Pre-Production units built at the assembly plant approximately 4 Months Before Job #1 (MBJ1). Considered Pre-Launch units.

Change Cutoff <CC> *

An FPDS Milestone. By the <CC> milestone, preliminary Engineering Signoff is completed including: CP durability testing, with known changes from the CP containable for the 1PP build, the initial set of road tests are completed, the design is at Job #1 level with "no further design changes except 'No Builds'", engineering confidence that objectives will be met is declared, and the Management drive is complete. In addition, color/graining tooling is authorized. Supplier commits to support the 1PP build with PSW parts, and the decision to support lifetime runs, changeover tooling, etc., is required.

Component

The individual parts that are linked or integrated into a vehicle, system or subsystem.

Confirmation Prototype (CP) *

An FPDS Event. At the (CP) event, prototype parts and assembly tools / ergonomics / process sheets are "Make like production" (to the extent feasible). The first CP's are available for tuning and durability testing. Coordinate measuring machines (CMM) analysis is complete for all CP end-items and subassemblies. P/T makes commitment to support Production Validation (PV) with Part Submission Warrant (PSW) parts.

Control Plan

A written description of the system for controlling processes producing products for Ford. A Control Plan describes a producer's quality planning actions for a specific product or process. The Control Plan lists all process parameters and part characteristics that require specific quality planning actions. A Control Plan contains all applicable Critical and Significant Characteristics.

Critical Characteristic

Production requirements (dimensions, performance tests) or process parameters that can affect compliance with government regulations or safe vehicle/production function, and which require Special Controls, i.e. specific supplier, assembly, shipping or monitoring actions to be included on Control Plans.

Criticality

A relative measure of the combined influence of the consequences of a failure mode (Severity) and its frequency (Occurrence). The product of Severity times Occurrence.

Customer

The next operation, department, person or company, whether internal or external, that receives or purchases products or services.

Dynamic Control Planning (DCP)

A methodology that ensures that customer expectations in the form of product design requirements are understood, deployed and controlled in the manufacturing and assembly processes. A team approach is used for the step-wise understanding and control of manufacturing process and products.

Design Freeze

A point in time determined by the Program Management when the design must be completed to support a prototype test program. Changes following the frozen design are not accepted without agreement from the Program's Chief Engineer and Program Manager.

Element

Specific documents, tasks and disciplines which must be completed to support the customer's program.

Fault Tree Analysis

A deductive analytical technique that uses a graphical tree to show cause and effect relationships between a single undesired event (failure) and the various contributing causes.

Field Evaluation Units (FEU)

Pre-Launch units built at the assembly plant around 3.5 Months Before Job #1 (MBJ1).

Ford Product Development System (FPDS)

The Process Definition, Deliverables, and Timing that was developed and is used by Ford Motor Company to develop/revise products. The timing for this process covers the Product Development cycle from Kick-off to Job #1.

Gantt Timing Chart

A bar chart used to describe timing of elements, events, and milestones in a visual manner.

Job #1 Achieved (J1) *

An FPDS Event. By the (J1) event, the integrated launch is complete. Initial operator training is complete, and is continued through ramp-up. In-process and final quality indicators meet program objectives. Powertrain Production Validation (PV) is complete in support of PTO plant's Job #1. Field Evaluation Unit (FEU) drive is complete. New Overall Vehicle Audit (NOVA-C) score of < 3 is obtained, and CAE models are correlated and the bookshelf is updated.

Kick-OFF (KO) *

An FPDS Milestone. (KO) is the beginning of the program and program specific work.

Launch Readiness <LR> *

An FPDS Milestone. By the <LR> milestone, Final Engineering Signoff (excluding Certification/Safety documentation) is completed including: Functional objectives met, final road tests completed, and formal Certification / homologation (except emissions) testing is completed. This is readiness to proceed to Tool Try-Out (TTO), 1PP and Job #1. Confirmation Prototype (CP), and Hard Tooled Functional Build (HTFB) issues are resolved. All production assembly tools have been functioned at the tool source or in homeline. Color / texture / gloss signoff is complete, and 100% PSW-1 parts are available for the 1PP build.

Launch Signoff <LS> *

An FPDS Milestone. By the <LS> milestone, analytical models are correlated with Confirmation Prototype (CP) test results. Tool Try-Out (TTO) and the 1PP Build are complete. Assembly plant tools and process verification is complete including aids & fixtures. New Overall Vehicle Audit (NOVA-C) score < 5 on manufacturing controlled items is obtained. Manufacturing assessment of full production feasibility is determined.

Lessons Learned

Problems, mistakes, things gone wrong/right (TGR, TGW) learned from reviewing similar part data. Information is gathered from government regulations, safety information, in-plant manufacturing data, G8D's, ES test data, user plant data, warranty data, field data, service data, campaigns, recalls or other sources of information.

Mistake Proofing

Techniques that use simple and inexpensive devices to prevent errors before they occur or detect errors and defects that have occurred.

Overall Equipment Effectiveness (OEE)

A combined analysis (or estimate) of Equipment Availability, Performance Efficiency, and Quality Rate which is meant to be used as a tool to track machine improvement progress. Included in the analysis are Total Available Time, Planned Downtime, Unplanned Downtime, and Ideal Cycle Time.

Percent Indices which are Process Capable (PIPC)

The number of characteristics, which are process capable, divided by the total number of characteristics being checked, multiplied by 100.

Percent Inspection Points which Satisfy Tolerance (PIST)

PIST is the number of conforming inspection checks divided by the total number of checks made, times 100.

Poka-Yoke

A particular method of Mistake Proofing developed by the Japanese.

Product to Process Characteristic Linkages

A statistical relationship between product characteristics and key process characteristics. These relationships are found by using tools such as scatter plots and designed experiments.

Product Quality Timing Plan

A supplier initiated plan that supports all elements of the APQP process. This plan includes supplier tasks, assignments, events, and timing required to ensure that system, subsystem or component meets customer expectations.

Product Readiness <PR> *

An FPDS Milestone. By the <PR> milestone, there is a full vehicle analytical sign-off that all objectives can be met. The last Class I surfaces are verified and released for major formed parts. Final Math 1, 2, & 3 data is released. The launch plan is confirmed and issued. CAD files reflect Pre-(CP) verification changes, and the Data Control Model is signed off.

Program Approval <PA> *

An FPDS Milestone. By the <PA> milestone, themes are approved for interior and exterior appearance (all trim levels). All targets become objectives. Facilities and tooling investments are approved. Marketing is committed to net revenue, and initial ordering guide is available. Program Design Verification Plans (DVP's) and Failure Mode and Effects Analyses (FMEA's) are to be complete. Program Parts List (PPL) is complete. Powertrain cross-section design is complete with manufacturing sign-off, and the final prototype (AP/CP) plan is available.

Program Metrics Tracking and Trends

A supplier led team defines and monitors the status of key metrics used throughout the APQP process. Metrics may include cost, weight, quality targets, mean time to failure (MTTF), reliability growth curves, 8D status, CR/CR status and functional performance.

Program Need Date

The last possible date the elements can be completed and not adversely affect quality or timing of a program.

Proportions & Hardpoints <PH> *

An FPDS Milestone. By the <PH> milestone, proportions are to be frozen, and hardpoints are to be selected. The package for people and cargo is to be frozen. Hardpoints and structural joint designs are compatible with all program targets. Level 2 subsystem targets are committed, and appearance themes have been reviewed in market research (interior / exterior).

Prototype

An initial or original model from which subsequent copies are made or improved models are developed.

Significant Characteristic

Product, process, and test requirements which are important for customer satisfaction and for which Quality Planning actions must be addressed, in a Control Plan.

Special Characteristics

Product and process characteristics designated by the customer, including governmental regulatory and safety, and/or selected by the team through knowledge of the product and process.

Strategic Confirmation <SC> *

An FPDS Milestone. By the <SC> milestone, Vehicle / System / and Level 1 Subsystem targets are committed. Powertrain line-up is selected. Manufacturing assembly locations for each derivative are confirmed. All system / subsystem suppliers are selected, and should be part of the team. Long lead funding has gone to the Board of Directors, and an initial Attribute Prototype (AP) / Confirmation Prototype (CP) plan is available.

Strategic Intent <SI> *

An FPDS Milestone. By the <SI> milestone, Strategies for product, market, manufacturing, supply, design and reusability are confirmed. Major customer/corporate wants and regulatory requirements compliance plans are done. Compatible vehicle level target ranges and product assumptions are established consistent with Affordable Business Structure (ABS) - including Craftsmanship. Appearance Stakeholder Team commits to appearance image. New technologies are identified, P/T and vehicle architecture are implementation ready, and program logistics are confirmed for timing, workplan, resources, and facilities.

Subcontractor

Providers of materials, parts, or services to a supplier.

Subsystem

A major part of a system which itself has the characteristics of a system, usually consisting of several components.

Supplier

A provider of production materials, parts or service parts.

Surface Transfer (ST) *

An FPDS Event. By the (ST) event, approved themes are refined for craftsmanship execution (consistent with <PA> Objectives). Interior and exterior Class IA surfaces are transferred to engineering (+/- 0.5 mm), and the Phased Data Notification process is initiated.

System

A set of interdependent subsystems or parts linked to perform a specific function.

Things Gone Right (TGR)

Product attributes or characteristics that produce a positive reaction from customers.

Things Gone Wrong (TGW)

Product attributes or characteristics that produce a negative reaction from customers. TGW includes both components and correct component functions that do not meet customer expectations.

* All FPDS Milestone/Event descriptions have been provided for your information. Any discrepancies between these descriptions, and those found in FPDS documentation after the publish date of this Glossary should be investigated, and the FPDS definition is to supersede this description.

Appendix D: References and Websites

References & Web Sites

AIAG APQP

Automotive Industry Action Group - Advanced Product Quality Planning and Control Plan Reference Manual (Chrysler, Ford, General Motors)

Second Printing, February 1995

Ford Intranet:

http://www.ctis.ford.com/fao_qualstandard/secure1/data/3223691.pdf

External Internet:

http://www.aiag.org

AIAG MSA

Automotive Industry Action Group - Measurement System Analysis Reference Manual (Chrysler, Ford, General Motors)

Second Edition, February 1995

Ford Intranet:

http://www.ctis.ford.com/fao_qualstandard/secure1/data/3224691.pdf

External Internet:

http://www.aiag.org

AIAG PFMEA

Automotive Industry Action Group - Potential Failure Mode and Effects Analysis Reference Manual (Chrysler, Ford, General Motors)

Second Edition, February 1995

Ford Intranet:

http://www.ctis.ford.com/fao_qualstandard/secure1/data/3224766.pdf

External Internet:

http://www.aiag.org

AIAG PPAP

Automotive Industry Action Group - Production Part Approval Process (PPAP) (Chrysler, Ford, General Motors)

Third Edition, September 1999

Ford Intranet:

http://www.ctis.ford.com/fao_qualstandard/secure1/data/3225266.pdfv

External Internet:

http://www.aiag.org

AIAG QS-9000

Automotive Industry Action Group - Quality Systems Requirements QS-9000 (Chrysler, Ford, General Motors)

Third Edition, January 1999

Ford Intranet:

http://www.ctis.ford.com/fao_qualstandard/secure1/data/3225316.pdf

External Internet:

http://www.aiag.org

AIAG SPC

Automotive Industry Action Group Statistical Process Control (SPC) (Chrysler, Ford, General Motors)

Second Edition, March, 1995

Ford Intranet:

http://www.ctis.ford.com/fao_qualstandard/secure1/data/3225741.pdf

External Internet:

http://www.aiag.org

AIAG Tooling & Equipment - Automotive Industry Action Group - Tooling & Equipment Supplement (Chrysler, Ford, General Motors)

Second Edition, June 1998

Ford Intranet:

http://www.ctis.ford.com/fao_qualstandard/secure1/data/ 3225144.pdf

External Internet:

http://www.aiag.org

APQP

Advanced Product Quality Planning - Resource Center

Ford Intranet:

http://www.dearborn2.ford.com/apgpcntr/

DCP

Dynamic Control Process - Powertrain

Ford Intranet:

http://www.ptoquality.ford.com/dcp/default.htm

FPDS

Ford Product Development System

Ford Intranet:

http://www.fpds.ford.com

External Internet:

https://web.fpds.ford.com/fpdsonline/

FPS

Ford Production System

Ford Intranet:

http://www.fps.ford.com/html/inf/fps/index.html

FRG

Ford Reliability Guide

Ford Intranet:

http://www.dearborn2.ford.com/avtqual2/frg

FTEP

Ford Technical Education Program - Design Verification Plan & Process Verification (DVP & PV)

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

FTEP

Ford Technical Education Program - Experimental Design

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

FTEP

Ford Technical Education Program - Failure Mode and Effects Analysis

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

FTEP

Ford Technical Education Program - Process Control Methods

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

FTEP

Ford Technical Education Program - Reliability

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

FTEP

Ford Technical Education Program - Robustness: Parameter Design

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

FTEP

Ford Technical Education Program - Robustness: Tolerance Design

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

FTEP

Ford Technical Education Program - Systems Engineering Fundamentals

Ford Intranet:

http://www.fdi.ford.com

Ford Training and Development Center:

http://www.dearborn3.ford.com/ftdc/

OEE

Overall Equipment Effectiveness

Ford Intranet:

http://www.fps.ford.com/measureables/reference/gem/index.html

PTPRP

Powertrain Program Review Process

Ford Intranet:

http://www.ptprocess.ford.com/

RVT

Research & Vehicle Technology - AVT Knowledge Base

Ford Intranet:

http://www.avt.ford.com

STA

Supplier Technical Assistance Program - Ford Supplier Network

Ford Intranet:

http://www.purchasing.ford.com/

External Internet:

https://fsn.ford.com/