



HAMPTON ROADS DISTRICT CITY OF CHESAPEAKE PROJECTS

Phase 2 Concept Screening Meeting | HR01














Introductions and Project Schedule

No-Build Conditions Review

**HR01 Concept Screening** 

MetroQuest Survey

HR02 Follow Up

Conclusions and Next Steps









## **Project Pipeline - Overview**

### **Program Goals:**

- Focus planning/project development on CTB VTrans priorities
- Streamline project planning and improve project readiness
- Improve and develop tools to make use of powerful data and improve collaboration
- Solve more problems with limited transportation dollars

Project Pipeline builds on the success of VDOT's STARS program

STARS recommendations submitted in SMART SCALE have had an 80% funding success rate

### Phased Approach to Study Process • PRPT- Planning and Investment Planning and









preferred

alternatives

### Phase 1 (Complete)

- **Broad analysis** to understand problems (VTrans needs) and the causes
- Develop range of possible alternatives to improve performance

We are here

#### Phase 2

(Nov – Feb)

- Stakeholder/Public engagement and feedback
- Sketch level analysis to narrow options then detailed analysis
- Planning level estimates and identify preferred alternatives

### Phase 3

(Mar – May)

- Investment strategy cost estimation and refinement
- Finalize multimodal investment strategy/deliverables

Methods Solutions High level analysis of Hand sketch level data dashboards concepts, targeted desktop field review approach - no politics Detailed analysis Conceptual sketches for to screen

concepts

Final refinement, address risks and finalize estimates









# **Overall Schedule and Major Milestones**

- Completed to-date: Existing and No-Build Conditions Analysis, Preliminary Concept Development and Screening
- January February: Concept Screening and Refinement
  - Full SWG Meeting (today)
  - MetroQuest Survey opening mid to late February
- February March: SWG Meeting
  - MetroQuest Results and selection of preferred alternative
  - Draft study summary of Phase 2
  - Identified Phase 3 risks
  - One-page preliminary draft summary sheets of preferred alternatives
  - Phase 3 Scope outline / highlights










# **MetroQuest Survey**

- MetroQuest survey can incorporate any new concepts discussed during this SWG meeting
- MetroQuest survey will be open from 2/24 to 3/10
- MetroQuest survey to stakeholders by Thursday 2/10











# **No-Build Conditions Methodology**



No-Build 2045 volumes developed using agreed upon linear growth rates









# Corridor Concept Screening



Pedestrian and bicycle facility improvements



- Pedestrian signal head
- Signing and marking improvements










# **Intersection Concept Screening**



Concepts developed for the following intersections with Battlefield Boulevard:

- Wal Mart Way
- Volvo Parkway
- Byron Street / Thrasher Road
- Gainsborough Square













# **Concept Screening Analysis Assumptions**

### Analysis Periods

- 2045 AM peak hour (7:30-8:30 am)
- 2045 PM peak hour (4:30-5:30 pm)

### Analysis Tools and Measures of Effectiveness

- Preliminary screening using VJuST
- Traffic Analysis
  - Synchro 10 (control delay and Level of Service)
- Crash Analysis
  - Latest five years (2015-2019)
  - F+I CMFs from SMART SCALE Planning, Virginia State Preferred, and Clearinghouse CMF lists

LOS	Unsignalized Intersection Criteria					
A or B	Delay ≤ 15 sec/veh					
C or D	15 sec/veh < Delay ≤ 35 sec/veh					
E or F	Delay > 35 sec/veh					
	•					
LOS	Signalized Intersection Criteria					
A or B	Delay ≤ 20 sec/veh					
C or D	20 sec/veh < Delay ≤ 55 sec/veh					
E or F	Delay > 55 sec/veh					










## 2045 No-Build Conditions Needs Identification



- Byron St/Thrasher Rd results in LOS F for the worst movements
- Operational issues clustered towards the northern end of the corridor
- Optimization of splits and offsets










## **Priority Intersections: 2015-2019 Crash Summary**







- Angle crash trend at Byron St and Thrasher Rd
- Rear end collision trend along Battlefield Blvd from Volvo Pkwy to Wal Mart Way





AM: +0.9s delay

PM: +0.5s delay









\$3,500,000 - 4,500,000

## **Wal Mart Way:** Concept 1 – I-64 Ramp Rerouting

#### **Design Considerations**

- Vehicle rerouting 50% of SB U-turns at Volvo Parkway
- Access impacts improve access to **businesses**
- Safety





AM: -16.1s delay

PM: -8.6s delay










## **Wal Mart Way:** Concept 2 – Access Management

### **Design Considerations**

- Access impacts
- R/W and utility impacts
- Risks
- Pedestrian impacts

CMF = 0.565-Year F+I Crash Reduction = 15.8 crashes



**Stage 1 Cost Estimate Range:** \$300,000 - 600,000










## Wal Mart Way: Concept Screening Summary

- MetroQuest survey to present:
  - 1-64 Off-Ramp Rerouting
  - 2 Access Management near Wal Mart Way





## **Volvo Parkway:** Concept 3 – Full **Displaced Left-Turn**

### **Design Considerations**

- Vehicle rerouting
- Access impacts
- R/W and utility impacts
- Pedestrian impacts

CMF = 0.85-Year F+I Crash Reduction = 9.4 crashes











#### **No-Build Results**




#### **Concept Results**



#### **Overall Intersection**

AM: -83s delay PM: -55.7s delay



**Stage 1 Cost Estimate Range:** \$22,000,000 - 30,000,000







Partial DLT displaces the


N/S left-turn movements




## **Volvo Parkway: Concept 4 – Partial Displaced Left-Turn**


### Design **Considerations**

- Vehicle rerouting
- Access impacts
- R/W and utility impacts
- Pedestrian impacts
- Volvo Pkwy concurrent left turns



### **No-Build Results**







### **ETT Results**

#### **Overall Intersection**

AM: -66.6s delay PM: -24.6s delay **Stage 1 Cost Estimate Range:** \$14,000,000 - 20,000,000





5-Year F+I Crash Reduction = 4.7 crashes

CMF = 0.9

VDOT

BATTLEFIELD BLVD







## **P** PROJECT PIPELINE

Benefit is no left-turning traffic

off Battlefield Blvd, less conflict

points, more green time


allocated to other phases

**Volvo Parkway: Concept 5 – Partial Quadrant** 

### **Design Considerations**

- Vehicle rerouting N/S left-turn
- Minor street impacts Phase 3 intersection control

**Concept Results** 



 
D
D
Battlefield Blvd E C ♣ РМ АМ

**ETT Results** 

CMF = 0.915-Year F+I Crash Reduction = 4.2 crashes **Overall Intersection** 

AM: -50.4s delay PM: -10.4s delay

Medians reduced to make room for eastbound and westbound concurrent lefts

**Stage 1 Cost Estimate Range:** \$10,000,000 - 14,000,000

Volvo Pkwy left-turns maintained, phasing changed to concurrent

Two-phase signal, right-out only from Coastal Way BATTLEFIELD BLVD

PM

Battlefield Blvd

PM AM









# **Volvo Parkway: Concept Screening Summary**

	Concept	Estimated 5- Year Crash Reduction		Ped & Bike Accommodation	Cost	Approach	Difference in Delay from No-Build		Notes
			ction				AM	PM	
	Full DLT	9.	.4	-	\$\$\$	Intersection	-83s	-55.7s	ROW Impacts
_	Partial DLT					EB	-28.8s	-93.8s	Consument phasing on Value Divisi
						WB	-5.8s	-22s	
		4.7	.7	-	\$\$	NB	-26.5s	-32.5s	Concurrent phasing on Volvo Pkwy ROW Impacts
						SB	-126.0s	+11s	
						Intersection	-66.6s	-24.6s	
	Quadrant	4.2		+	\$	EB	+8.9s	-67.1s	Minor street impacts
						WB	+29.8s	+8.2s	
						NB	+1.6s	-20.9s	
						SB	-130.8s	+11.0s	
						Intersection	-50.7s	-10.4s	
ike/Ped Accommodations Compared to No-Build								•	
			Cost	Build LOS		EB	D (54.7s)	F (129.5s)	
_	Negative Impact	\$	Low	LOS A-B		WB	C (28.0s)	D (48.7s)	
			2017		2045 No-Build	NB	D (39.2s)	E (63.2s)	
0	Neutral Impact	\$\$	Moderate	LOS C-D		SB	F (159.8s)	D (46.2s)	
+	Positive Impact	\$\$\$	High	LOS E-F		Intersection	F (90.7s)	E (65.0s)	











## **Volvo Parkway: Concept Screening Summary**

- MetroQuest survey to present:
  - Partial Displaced Left-Turn
  - 2 Quadrant Intersection









Minor street movements

converted to right-turn only

PROJECT PIPELINE - HR01

NORTH BATTLEFIELD BLVD AT THRASHER ROAD AND BYRON STREET





Unsignalized

VDOT


Reduction in conflict points, improved minor street operations

## **Byron St/ Thrasher Rd:** Concept 6 - RCUT


### **Design Considerations**

- Vehicle rerouting
- Access impacts
- Discuss closing median

### **Concept Results**




ы ма Battlefield Blvd D AM



**Stage 1 Cost Estimate Range:** \$2,700,000 - 3,300,000

BATTLEFIELD BLVD



CMF = 0.455-Year F+I Crash Reduction = 11.5 crashes










## **MetroQuest Survey**

- Ped/Bike Improvements
- I-64 Off-Ramp rerouting vehicles at Wal Mart Way
- Access Management near Wal Mart Way
- Partial DLT at Volvo Pkwy
- Partial Quadrant at Volvo Pkwy
- RCUT at Byron St/Thrasher Rd











# **Next Steps**

- Finalize and launch MetroQuest survey comments due Feb. 15, live Feb. 24
- Process MetroQuest results
- Begin drafting Phase 2 project summary sheets
- Identify Phase 3 risks



