



Hey Construction, Let's Influence Design and Drive Innovation!

# Charlie Dunn DPR Construction

Steve Gantner
Conspectus, Inc.

David Stutzman
Conspectus, Inc.





#### Earn CE hours for this Session

#### Participants must:

- 1. Sign in using attendance sheet in the back of the room.
- 2. Attend at least 95% of the session.
- 3. Complete the session and post-program evaluation.

Additional instructions will be emailed to attendees requesting CE credits. If requesting AIA credits, please provide your AIA number so we can report your attendance. For questions regarding continuing education credits, please contact **Jo-Anne Torres**, Manager of Professional Development and Continuing Education, at **jo-anne.torres@agc.org**, or (703) 837-5360.



#### Earn CE hours for this Session





**1.0 AIC CPD Credit** | AGC of America has been approved to offer Continuing Professional Development (CPD) credits for qualifying programs by the <u>American Institute of Constructors</u> (AIC).



**1.0 AIA Learning Unit (LU)** | The Associated General Contractors of America is a registered provider of AIA-approved continuing education under Provider Number G523. All registered AIA CES Providers must comply with the AIA Standards for Continuing Education Programs.



AGC of America is registered with the National Association of State Boards of Accountancy (NASBA) as a sponsor of continuing professional education on the <u>National Registry of CPE Sponsors</u>. This session is designated for **1.0 CPE credit** in the field of Communications and Marketing.



# **Learning Objectives**

By the end of this session, participants will be able to:

- 1. Discuss how the relationship and process of the specifier and a conceptual estimator, working alongside the design team and owner, encourages questions, reveals answers, and drives innovation.
- 2. Demonstrate how organizational FORMATS already in existence will be used in new and innovative ways to revolutionize the way the design and construction industry delivers the written portion of Construction Documents.
- 3. Recommend comprehensive participation by all parties, resulting in time and cost saving benefits.
- 4. Implement an open and transparent discussion among the Contractor, Estimator, Owner, Specifier, and Supplier.



# **Case Study**

#### **Urban Apartment Building**



#### **Concept Design**


15 Stories plus penthouse

91 Apartments

142,600 GSF

\$45,600,000 to \$53,700,000

17% budget range



#### Schematic Design


18 Stories plus penthouse

112 Apartments

169,500 GSF

\$55,000,000


Same height as Concept Design





#### **Order of Decisions/Documents**







The	Rethink	<b>Moment</b>						
Specification								

В	SHELL		LOD		=stimate	•	G CTO
B20 B2010 B2010.A	EXTERIOR ENCLOSURE EXTERIOR WALLS PODIUM WALLS		100	Drainable EIFS on gypsum sheathing on steel studs	15,000 SF	40.0	600,000
52020#X	Description	Drainable EIFS on gypsum sheathing on metal studs					600,000
	Performance Requirement	s Drainable R19 cavity and R7.5 continuous insulation	200	Drainable EIFS on gypsum sheathing on steel studs	15,000 SF	40.0	600,000
				Cavity insulation, R19	15,000 SF	1.5	22,500
				Continuous exterior insulation, R7.5	15,000 SF	3.00	45,000
							577,500
072410	Components EIFS	Description Drainable system 2" insulation, WRB adhesive custom color	300	Drainable EIFS on gypsum sheathing on steel studs	15,000 SF	12.00	180,000
061600 054000 072100	Sheathing CFMF Blanket Insultation	5/8" glass mat gypsum board 6" steel studs, 43 mil think minimum 6" foil faces glass fiber; R21		Glass mat EIFS	15,000 SF	3.50	52,500
092900 079200	Interior Skin Sealant Joints	5/8" gypsum board Low-modulus silicone; standard colors		2" insulation, R7.5 Adhesive membrane Fluid applied exterior coating	15,000 SF 15,000 SF	3.00 2.50	45,000 37,500
	WNOVAT/ON			Custom color Batt insulation, 6", R2: Joint sealant	15,000 SF L 15,000 SF 15,000 SF	12.50 1.75 0.85	187,500 26,250 12,750
100	2021 THE CONSTRUCTION						541,500



Hey Construction! Let's Influence Design and Drive Innovation

#### Target Value Design


Legend:

Progress Estimate

Final Estimate of Design Phase

Owner Construction Budget

- All-Hands OAC Design / Estimate Review
- Major Design Options Cost Analysis







54 months

#### CHALLENGE & OPPORTUNITY




30 months



#### **WORK PACKAGING @ BSPB**


Area-Loc	Scope	Program	Element	Uniformat 5	Description	Takeoff Quantity	Labor Cost/Unit	Labor Price	Labor Amount	Material F		
100					Office Building	####### SF	38.70 /SF		3,900,562			
	200				Shell	100,800.00 SF	8.03 /SF		809,823			
77		B1000.9010			Steel Frame Structure	655.00 tn	162.02 /tn		106,124			
			B1010.001		Steel Frame	lb	/lb		18,144			
				A1010.10.1	Continuous Footings	су	icy					
					Continuous Footings	60.00 cy		1.41	-	2		
				A1010.30.1	Spread Footings	су	/cy		18,144			
				A1020.80.1	Grade Beams	су	lcy					
				A4010.10.1	Slab On Grade	sf	/sf					
				A6010.20.1	Perimeter Sub Slab Drainage							
				B1010.10.5	Structural Steel	655.00 tn	/tn					
.0				B1010.10.5	Slab on Metal Deck	sf	/sf					
. 1	11/11/			B1010.20.4	Metal Decking	sf	/sf					
	Fy 11 1			B1010.20.9	Equipment Pads	sf	/sf					
	M. In All			B1010.90.5	Fireproofing	sf	/sf					
				B1020.20.3	Lightweight Insulating Fill	sf	/sf					
ATT CONTRACTOR	1. 111/10	WEBBE		B1090.10.1	Miscellaneous Steel	sf	/sf					
		THE REAL PROPERTY.	B1010.005		Stairs	ea	/ea					
	小面看		D1010.010		Elevator Core: Office	ea	/ea					
			D2000.005		Plumbing Shell	sf	/sf		63,180		70,381	
	2777	1 1	D4000.005	ļ.	Fire Protection Shell	sf	/sf	Define Locations & Refi				
			Z1050.021		Project Requirements Shell	mo	/mo	Model Register	esh Models			
	FRIEDRY.				Balconies	2,450.00 sf	/sf	1 2 3	4			Elevation
-		1	B1100.010		Balconies	sf	/sf	Project	red (4)			1020'-1 : 1020'-1 :
The state of the s			B2090.0100		Exterior Skin Specialties	sf	/sf	<b>6</b> H	Unnamed (1)			1020'-17
					Exterior Skin System: Metal Panel /	67,500.00 sf	10.43 /sf		named (2) BPB_Level 11			1020'-1 7 12
			B2010.005		Stone Veneer System	6,050.00 sf	/sf		BPB_Level 10			1222'
			B2010.011		Metal Panel System	27,600.00 sf	/sf		BPB_Level 9			12 1193'
			B2020.005		Sliding Window Wall System	800.00 sf	863.78 /sf		BPB_Level 8 BPB_Level 7			1193
			B2020.010		Curtainwall	12,000.00 sf	/sf		BPB_Level 6			1164
			B2050.005		Exterior Entry Doors	2.00 ea	/ea		BPB_Level 5 BPB_Level 4			11 1135'
			B2050.011		Exterior Door Assemblies	20.00 ea	633.60 /ea		BPB_Level 3			11
			B2050.0886		Exterior Storefront	21,050.00 sf	/sf		BPB_Level 2			11 1088'
			B2090.0100		Exterior Skin Specialties	67,500.00 sf	/sf		BPB_Level 1 BPB_Basement			1088
		B3010.0100			Built Up Roofing	24,850.00 sf	/sf		BPB _Vivarium			1063'-
1.17	51 015 1 5 5 1		B3010.015		Built Up Roofing: Steel Frame Office e/Program/Element/Uniformat5	24.850.00 sf	/sf	& Unn	BPR_Below Vivarius	m		1020'-1 7/ 4'-9 9/1

#### **WORK PACKAGE: BASEMENT WALLS**




D	E	F	G	Н	I	J	K	L	М
GMP REC	ONCILIATION								
		iGMP1 SUBMITTAL		on 10/20/2014 Orawings	iGMP2 SUBMITTAL	Based on 2/2 Overlay for iGMF			
Pricing Updated			UM	Total Cost	Oty	UM	Total Cost	Qty Change FROM BUDGET TO iGMP2	Cost Change FROM BUDGET TO iGMP2
2/27/2015	BASEMENT								
2/27/2015	CAISSONS	1,825	LF.	\$ 710,227	1,845	LF	\$ 718,297	20	\$8,070
2/27/2015	CONTINOUS FOOTINGS	374	CY	\$ 66,703	200	CY	\$ 48,277	(174)	(\$18.426)
2/27/2015	GRADE BEAMS	319	CY	\$ 64,316	552	CY	\$ 115,400	233	\$51,085
2/27/2015	ELEVATOR PIT MATS	35	CY	\$ 8,416	25	CY	\$ 7,747	(10)	(\$669)
2/27/2015	VIVARIUM MAT FND: 46" THICK	-	CY	s -	150	CY	\$ 32,533	150	\$32,533
2/27/2015	LOWER VIVARIUM/BASEMENT WALLS	10,636	SF	\$ 262,889	11,010	SF	\$ 278,239	374	\$15,350
2/27/2015	2/27/2015 CORE / ELEVATOR WALLS 4,506 SR		SF	\$ 186,728	3,700	SF	\$ 194,243	(806)	\$7,515
2/27/2015	BASEMENT COLUMNS	125	CY	\$ 55,882	127	CY	\$ 57,854	2	\$1,973

Α	В	С	D	E	F	G	Н
Bid	<u>Description</u>	Bid Quan	Unit	Unit Cost	TTL \$	Manhours	<u>CYDS</u>
21	CAISSONS	1,825.000	LNFT	\$477.48	\$871,399	2,350	3,900
22	CONTINOUS FOOTINGS	374.000	CY	\$238.73	\$89,286	610	374
23	GRADE BEAMS	319.000	CY	\$269.88	\$86,091	846	319
24	ELEVATOR PIT MATS	35.000	CY	\$321.88	\$11,266	94	35
31	BASEMENT WALLS	10,636.000	SF	\$33.10	\$352,077	3,094	700
32	CORE / ELEVATOR WALLS	4,506.000	SF	\$55.49	\$250,047	2,206	292
41	BASEMENT COLUMNS	125.000	CY	\$598.77	\$74,846	480	125
51	VIVARIUM LEVEL SOG	780.000	SF	\$35.15	\$27,418	154	16
52	BASEMENT LEVEL WASTE SLAB	16,808.000	SF	\$7.06	\$118,640	305	226
100	LEVEL ONE						
101	BASEMENT SOG	16,808.000	SF	\$7.17	\$120,586	798	454
102	SHORED SLAB	19,087.000	SF	\$31.19	\$595,417	5,479	771
103	CORE WALLS	3,406.000	SF	\$28.51	\$97,108	1,002	170
104	LEVEL ONE CONTINOUS FOOTINGS	64.000	CY	\$483.78	\$30,962	346	64
105	SHEAR WALLS	16,223.000	SF	\$37.10	\$601,912	4,900	663
106	COLUMNS	125.000	CY	\$605.05	\$75,631	494	125
107	SOG 12" Loading Dock 4' AFF	2,934.000	SF	\$10.58	\$31,030	227	120
108	30" Walls	2,723.000	SF	\$37.18	\$101,243	906	279
110	4" Built up Slab	1,954.000	SF	\$32.24	\$63,007	493	78
111	Loading Dock Walls	494.000	SF	\$36.67	\$18,113	203	20
112	West Ext Slab over Vivarium	1,093.000	SF	\$26.99	\$29,497	254	90
200	LEVEL TWO						
202	SHORED SLAB	19,586.000	SF	\$20.48	\$401,113	4,124	856
203	36" x 72" Beam at Loading Dock	354.000	SF	\$43.34	\$15,343	137	40
204	CORE WALLS	3,146.000	SF	\$28.44	\$89,460	892	156
206	COLUMNS	86.000	CY	\$694.31	\$59,710	464	86
208	SOMD	2,168.000	SF	\$6.05	\$13,108	93	39
300	LEVEL THREE						
302	SHORED SLAB	21,811.000	SF	\$27.00	\$588,843	6,512	866
304	CORE WALLS	3,146.000	SF	\$28.44	\$89,460	892	156
306	COLUMNS	86.000	CY	\$694.31	\$59,710	464	83
400	LEVEL FOUR						
402	SHORED SLAB	20,531.000	SF	\$19.60	\$402,342	3,785	813
404	CORE WALLS	3,146.000	SF	\$28.44	\$89,460	892	156




03\_iCAPP\_100% Complete






1	Name	Target									Actual			Predicted					Difference
2		Quantity	Unit	Production rate Deg	ree of comp Be	egin time	End point	Duration	- 1	MAN HOURS	Quantity	Unit	Production rate Begr	Begin time	End point	Duration			Production rate
3	WALLS				27.20%	3/24/2015	2/10/2016		302	2415.8				3/24/2019	2/24/2016		306	2362	
4	BWP01	2013.76	SF	465.9	100.00%	3/24/2015	3/30/2015		4.3	34.6	1/0/19	00 SF	435.4	3/24/2019	3/30/2015		5	40	-30.5
		2193.33		438.6	100.00%	3/27/2015	4/3/2015		5	40	1/0/19		365.6	3/27/2019			6	56	-73
	BWP03	1754.68		412.7	100.00%	3/31/2015	4/6/2015		4.3	34	1/0/19		311.9	3/31/2019	5 4/7/2015		6	48	-100.8
	BWP04	1740.45		316.4	100.00%	4/3/2015	4/10/2015		5.5	44	1/0/19		309.4	4/3/2019			8	64	-7
8	BWP05	1764.12	SF	320.7	100.00%	4/7/2015	4/14/2015		5.5	44	1/0/19	10 SF	352.8	4/7/2019			7	56	32.1
	BWP06	1981.45		428.3	100.00%	4/15/2015	4/21/2015		4.6	37	1/0/19	00 SF	352.3	4/16/2019			6	48	-76.1
10	BWP07	1713.59		548.2	100.00%	4/13/2015	4/16/2015		3.1	25	1/0/19		285.6	4/13/2019			5	40	-262.6
11	BWP08	1598.47		206.2	100.00%	4/15/2015	4/24/2015		7.8	62	1/0/19		319.7	4/15/2019			9	72	
	BWP09	1073.44	SF	260.1	100.00%	5/7/2015	5/13/2015		4.1	33	1/0/19		57.6	6/3/2019			3	24	-202.5
	BWP10	4514.94	SF	440.4	100.00%	5/5/2015	5/19/2015		10.3	82	1/0/19	00 SF	424.9	5/6/2019			13	104	-15.5
14	VWP01	1163.89	SF	265.8	100.00%	3/25/2015	3/31/2015		4.4	35				3/25/2019	3/31/2015		4.4	0	
15	VWP02	1108.41	SF	316.6	100.00%	4/1/2015	4/6/2015		3.5	28				4/1/2019	4/6/2015		3.5	0	
16	VWP03	743.71	SF	191.7	100.00%	4/8/2015	4/13/2015		3.9	31				4/8/2019	5 4/13/2015		3.9	0	37.1
17	L1-ECW	519	SF	75.5	100.00%	6/17/2015	6/25/2015		6.9	55				7/1/2019	7/14/2015		7.4	59	-5.1
18	L1-ESW	152.27	SF	25.3	100.00%	6/4/2015	6/12/2015		6	48.1				7/1/2019	7/9/2015		4.4	35	9.5
19	L1-WCW	2891.92	SF	537.9	55.80%	6/29/2015	7/7/2015		5.4	43				7/8/2019	7/16/2015		6.4	51	-84.2
53	SLAB ON GRAD	Œ			52.10%	5/4/2015	9/24/2015	1	36.9	1095				5/11/2019	9/29/2015		37.6	309	
54	S0G1	760.91	SF	8	38.90%	5/11/2015	9/24/2015		95.1	760.9	1/0/19	00 SF	65.5	5/11/2019	5/27/2015		12	96	57.5
55	"AHUPAD				100.00%	5/4/2015	5/11/2015		-5.4	43				7/1/2019			-5.4	43	
56	SOG 2A	244.1	SF	8	91.80%	5/22/2015	7/7/2015		30.5	244.1	1/0/19	00 SF	17.9	5/27/2019	6/10/2015		11	88	9.9
57	SOG 2B	0	SF	1	100.00%	6/1/2015	6/1/2015		- 1	8		0 SF	0.2	6/1/2019	6/5/2015		5	48	-0.8
58	SOGL1	2023.33	SF	415	0.00%	9/16/2015	9/22/2015		4.9	39				9/23/2019	9/29/2015		4.3	34	61.1
53	COLUMNS				6.40%	4/7/2015	2/22/2016	6	39.8	5118.6				4/7/2019	3/1/2016		631.9	4864	
	BCP 01		EΑ	1.6	100.00%	4/7/2015	4/10/2015		3.8	30				4/7/2019			3.8	0	
61	BCP 02	7	EΑ	1.4	100.00%	4/15/2015	4/21/2015		4.9	39				4/15/2019	4/21/2015		4.9	0	
62	BCP 03		EΑ	0.4	100.00%	4/30/2015	5/18/2015		12.6	101	1/0/19	00 EA	0.4	4/30/2019	5/20/2015		15	120	0
63	L1CP1	19	EΑ	8	100.00%	6/16/2015	6/18/2015		2.4	19				6/17/2019	7/7/2015		3.8	24	-1.7
64	L1CP2	26	EΑ	6.1	100.00%	6/9/2015	6/15/2015		4.3	34				6/11/2019	7/9/2015		7.1	40	-0.9
65	L1CP3	2	EΑ	0.9	100.00%	6/26/2015	6/30/2015		2.3	18				6/26/2019	6/30/2015		2.3	0	-0.2
107	CIP Deck				19.00%	5/26/2015	2/2/2016	2	35.6	1885.1				6/9/2019	5 2/12/2016	. 2	262.2	1921	
131	1																		
132	on on date of rep	ort 18.2%																	
133	on 11.1%																		
34	mpletion -7.2%						1												
135	re are only those	tied to schedule	9		_														
136																			

#### Planned Finish




Actual Finish



### Drive Innovation Through Collaboration





- · Facilitate design.
- Make informed decisions.
- Provide transparency.
- Transform behavior.
- Transform documents.
- Transform outcomes.





### What's Next?

- Life Cycle Data Feedback
- UniFormat
- Reusable Data and Design





## Thank you.

# Questions?

