# CH2MHILL。 Incheon Bridge Project

## ASCE Structural Engineering Conference - Iowa 10 November 2014



Andrew Yeoward – Global Director of Bridge Engineering, CH2M HILL


#### Contents

- Introduction to the Project
- Construction
- Role of the Contractors Checking Engineer (CCE)
- Conclusions



# Introduction to Project

#### **Project Location**





# **Project Location**





## **Project Details**



#### Crossing length 12.3 km

#### **Cable Stayed Bridge**

- 1480m total length
- 800m main span
- 74m high navigation clearance

#### **Approach Bridges**

- 1778m total length
- 145m span lengths

#### Low Level Viaduct

- 8400m total length
- 50m span lengths




#### **Project Details**

#### Project Statistics

- Total construction cost of €1.1 billion
- 52 month construction period
- Completion date of October 2009
- Contractors Checking Engineer (CCE) Role
- CH2M HILL Arup Dasan JV
- CH2M HILL lead consultant
- Period of service March 2005 to December 2009



## **Project Organisation**



#### CH2MHILL.

# Construction

# Site construction work area activities

# **Project Location**





#### **Site Construction Yard**

Concrete batching Concrete batching cutting and bending

Site offices and staff accommodation

Prefabricated pile reinforcement cage storage

CSB pylon precast cross-beams

Approach Bridge deck precast segment fabrication

50m viaduct deck precasting shed 1 unit every 2 days

50m viaduct deck storage and loading area

Approach Bridge pierhead segment precasting



#### **Pile Cage Prefabrication**






- Pile reinforcement cages fabricated in 12m lengths
- Link reinforcement rolled onto the pile cage
- Up to 3.0m diameter piles
- Accurate assembly allows the used of threaded couplers to join cages



#### **Balanced Cantilever Deck Segments**









• Short bed match casting



#### Viaduct Deck Spans (50m)







- Target 1 span every 2 days
- 3 stage fabrication
  - Reinforcement stage 1
  - Internal formwork + complete reinforcement
  - External formwork + stressing + concreting
- Longitudinally and transversely pre-tensioned 1400t each



# Construction activities on site

#### **Deep Water Piles**








- Piles constructed in up to 25m deep water
- Permanent steel casing to rock level
- Pile diameters between 1.8m and 3.0m

CH2MHILL.

#### **Shallow Water Piles**







- 2km long steel temporary access trestle
- Driven steel piles
- Access for construction of piles and cross beams



#### Pilecaps



- Pilecap precast formwork up to 1650t
  lifted using 3000t floating crane
- Precast formwork sealed onto steel pile casings - dry working area for fabrication of pilecap reinforcement
- Temporary pilecap working enclosure (upto 70mx25m in plan)









#### **Pilecaps**



- Temporary enclosure for pilecap concreting and curing
- Low level viaducts consist of pile bent and in-situ cross beam below deck level







#### Viaduct Deck





- 1500t viaduct deck units brought out to deep water using 3000t floating crane
- Loaded onto multi-wheel carrier
- Multi-wheel carrier moves deck unit out to launching girder operating in shallow water area inaccessible to floating crane
- Units lifted onto bearings
  using launching gantry

**CH2MHILL** 

# **Viaduct Deck**



#### CH2MHILL.


#### **Viaduct Deck Construction**





# **Viaduct Deck**







- Precast pier head segments erected using 3000t floating crane
- Precast deck segments lifted from barges using derrick cranes erected on the cantilever







































CH2MHILL.





# **Cable Stayed Bridge**





- 225m high pylons
  erected using self
  climbing jump formwork
- Backspan erected with 80m long large segments supported on temporary piers
- Mainspan cantilevered out in 15m segments

**CH2MHILL** 

## **Pylon Construction**



- Precast, post tensioned crossbeams
- In-situ connection to pylon legs







# **Pylon Construction**





## **Deck Construction - Side Spans**









### **Deck Construction - Main Span**







# Contractor's checking engineer

#### <u>INPUTS</u>

- Independent Design Check of the Permanent Works
- Independent Design Review of the Temporary Works
- Review Technical Notes produced by others
- Provide Technical Assistance to the Contractor

#### DELIVERABLES

- Design Check Certificates (DCC) for permanent works
- Design Review Certificates (DRC) for temporary works
- Design Review Certificates (DRC) for technical reports



#### Design Standards

#### 2 key documents

- Project Performance Requirements (PPR)
  - Written by the Ministry of Construction and Transportation
- Concessionaire's Supplementary Requirements (CSR)
  - Written by Incheon Bridge Company Ltd (IBC)

#### AASHTO LRFD (3rd Edition) & Korean Bridge Design Standards

- Interpretation of LRFD required new document
  - CCE produced many Technical Notes
- Design Manual produced by SCJV



Cable Stayed Bridge Design Check

- 1480m long with 800m main span
- 33.4m wide steel orthotropic deck
- Pylon reinforced concrete hollow section in diamond configuration
- Design tools TDV RM2000, Oasys GSA, LARSA
- Fast track design & check 12 weeks to start of piling
- Interaction with the Designer agree loads before detailing re-bar
- Wind buffeting analysis, response spectrum seismic analysis



Approach Bridge Design Check

- 145m long spans by balanced cantilever construction
- Built in pier tops no bearings apart from end spans
- Design tools LARSA, stage construction & time dependent effects
- REPUTE non-linear analysis of pile groups in multiple soil strata
- Camber curves checked for casting yard segment alignment
- Sub-structure certified for construction before deck checked
- Low Level Viaduct Design Check
  - 50m spans built by the span-by-span method
  - pre-tensioned 1400 tonne units erected by floating crane
  - Majority of sub-structure on pile bents
  - Represented the majority of the crossing



**Temporary Works** 

- Major Temporary Works (MTW)
  - 2km long temporary jetty
  - temporary back span piers for the CSB
  - temporary struts to prop the inclined pylon legs
  - self-launching overhead gantry for the viaduct
- Temporary Works (TW)
- Method Statements (MS)
- Independent design check for MTW's
- Independent design review for TW's and MS's



**Technical Reports for Review** 

- Probabilistic Seismic Hazard Assessment
- Oceanographic Investigations
- Ground Investigations
- Pile Load Tests
- Wind Tunnel Testing
- Ship Impact Protection Test Programme and Results
- Scour Test Report



- 16,700 drawings reviewed
- 140 'Design' and 'For Construction' check certificates issued
- 149 review certificates issued
- 40 technical notes issued



- Independent professional verification of design
- Wide ranging international input to design process
- Co-location advantageous
- Fast-track' partial certification



# CH2MHILL。 Incheon Bridge Project

### ASCE Structural Engineering Conference - Iowa 10 November 2014



Andrew Yeoward – Global Director of Bridge Engineering, CH2M HILL