


## <section-header><list-item><list-item><list-item><list-item>




### **ODOT Standard Specifications** 00512.49 Scheduling and Restrictions

Approval to proceed with the construction of subsequent shafts, before receiving approval of the first shaft will be based on the Engineer's observations of the Contractor's workmanship during construction of the first shaft and the Engineer's review and assessment of the following:

- The Contractor's conformance with the approved shaft installation plan.
- The Contractor's daily reports and Inspector's daily logs of excavation, rebar, and concrete placement.
- The concrete placement logs and volume curves.








### ODOT Standard Specifications 00512.49 Scheduling and Restrictions

- Do not proceed with the third drilled shaft until the final CSL test results from the first drilled shaft has been received and reviewed and the shaft accepted, in writing, by the Engineer.
- After the first drilled shaft on the Project has been accepted, make no significant changes in construction methods, equipment, or materials used to construct subsequent shafts, unless otherwise approved.











# <section-header><section-header><section-header><text><text><text><text>





### **Integrity Tests**


- The purpose of post-construction integrity testing is quality assurance of concrete placement.
- Most tests used for this purpose have no permanent effect on a drilled shaft and are therefore referred to as "non-destructive tests", or NDT.
- NDT results are used in "nondestructive evaluation", or NDE, in combination with construction observations, inspection records and other quality control assurance measures to assess shaft acceptance.
- NDE provides a tool for ensuring the as-built foundation satisfies the construction specifications and will perform as assumed in the design.





































## **Integrity Test Results**

If an anomaly is detected, the Engineer will determine course of action which may include:

- Additional CSL testing or tomography
- Excavation around shaft to expose defect
- Core drilling
- Down-hole cameras




Whatever the course of action is, the Engineer will want to review all of the shaft construction records to try and determine what caused the problem.






### November 2021























Reinforcing Cage (Construction & Placement)
Yes No No NA 25. Is the rebar the proper grade steel, correct sizes and correct configurations as shown in the project plans a dowings?
Yes No No A 26. Is the rebar properly tied in accordance with Section 00530.41(b)?
Yes No NA 27. Are the proper number of Crosshole Sonic Log (CSL) tubes furnished and installed according to the project
Yes No Na 28. Does the Contractor have the proper number and type of spacers for the steel cage in accordance with th Driled Shaft Installation Plan and Section 00512:45(d)?
Yes No NA 29. If the steel cage was spliced, was it done in accordance with the details shown on the contract plans?
Yes No NA 30. Is the steel cage adequately secured to maintain vertical tolerance during concrete placement operations and 00512.47/eIIP
Concrete Operations
Ves No NA 31. Prior to concrete placement, has the slumy (both manufactured and natural) been tested in accordance w 00512.43(a)?
Yes No NA 32. Frequired, was the casing removed in accordance with Section 00512.47(e)?
Yes No NA 33. Does the Contractor's tremie meet the requirements of Section 00512.47(a)?
Yes No NA 34. Was the discharge end of the tremie maintained in the concrete mass with proper concrete head above it (00512.47/c)/2
Ves No Na 35. For shafts with non-contact splices, have the cold joints been properly cleaned and roughened in accords Section 00512.47(a)?
Yes No NA 36. For shafts without non-contact splices, did the Contractor overflow the shaft until good concrete flowed a of the excursion 00512.47(30)?
Yes No NA 37. Have the Concrete Placement and Concrete Volume logs been completed?
Yes □ No □ NA 38. Were the concrete acceptance tests performed as required?
Yes No. No. NA 39. Were the Crosshole Sonic Log (CSL) tubes filed with water and capped in accordance to Section 00512.46
Post Installation
Yes No NA 40. Is all casing removed to the proper elevations in accordance with 00512.47(e)?
Yes No NA 41. Is the concrete being cured in accordance with Section 00540.517
Yes No NA 42. Has all Crosshole Sonic Log (CSL) Testing been completed in accordance with Section 0051248?
Yes No NA 43. Is the shaft within the allowable construction tolerances (00512.42)?
Yes No NA 44. Has the Contractor completed the Drilled Shaft Inspection Report (00512.40)c)/7
Yes No NA 45. Has the Inspector completed the Drilled Shaft Inspection Report (00512.40(c))?

## Measurement Standard Specifications 00512.80 Measurement (f) Crosshole Sonic Log Test

) Crosshole Sonic Log Test Access Tubes CSL access tubes will be measured on the length basis of the number of tubes installed in the shafts. Grout used to fill the access tubes after the completion of CSL testing will not be measured

(g) Crosshole Sonic Log Tests CSL tests will be measured on the unit basis for each CSL test completed, reported, and accepted. No separate measurement will be made for CSL tests performed at the Contractor's option.

MATERIALS &

	ress what the pay items are, the unit of work is included with each pay item.	
<b>Pay Item</b> (f) CSL Test Access Tubes (g) CSL Tests	Unit of Measurement Foot Each	
<ul> <li>Item (f) includes filling the tube testing.</li> </ul>	es with grout after completion of CSL	
<ul> <li>Item (g) includes mobilization of all CSL testing equipment and personnel to and from the site, all CSL testing, interpretation, analysis, electronic data, and final report for each tested and accepted shaft.</li> </ul>		