



PRESTRESSED CONCRETE BENT CAPS

Christopher Miller, P.E.



October 2017

1 Conventionally Reinforced, Precast Bent Caps	3
2 Prestressed, Precast Bent Caps	4
3 Completed Projects	5-11
4 Prestressed Standard	12-13
5 Ongoing Research	14
6 Going Forward	15

Conventionally Reinforced, Precast Bent Caps

Better concrete quality

M


Faster construction

- Same advantages as conventionally reinforced, precast caps
- Prestressing provides enhanced crack control



Completed Projects

- 1. LP 1604, Bexar Co
- 2. FM 973, Travis Co
- 3. Pecos River Bridge, Crane Co
- 4. Fischer Store Road, Hays Co



LP 1604 Bexar County, San Antonio, TX

- 36 Bents Total (18 NB, 18 SB)
- Identical Length and Column Spacing



FM 973 over Colorado River, Travis Co



Pecos River Bridge

- Remote site location:
 - No concrete batch plants nearby
 - Precast a number of different concrete members, including:
 - Prestressed Abutments and Precast Approach Slabs

Fischer Store Road

Original Bridge washed out from major flood event




Fischer Store Road

Emergency Replacement Project w/ Short Construction Timeline



Fischer Store Road


Demolition/New Construction complete in approximately 80 days



Prestressed, Precast Bent Cap Standard

- Released April 2017
- Intended as an alternate for standard bridge interior bent standards
- Include standard in plan sets using standard designed interior bents supported on <u>round columns</u>
- Applies to bridges with following beam types:
 - TxGirders
 - X-Beams
 - Box Beams
 - Decked Slab Beams
 - Slab Beams
- No adjustments to quantities required
- No Special Specifications

Prestressed, Precast Bent Cap Standard



Ongoing Research: 0-6863

 Full scale tests analyzing performance at varying service and strength load levels



Implementation of research project 0-6863 findings

- Update Standards
 - Refinement of reinforcing details
 - Addition of voids to reduce shipping weight
 - Revised connection details for easier constructability

 Increase awareness and use of prestressed, precast standards across the state

- Fabricator:
 - Bexar Concrete Works
- Contractor:
 - Texas Sterling Construction Co. LP 1604
 - Lane Construction FM 973
 - Relmco Inc.- Pecos River Bridge
 - Dan Williams Co Fischer Store Rd
- Research Team
 - Texas A&M and TTI

Questions?

Christopher Miller, EIT, MSE Bridge Division 512-416-2202 | *christopher.miller@txdot.gov*

Copyright 2014 • Texas Department of Transportation • All Rights Reserved

Entities or individuals that copy and present state agency information must identify the source of the content, including the date the content was copied. Entities or individuals that copy and present state agency information on their websites must accompany that information with a statement that neither the entity or individual nor the information, as it is presented on its website, is endorsed by the State of Texas or any state agency. To protect the intellectual property of state agency whose protected information must reflect the copyright, trademark, service mark, or other intellectual property rights of the state agency whose protected information is being used by the entity or individual. Entities or individuals may not copy, reproduce, distribute, publish, or transmit, in any way this content for commercial purposes. This presentation is distributed without profit and is being made available solely for educational purposes. The use of any copyrighted material included in this presentation is intended to be a 'fair use' of such material as provided for in Title 17 U.S.C. Section 107 of the U.S. Copyright Law.