The Pennsylvania State University NECA Student Chapter









2015 Green Energy Challenge

Our Team



Nicholas Kolesar

Project Manager, Energy Analyst



Finding a Client: The Pennsylvania State University







24 Campuses 8th Largest Employer in PA



Finding a Client: Henning Building



Client

Primary Use: Research Year Built: 1969 Gross Square Footage: 59,000 Site EUI: 363 kBtu/ft² Projected Renovations: 2020



Project Goals

Safety

Economic Feasibility

Business Development


Student Education








Project Scope



LED Lighting Retrofit with Vacancy Sensors



Microgrid with Solar PV Array




Lighting




Nicholas Kolesar


Project Manager, Energy Analyst



Current Lighting








Lighting Retrofit

Retrofit Kits



Client

LED Replacements




PennState


LED Technology



From Lithonia's Catalog



Elum Tools Rendering of Office





		ENERGY AND COST SAVINGS OF LIGHTING RETROFIT							
	Scheduled Hours (Weekly)	Existing Fixture	Number of Fixtures	Wattage	Existing Consumption (kWh)	Retrofit Fixture	Number of Fixtures	Wattage	Retrofit Consumption (kWh)
	60	2X4 Parabolic 3L	233	96	1342	2RTL4R	233	38.52	539
	60	2X4 Parabolic Industrial	342	96	1970	2TLED	342	50	1026
	60	2X2 Parabolic U-tube	9	93	50	2RTL2R	9	40.08	22
	60	2X2 Parabolic 3L	40	84	202	2RTL2R	40	40.08	96
ĸ	60	1X4 Parabolic 2L	76	64	292	RTL	76	40.68	186
INTERIOR	168	1X4 Industrial 2L	159	64	1710	TLX4	159	46	1229
Ξ	60	Display	3	80	14	TL4	3	30	5
	60	1x1 Square Fixture	2	20	2	RT5D LED	2	41	5
	60	Luminous Ceiling	2	480	58	Cubic-A2	2	137	16
	168	Stairwell Fixture	18	64	194	TLX4	18	46	139
	168	Exit Signs	13	14	31	EDG	13	2.5	5
R	91	Lamp Post	1	100	9	Louis Poulsen KIPP 416 Luminair models	1	100	9
EXTERIOR	91	Wall Pack	3	100	27	LED Mini Wall Sconce	3	9	2
E	91	Square	3	20	5	CREE LED Light Bulbs	3	11	3
		Total Number of Fixtures:	904	Total kWh:	5906	Total Number of Fixtures:	904	Total kWh:	3282
				Annually:	289374			Annually:	160842
				Cost:	\$ 72,343.60			Cost:	\$ 40,210.40

Annual Savings: 129,000 kWh \$32,000



Controls




Figure prepared by National Renewable Energy Laboratory and the U.S. Department of Energy

FRIDAY NIGHT LIGHTS OUT!

PennState

Energy

Client

Lighting

Microgrid

Controls



- *by User Automatically off*
- after 15 minutes




Figure prepared by National Renewable Energy Laboratory and the U.S. Department of Energy



Microgrid




Nicholas Kolesar


Project Manager, Energy Analyst




Critical Load identified as 46.1 kW








Components








Components



Client







ABB

Der Litte 2 : : :

Components



Client



28 EnerSys Genesis Pure Lead XE95 0790-6001 (20.9 kWh) \$10,775



Microgrid Breakdown

Client

Description	Cost] 7 ⁹
Racking	\$11,850	22%
PV Panels	\$79,875	
Inverter	\$19,150	6%
Batteries	\$10,775	1 = 0/
Other Costs	\$34,350	15%
Project Total	\$156,000	

Energy

Racking PV Panels Inverters Batteries Other Costs

Lighting

Microgrid

50%

Construction

Outreach

PennState

Construction Management



Nicholas Kolesar

Project Manager, Energy Analyst



Main Focus for PSU

- Student & Faculty Safety
- Summer
- Resilient power for animal lab spaces
- Payback Period 10 years







Schedule



vity ID	Activity Name	Original Start	Finish	Qtr 2, 2015				Qtr 3, 2015		
		Duration			Apr	May	Jun	Jul	Aug	Sep
PSU Hen	nning Renovation	94 23-Mar-1	5 31-Jul-15						31-Jul-15, PSU Henning Renovation	n l
🔲 A1000	Notice to Proceed	0 23-Mar-1	5	Notic	ce to Proceed, 23-Mar-15					
💼 A1020	Submittals and Shop Drawings	15 23-Mar-1	5 10-Apr-15	5	Submittals and Shop D	rawings				
A1025	Obtain Permits	10 06-Apr-1	5 17-Apr-15	5	Cobtain Permits					
A1030	Penn State Submittal Review and Aprroval	20 13-Apr-1	5 08-May-1	5		Penn State Submittal Rev	p			
A1040	Lighting Retrofit Procurement	5 11-May-1	5 15-May-1	5		Lighting Retrofit F	rocurement			
A1045	Lighting Mobilization	2 18-May-1	5 19-May-1	5		Lighting Mob	lization			
A1050	Ground Floor Installation	6 20-May-1	5 27-May-1	5		Gr	und Floor Installation			
🔲 A1060	First Floor Installation	9 28-May-1	5 09-Jun-15	5			First Floor In	Istallation		
🔲 A1070	Second Floor Installation	9 10-Jun-1	5 22-Jun-15	5			-	Second Floor Installation		
A1080	Third Floor Installation	8 23-Jun-1	5 02-Jul-15	1			[Third Floor Installation		
👝 A1090	Lighting Retrofit Testing and Commisioning	5 03-Jul-15	09-Jul-15					Lighting Retrofit	Testing d Commisioning	
💼 A1095	Lighting Demobilization	2 10-Jul-15	13-Jul-15					Lighting De	mobilization	
🔲 A1100	Photovoltaic Procurement	5 22-Jun-1	5 26-Jun-15	5			· · · ·	Itaic Procurement		
💼 A1105	PV Array Mobilization	2 29-Jun-1	5 30-Jun-15	5				PV Arra, Duces		
🔲 A1110	Ballast System Installation & Inverter Layout	3 01-Jul-15	03-Jul-15					Ballast Syster Installati	on & Inverter Layout	
🔲 A1120	Attaching Panels to Ballast System	4 06-Jul-15	09-Jul-15					Attaching Parts	to Ballast System	
🔲 A1130	Wire Panels Together	2 10-Jul-15	13-Jul-15					🖵 Wire Pane	gether	
🔲 A1140	Wire Inverters	2 14-Jul-15	15-Jul-15					Wire Inv	erters	
🔲 A1145	Install Battery Bank	10 02-Jul-15	15-Jul-15					Install Ba	attery Bank	
🔲 A1150	Tie PV Array to Building System and Battery Ban	4 16-Jul-15	21-Jul-15						ie PV Array to Buyling System and Battery Ba	nk
💼 A1160	Testing and Commisioning	3 22-Jul-15	24-Jul-15						Testing and Computing	
A1165	Substantial Completion	0	24-Jul-15						Substantial Completio	
A1170	PV Array Demobilization and Punchlist	4 27-Jul-15	30-Jul-15						PV Array Demobility tion and Punchli	st
A1180	Project Completion	0	31-Jul-15	- I I					 Project Completion; 	
		1				weeks				<u>.</u>

PennState

Pre


Client


Microgrid


Construction

Outreach

Sequencing








Outreach



Nicholas Kolesar

Project Manager, Energy Analyst



East Halls Freshman Dormitories



14 Residence Halls and Johnston Commons

4, 000 Freshman Residents

117 MWh/week



Tabling and Student Interaction







ł	Reduce your De	100	2015
1.	Turn off your lights when you leave the room.	6.	Purchase Energy Star label appliances.
2.	Unplug any chargers or appliances when not in use.	7.	Get outside and enjoy the fresh air!
3.	Take the stairs instead of the elevator.	8.	Alter your appliance settings to save energy or use a power strip.
4.	Use cold water doing laundry and skip the dryer when possible.	9.	Use your windows and curtains to control your room temperature.
5.	Save hot water by taking a shorter shower.	10.	Double your impact; convince a friend to do the same!
Ŀ	Reduce your usage as a building http://buildingdashboard.net/psu/#/		
	Remember, the competition er	nds April	12, so start saving now!



Energy


Tabling and Community Interaction








Project Summary



LED Lighting Retrofit with Vacancy Sensors



Microgrid with Solar PV Array

Client

Energy

PennState



Microgrid

Construction

Outreach

Lighting

Special Thanks

NECA Penn-Del-Jersey Chapter Faculty and Advisors Penn State NECA Alumni Members of the PSU NECA Student Chapter

